

ENGINEERS NORTHWEST, INC. P.S.

9725 THIRD AVENUE N.E., SUITE #207
SEATTLE, WASHINGTON 98115

PHONE - (206) 525-7560 / FAX - (206) 522-6698

LETTER OF TRANSMITTAL

TO: MG2 Architecture
1101 Second Ave, Ste 100
Seattle, WA 98101

DATE: February 25, 2021

JOB NO: 16038004

ATTENTION: Travis Morton

RE: Costco Headquarters- Building 5

WE ARE SENDING YOU ☒ Attached ☐ Under separate cover via COURIER the following items:

☒ Shop drawings

☐ Prints

☐ Plans

☐ Samples

☐ Specifications

☐ Copy of letter

☐ Change order

☐ _____

COPIES	DATE	NO.	DESCRIPTION
E	02/23/21		Submittal No. 095423.02 - Linear Delegated Design Calc's

THESE ARE TRANSMITTED as checked below:

☐ For approval

☒ Reviewed as loads only

☐ Resubmit _____ copies for approval

☒ For your use

☐ Reviewed as noted

☐ Submit _____ copies for distribution

☐ As requested

☐ Returned for corrections

☐ Return _____ corrected prints

☐ For review and comment

☐ REVISE AND RESUBMIT

☐ No Action Taken

☐ PRINTS RETURNED AFTER LOAN TO US

**** If enclosures are not as noted, kindly notify us at once. ****

REMARKS:

COPY TO: FILE

SIGNED: _____

Cesar A. Ruiz

URGENT ☐

Submittal CSI No.: 09510

SUBMITTAL TRANSMITTAL

Submittal No. 095423.02 - DIVISION 9 - FINISHES - Submittal Material

Project: US Home Garage Corp Campus , WA

Date: 02.22.2021

BLDG 4: 730 Lake Drive BLDG 5: 755 Lake
Drive

MG2 #: 15-0035-03

CW#: CW17-1048-03

Owner: Costco Wholesale

Contractor: Ferguson Construction

☐ **Shop Drawings**

☐ **Project Data**

☐ **Samples**

Submittal Description: Linear Metal Ceilings Delegated Design Calc's

Number of Sheets: 5 sets (see fwd log)

☐ **Catalogs / Books**

Date: 02.22.2021

Supplier / Subcontractor / Manufacturer:

Comments / Questions:

-

Submittal Action

- ☐ Not Issued
- ☐ Under Review
- ☐ Approved
- ☐ Conforms to Design Concept
- ☐ Conforms to Design Concept with Revisions as Shown
- ☐ Non-Conforming, Revise & Re-Submit
- ☐ No Action Required - Submittal not required; retained for project file

Reviewer Comments:

Attachments:

Reviewed By:

Date:



Costco Garage

09 54 23 Linear Metal Ceilings: Delegated Design Supplemental Submittal

ENGINEERS NORTHWEST, INC. is not responsible
for this design or performance of this product.

ENGINEERS NORTHWEST, INC. has reviewed the
applied loads only for conformance to the construction
documents and has reviewed absolutely nothing else

02-25-2021

Date

CAR

By



REVIEWED BY John B.
SUBMITTAL # 095423.02 DATE: 2/22/2021
SUB/SUPPLIER: PCI
PROJECT: CC5

- ☒ REVIEWED
☐ REVIEWED AS NOTED
☐ REVISE & RESUBMIT

FERGUSON CONSTRUCTION'S REVIEW OF THESE DOCUMENTS DOES
NOT RELIEVE SUB/SUPPLIER OF ITS RESPONSIBILITY FOR:

- 1) FIELD VERIFICATION OF ALL DIMENSIONS AND JOB-SITE CONDITIONS
AND REQUIREMENTS
- 2) COMPLIANCE WITH CONTRACT DOCUMENTS AND ALL APPLICABLE
STATE AND CITY ORDINANCES AND REQUIREMENTS
- 3) COORDINATION WITH ALL TRADES.

Material Submittal

Submitted: 02/22/2021



MG2

1101 Second Ave, Ste 100
Seattle, WA 98101

Ferguson Construction, Inc.

13810 SE Eastgate Way, Suite 110
Bellevue, WA 98005

Performance Contracting, Inc.

16220 Woodinville Redmond Rd NE
Woodinville, WA 98072
Office: 425-488-7171
Fax: 425-488-4744



SPEC SECTION NO.	09 54 23
SECTION DESCRIPTION	Linear Metal Ceilings
PROJECT	Costco Garage
PCI JOB #	20-06808

16220 Woodinville Redmond Rd NE, Woodinville, WA 98072

P: (425) 488-7171

PARAGRAPH	DESCRIPTION	MANUFACTURER	REMARKS	PAGE NO.
2.1.A	Delegated Design			4
2.3.D	Seismic/Wind Uplift Compression Struts	Cemco, Scafco, & Unistrut		7
2.4	Accessory Materials (Fasteners)	Hilti, Simpson, Pro-Twist, & I-Lag		22
	Delegated Design Calculations			62

COSTCO GARAGE INTERIOR ACT CEILING
& EXTERIOR METAL PANEL CEILING
ISSAQUAH, WASHINGTON

- GENERAL
1. VERIFY DESIGN CRITERIA (BELOW) AND DIMENSIONS PER DRAWINGS.
 2. DEVCO ENGINEERING, INC'S SCOPE OF WORK IS LIMITED TO THOSE ITEMS SHOWN ON OUR SEALED DRAWINGS. DESIGN OF ALL OTHER ITEMS IS BY OTHERS.

DESIGN CRITERIA
CEILING DEAD LOAD: 4 PSF MAX CEILING WEIGHT (ACT)
4 PSF MAX CEILING WEIGHT (METAL PANEL)

CEILING LIVE LOAD: 0 (NON ACCESSIBLE)
SEISMIC LOAD: 2015 IBC
WIND V = 110MPH, EXP. = B
EXTERIOR CEILING WIND PRESSURE = 17.1 PSF
RISK CATEGORY: II
Sds =0.634, Ip = 1.0, ap = 1.0, Rp = 2.5

DEFLECTION LIMIT:
L/360 ACT
L/240 METAL PANEL

- MATERIALS
1. STUD TRACK AND MISC. SHAPES TO BE MANUFACTURED FROM STEEL MEETING THE REQUIREMENTS OF ASTM A653, SS GRADE 33 FOR 43-MIL AND LIGHTER PRODUCTS AND ASTM A653, SS GRADE 50 FOR 54-MIL AND HEAVIER.
 2. DESIGN BASED ON SECTION PROPERTIES FROM ICC ESR 3064P (SSMA). OTHER MANUFACTURES ARE ACCEPTABLE PROVIDING PROVISION 1 ABOVE IS MET AND SECTION PROPERTIES MEET OR EXCEED THE ABOVE LISTED ICC-ES.
 3. PROVIDE PERIMETER SUPPORTING CLOSURE ANGLES PER ASCE 7-10 13.5.6.2.2. INSTALL ALL CEILINGS IN ACCORDANCE WITH ASCE 7-10 13.5.6.2. , ASTM C635 / C636, & ASTM E580.
 4. WIRE TO BE GALVANIZED SOFT ANNEALED MILD STEEL WIRE AS DEFINED IN ASTM A641. USE A MINIMUM OF THREE TWISTS WITHIN 1/2" LENGTH AT ENDS OF HANGER WIRE.
 5. SCREWS USED IN DESIGN MEET THE REQUIREMENTS OF SECTION E4 OF THE 2012 EDITION OF THE AISI "NORTH AMERICAN SPECIFICATION FOR THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS" FOR SCREW CONNECTIONS.
 6. HILTI KWIK HUS-EZ (WH-EZ) CONCRETE SCREW ANCHOR, ICC ESR-3027 IN CONCRETE, ICC ESR-3056 IN MASONRY : DIAMETER AND EMBEDMENT LENGTH PER DRAWINGS. EDGE DISTANCE AND O.C. SPACING PER ICC ESR.
 7. SIMPSON TITEN HD CONCRETE SCREW ANCHOR, ICC ESR-2713 IN CONCRETE, ICC ESR-1056 IN MASONRY : DIAMETER AND EMBEDMENT LENGTH PER DRAWINGS. EDGE DISTANCE AND O.C. SPACING PER ICC ESR.
 8. LVF-RAMSET, ICC ESR-1799:
P.T. SLAB IN NORMAL WEIGHT CONCRETE: 0.150"Ø x MIN. 3/4" EMBED, SPC 78. MIN. 3.5" EDGE DISTANCE, SPACING PER SECTIONS AND DETAILS, BUT NOT LESS THAN 5" O.C.

IN CONCRETE OVER METAL DECK: 0.150"Ø x MIN. 1 1/8" EMBED, SPC 114. MIN. 3.5" EDGE DISTANCE, SPACING PER SECTIONS AND DETAILS, BUT NOT LESS THAN 5" O.C.

- MAXIMUM SPACING OF L.V.F. SHOWN ON THE DRAWINGS. IN ADDITION, PLACE ONE L.V.F. NO MORE THAN 6" FROM ANY TRACK TERMINATION.
9. LVF- HILTI, ICC-ESR-2184:
P.T. SLAB IN NORMAL WEIGHT CONCRETE: 0.177"Ø x MIN. 7/8" EMBED, X-CX ALH 27. MIN. 3.5" EDGE DISTANCE, SPACING PER SECTIONS AND DETAILS, BUT NOT LESS THAN 5" O.C.

IN CONCRETE OVER METAL DECK: 0.177"Ø x MIN 1" EMBED, X-CX ALH 32. MIN. 3.5" EDGE DISTANCE, SPACING PER SECTIONS AND DETAILS, BUT NOT LESS THAN 5" O.C.

MAXIMUM SPACING OF L.V.F. SHOWN ON THE DRAWINGS. IN ADDITION, PLACE ONE L.V.F. NO MORE THAN 6" FROM ANY TRACK TERMINATION.

SHEET INDEX			
SF 6.00	COVER SHEET		
SF 6.40	INT. ACT FRAMING DETAILS		
SF 6.60	EXT. ACT FRAMING DETAILS		



DRAWING STATUS:	DATE	REVISION	DATE
<input type="checkbox"/> PRELIMINARY			
<input checked="" type="checkbox"/> SUBMITTED	02/08/21		
<input type="checkbox"/> BID SET			
<input type="checkbox"/> PERMIT SET			
<input type="checkbox"/> CONST. SET			



Corvallis
Oregon

devco
engineering inc.

(541) 757-9991

245 NE CENTER, P.O. BOX 1211
CORVALLIS, OR 97339

WWW.DEVCOENGINEERING.COM

© COPYRIGHT 2021
DEVCO ENGINEERING, INC.

ALL RIGHTS RESERVED.

PROJECT:

COSTCO GARAGE INTERIOR ACT CEILING
+ EXTERIOR METAL PANEL CEILING

PROJECT LOCATION:

ISSAQUAH, WASHINGTON

CLIENT:

PCI

SHEET TITLE:

COVER SHEET

JOB NO.

20-086

DRAWN BY:

DEVCO

DRAWING:


SF 6.00

This shop Drawing (product data, sample, etc.) has been prepared by Performance Contracting, Inc. in its capacity as a contractor and not as a licensed design professional. It is submitted in reliance on the accuracy of the information contained in the Contract Documents is in accordance with applicable laws, statutes, ordinances, building codes, rules and regulations and/or standards. Any comparison of Contract Documents, field measurements and observation of site conditions by Performance Contracting, Inc. has been for the sole purpose of facilitation construction and not for the purpose of discovering errors, omissions or inconsistencies with the Contract Documents.


INTERIOR ACT CEILING DETAILS

1. SEISMIC RIGID BRACING & SPLAY DETAIL PER 2 & 5/SF6.40 MAY BE USED ON EXTERIOR & INTERIOR SUSPENDED CEILINGS AS REQUIRED.
2. INTERIOR DESIGN CRITERIA SEE GENERAL NOTE SHEET SF6.00.


This shop Drawing (product data, sample, etc.) has been prepared by Performance Contracting, Inc. in its capacity as a contractor and not as a licensed design professional. It is submitted in reliance on the accuracy of the information contained in the Contract Documents in accordance with applicable laws, statutes, ordinances, building codes, rules and regulations and/or standards. Any comparison of Contract Documents, field measurements and observation of site conditions by Performance Contracting, Inc. has been for the sole purpose of facilitation construction and not for the purpose of discovering errors, omissions or inconsistencies with the Contract Documents.



9C PERIMETER DETAIL - UNATTACHED WALL
SCALE: N.T.S.




9B PERIMETER DETAIL - ATTACHED WALL OPTION 2
SCALE: N.T.S.




9A PERIMETER DETAIL - ATTACHED WALL OPTION 1
SCALE: N.T.S.

9 PERIMETER DETAILS
SCALE: N.T.S.


TRAPEZE MEMBER	SPAN
SINGLE 150U50-54 CRC (1½" 16GA)	4'-0"
BACK TO BACK 150U50-54 CRC (1½" 16GA)	4'-6"
UNISTRUT P1000	8'-0"




11 INTERIOR MAIN TEE SUPPORT DETAIL
SCALE: 1\"/>




10 INTERIOR MAIN TEE SUPPORT DETAIL
SCALE: 1\"/>




8 CONNECTION DETAIL @ P.T. SLAB
SCALE: N.T.S.




7 CONNECTION DETAIL @ CONC. DECK
SCALE: N.T.S.




6 BRACE CONNECTION @ CONC. DECK
SCALE: N.T.S.




5 RIGID BRACE DETAIL
SCALE: 3\"/>



4C @ P.T. SLAB
SCALE: 1\"/>




4B @ METAL ROOK DECKING
SCALE: 1\"/>




4A @ CONCRETE OVER METAL DECK
SCALE: 1\"/>


4 SPLAY WIRE CONNECTIONS
SCALE: N.T.S.



3C @ P.T. SLAB
SCALE: 1\"/>




3B @ METAL ROOK DECKING
SCALE: 1\"/>



3A @ CONCRETE OVER METAL DECK
SCALE: 1\"/>


3 INTERIOR WIRE HANGER CONNECTIONS
SCALE: N.T.S.



NOTES:
1. INSTALL SPLAY WIRES @ MAX 12'-0\"/>

2 SPLAY WIRE & COMPRESSION POST DETAIL
SCALE: N.T.S.

NOTES:
1. FRAMING & INSTALLATION TO COMPLY WITH MANUFACTURER ICC REPORT.
2. SEISMIC SPLAY WIRES & COMPRESSION POSTS ARE REQ'D FOR CEILING AREA GREATER THAN 1000 SQUARE FEET, BRACES PER DETAIL 2/6.40. CEILINGS SURROUNDED ON ALL (4) SIDES BY FULL HEIGHT WALLS WITH A CEILING AREA OF 1000 SQUARE FEET OR LESS ARE EXEMPT FROM SEISMIC BRACING REQ'S.
3. LIGHT FIXTURE SUPPORTS PER ASTM E-580.



1 INTERIOR ACT SUSPENDED CEILING GRID SYSTEM
SCALE: N.T.S.



DRAWING STATUS:	DATE:	REVISION:
PRELIMINARY		
SUBMITTED	02/08/21	
BID SET		
PERMIT SET		
CONST. SET		




Corvallis
Oregon
devco
engineering inc.
245 NE CENTER, P.O. BOX 1211
CORVALLIS, OR 97339
WWW.DEVCOENGINEERING.COM
© COPYRIGHT 2021
DEVCO ENGINEERING, INC.
ALL RIGHTS RESERVED

PROJECT: COSTCO GARAGE INTERIOR ACT CEILING
+ EXTERIOR METAL PANEL CEILING
PROJECT LOCATION: ISSAQUAH, WASHINGTON
CLIENT: PCI

SHEET TITLE:
INT. ACT FRAMING DETAILS


JOB NO. 20-086
DRAWN BY: DEVCO
DRAWING:
SF 6.40

This shop Drawing (product data, sample, etc.) has been prepared by Performance Contracting, Inc. in its capacity as a contractor and not as a licensed design professional. It is submitted in reliance on the accuracy of the information contained in the Contract Documents. It is in accordance with applicable laws, statutes, ordinances, building codes, rules and regulations and/or standards. Any comparison of Contract Documents, field measurements and observation of site conditions by Performance Contracting, Inc. has been for the sole purpose of facilitation construction and not for the purpose of discovering errors, omissions or inconsistencies with the Contract Documents.




EXTERIOR METAL PANEL CEILING DETAILS


- SEISMIC RIGID BRACING & SPLAY DETAIL PER 2 & 5/SF6.40 MAY BE USED ON EXTERIOR & INTERIOR SUSPENDED CEILINGS AS REQUIRED.
- EXTERIOR DESIGN CRITERIA SEE GENERAL NOTE SHEET SF6.00.



DRAWING STATUS:	DATE:	REVISION:
<input type="checkbox"/> PRELIMINARY		
<input checked="" type="checkbox"/> SUBMITTED	02/08/21	
<input type="checkbox"/> BID SET		
<input type="checkbox"/> PERMIT SET		
<input type="checkbox"/> CONST. SET		




2B @ P.T. SLAB
SCALE: 1 1/2\" = 1'-0"




2A @ METAL DECK
SCALE: 1 1/2\" = 1'-0"

2 HANGER WIRE
TOP CONN. @ EXTERIOR
SCALE: 1 1/2\" = 1'-0"

NOTE:
SEISMIC SPLAY BRACING REQUIRED PER 2/6.40.
UPLIFT POST CAN BE USED AS COMPRESSION
POST IN SPLAY BRACING DETAIL.



1 UNIVERSAL CARRIER SPLICE @ EXTERIOR
SCALE: N.T.S.



PROJECT: COSTCO GARAGE INTERIOR ACT CEILING
+ EXTERIOR METAL PANEL CEILING
PROJECT LOCATION: ISSAQUAH, WASHINGTON
CLIENT: PCI

SHEET TITLE:
EXT. ACT FRAMING DETAILS

JOB NO. 20-086
DRAWN BY: DEVCO
DRAWING:
SF 6.60



Expanding Your Solutions

Corporate Headquarters

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.775.2362
Fax: 626.330.7598
www.cemcosteel.com

Manufacturing Facilities

City of Industry, CA
Denver, CO
Ft. Worth, TX
Pittsburg, CA

2.3.D Seismic/Wind Uplift Compression Struts

1001-A Pittsburgh Antioch Hwy
Pittsburg, CA 94565
Phone: 800.775.2362
Fax: 626.330.7598
www.cemcoengineering.com

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.416.2278
Fax: 626.249.5004

362S200-43 C-STUDS 43 MIL. (18 GA. STRUCTURAL)

Geometric Properties

362S200-43 "S" structural load-bearing studs are produced from hot-dipped galvanized steel in standard CP60 coating. CP90 is available upon special request, and may require up-charges and extended lead times.

Physical Properties

Model No.	Design Thickness (in)	Minimum Thickness (in)	Yield (ksi)	Coating ^{3,4}	Web Depth (in)	Flange Size (in)	Lip (in)
362S200-43	0.0451	0.0428	33	CP60	3-5/8	2	5/8

Notes:

- Uncoated steel thickness. Thickness is for carbon sheet steel.
- Minimum thickness represents 95% of the design thickness and is the minimum acceptable thickness.
- Per ASTM C955 & A1003, Table 1.
- CP90 available upon request. Will require extended lead time and upcharge.

Color Code (painted on ends): 43-mil: Yellow

ASTM & Code Standards:

- ASTM A653/A653M, A924/A924M, A1003/1003, C955 & C1007
- ICC-ES & SFIA Code Compliance Certification Program
- ICC ESR-3016
- ATI CCRR-0224
- IBC: 2012, 2015, 2018
- CBC: 2013, 2016
- AISI: S100-07, S100-12, S100-16, S200-12, S240-15



LEED v4 for Building and Design Construction

- MR Prerequisite: Construction and Demolition Waste Management Planning.
- MR Credit: Construction and Demolition Waste Management.
- MR Credit: Building Product Disclosure and Optimization – Sourcing of Raw Materials, Option 2.
- MR Credit: Building Product Disclosure and Optimization – Environmental Product Declarations, Options 1 & 2.
- MR Credit: Building Product Disclosure and Optimization – Material Ingredients, Option 1.
- MR Credit: Building Life-Cycle Impact Reduction, Option 4.

CEMCO cold-formed steel framing products contain 30% to 37% recycled steel.

- Total Recycled Content: 36.9%
- Post-Consumer: 19.8%
- Pre-Consumer: 14.4%

CSI Division: 05.40.00 – Cold-Formed Metal Framing



Hole Detail

Standard Hole Centers are 24"	(Z) (in)	(Y) (in)
2-1/2" studs	2.000	0.750
3-1/2" to 14" studs	3.250	1.500

362S200-43 Section Properties

Design Thickness (in.)	Fy (ksi)	Gross ³					Effective Properties ²						Torsional Properties						Lu (in)
		Ix (in ⁴)	Sx (in ³)	Rx (in)	Iy (in ⁴)	Ry (in)	Ix (in ⁴)	Sx (in ³)	Ma (in-k)	Vag (lb)	Vanet (lb)	Mad (in-k)	Jx1000 (in ⁴)	Cw (in ⁶)	Xo (in)	m (in)	Ro (in)	β	
0.0451	33	0.836	0.461	1.474	0.227	0.767	0.836	0.427	8.43	1739	676	8.70	0.261	0.734	-1.729	1.024	2.398	0.480	53.5

Notes: 1. Web depth for track sections equals nominal depth plus 2 times the design thickness plus bend radius. 2. The values are for members with punch-outs. 3. Gross properties are based on the full, unreduced cross-section, away from web

punchouts. 4. Use the effective moment of inertia for deflection calculation. 5. Allowable moment is lesser of Ma and Mad. Distortional buckling is based on an assumed $K\phi = 0$. 6. These members are available un-punched only.

Check the updated list of Certified Production Facilities at Intertek's website at <http://www.intertek.com/building/sfia>



This technical information reflects the most current information available and supersedes any and all previous publications effective December 04, 2018.

12-04-18 AT



Expanding Your Solutions

Corporate Headquarters

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.775.2362
Fax: 626.330.7598
www.cemcosteel.com

Manufacturing

City of Industry, CA
Denver, CO
Ft. Worth, TX
Pittsburg, CA

2.3.D Seismic/Wind Uplift Compression Struts

1001-A Pittsburgh Antioch Hwy
Pittsburg, CA 94565
Phone: 800.775.2362
Fax: 626.330.7598
www.cemcoengineering.com

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.416.2278
Fax: 626.249.5004

362S162-33 C-STUDS 33 MIL. (20 GA. STRUCTURAL)

Geometric Properties

362S162-33 "S" structural load-bearing studs are produced from hot-dipped galvanized steel in standard CP60 coating. CP90 is available upon special request, and may require up-charges and extended lead times.

Physical Properties

Model No.	Design Thickness (in)	Minimum Thickness (in)	Yield (ksi)	Coating ^{3,4}	Web Depth (in)	Flange Size (in)	Lip (in)
362S162-33	0.0346	0.0329	33	CP60	3-5/8	1-5/8	1/2

Notes:

1. Uncoated steel thickness. Thickness is for carbon sheet steel.
2. Minimum thickness represents 95% of the design thickness and is the minimum acceptable thickness.
3. Per ASTM C955 & A1003, Table 1.
4. CP90 available upon request. Will require extended lead time and upcharge.

Color Code (painted on ends): 33-mil: White

ASTM & Code Standards:

- ASTM A653/A653M, A924/A924M, A1003/1003, C955 & C1007
- ICC-ES & SFIA Code Compliance Certification Program
- ICC ESR-3016
- ATI CCRR-0224
- IBC: 2012, 2015, 2018
- CBC: 2013, 2016
- AISI: S100-07, S100-12, S100-16, S200-12, S240-15



LEED v4 for Building and Design Construction

- MR Prerequisite: Construction and Demolition Waste Management Planning.
- MR Credit: Construction and Demolition Waste Management.
- MR Credit: Building Product Disclosure and Optimization – Sourcing of Raw Materials, Option 2.
- MR Credit: Building Product Disclosure and Optimization – Environmental Product Declarations, Options 1 & 2.
- MR Credit: Building Product Disclosure and Optimization – Material Ingredients, Option 1.
- MR Credit: Building Life-Cycle Impact Reduction, Option 4.

CEMCO cold-formed steel framing products contain 30% to 37% recycled steel.

- Total Recycled Content: 36.9%
- Post-Consumer: 19.8%
- Pre-Consumer: 14.4%

CSI Division: 05.40.00 – Cold-Formed Metal Framing



Hole Detail

Standard Hole Centers are 24"	(Z) (in)	(Y) (in)
2-1/2" studs	2.000	0.750
3-1/2" to 14" studs	3.250	1.500

362S162-33 Section Properties

Design Thickness (in.)	Fy (ksi)	Gross ³					Effective Properties ²						Torsional Properties							Lu (in)
		Ix (in ⁴)	Sx (in ³)	Rx (in)	Iy (in ⁴)	Ry (in)	Ix (in ⁴)	Sx (in ³)	Ma (in-k)	Vag (lb)	Vanet (lb)	Mad (in-k)	Jx1000 (in ⁴)	Cw (in ⁶)	Xo (in)	m (in)	Ro (in)	β		
0.0346	33	0.551	0.304	1.450	0.099	0.616	0.551	0.268	5.29	1024	521	5.43	0.105	0.297	-1.308	0.789	2.048	0.592	42.6	

Notes: 1. Web depth for track sections equals nominal depth plus 2 times the design thickness plus bend radius. 2. The values are for members with punch-outs. 3. Gross properties are based on the full, unreduced cross-section, away from web

punchouts. 4. Use the effective moment of inertia for deflection calculation. 5. Allowable moment is lesser of Ma and Mad. Distortional buckling is based on an assumed $K\phi = 0$. 6. These members are available un-punched only.

Check the updated list of Certified Production Facilities at Intertek's website at <http://www.intertek.com/building/sfia>



This technical information reflects the most current information available and supersedes any and all previous publications effective December 04, 2018.

12-04-18 AT

362S137-33 C-STUDS 33 MIL. (20 GA. STRUCTURAL)

Geometric Properties

362S137-33 "S" structural load-bearing studs are produced from hot-dipped galvanized steel in standard CP60 coating. CP90 is available upon special request, and may require up-charges and extended lead times.

Physical Properties

Model No.	Design Thickness (in)	Minimum Thickness (in)	Yield (ksi)	Coating ^{3,4}	Web Depth (in)	Flange Size (in)	Lip (in)
362S137-33	0.0346	0.0329	33	CP60	3-5/8	1-3/8	3/8

Notes:

1. Uncoated steel thickness. Thickness is for carbon sheet steel.
2. Minimum thickness represents 95% of the design thickness and is the minimum acceptable thickness.
3. Per ASTM C955 & A1003, Table 1.
4. CP90 available upon request. Will require extended lead time and upcharge.

Color Code (painted on ends): 33-mil: White

ASTM & Code Standards:

- ASTM A653/A653M, A924/A924M, A1003/1003, C955 & C1007
- ICC-ES & SFIA Code Compliance Certification Program
- ICC ESR-3016
- ATI CCRR-0224
- IBC: 2012, 2015, 2018
- CBC: 2013, 2016
- AISI: S100-07, S100-12, S100-16, S200-12, S240-15



LEED v4 for Building and Design Construction

- MR Prerequisite: Construction and Demolition Waste Management Planning.
- MR Credit: Construction and Demolition Waste Management.
- MR Credit: Building Product Disclosure and Optimization – Sourcing of Raw Materials, Option 2.
- MR Credit: Building Product Disclosure and Optimization – Environmental Product Declarations, Options 1 & 2.
- MR Credit: Building Product Disclosure and Optimization – Material Ingredients, Option 1.
- MR Credit: Building Life-Cycle Impact Reduction, Option 4.

CEMCO cold-formed steel framing products contain 30% to 37% recycled steel.

- Total Recycled Content: 36.9%
- Post-Consumer: 19.8%
- Pre-Consumer: 14.4%

CSI Division: 05.40.00 – Cold-Formed Metal Framing



Hole Detail

Standard Hole Centers are 24"	(Z) (in)	(Y) (in)
2-1/2" studs	2.000	0.750
3-1/2" to 14" studs	3.250	1.500

362S137-33 Section Properties

Design Thickness (in.)	Fy (ksi)	Gross ³					Effective Properties ²						Torsional Properties							Lu (in)
		Ix (in ⁴)	Sx (in ³)	Rx (in)	Iy (in ⁴)	Ry (in)	Ix (in ⁴)	Sx (in ³)	Ma (in-k)	Vag (lb)	Vanet (lb)	Mad (in-k)	Jx1000 (in ⁴)	Cw (in ⁶)	Xo (in)	m (in)	Ro (in)	β		
0.0346	33	0.479	0.264	1.424	0.059	0.501	0.479	0.232	4.59	1024	521	4.72	0.094	0.165	-1.003	0.615	1.813	0.694	34.7	

Notes: 1. Web depth for track sections equals nominal depth plus 2 times the design thickness plus bend radius. 2. The values are for members with punch-outs. 3. Gross properties are based on the full, unreduced cross-section, away from web

punchouts. 4. Use the effective moment of inertia for deflection calculation. 5. Allowable moment is lesser of Ma and Mad. Distortional buckling is based on an assumed $K\phi = 0$. 6. These members are available un-punched only.

162VS125-30 VIPERSTUD

Geometric Properties

1-5/8" x 1-1/4" flange, 30 mil ViperStuds are manufactured from standard G40 hot-dipped galvanized steel. G60 and G90 coatings are available through special order, and may require up-charges and extended lead times.

Steel Thickness

Model No.	Design Thickness (in)	Minimum Thickness (in)	Yield (ksi)	"W" Web Sizes (in)	Coating ^{4,5}	Flange (in)	"L" Return Lip (in)
162VS125-30	0.0312	0.0296	33	1-5/8	G40	1-1/4	1/4

Notes: 1. Uncoated steel thickness. Thickness is for carbon sheet steel. 2. Minimum thickness represents 95% of the design thickness and is the minimum acceptable thickness. 3. Knockout size for 1-5/8" Stud is 3/4" x 1-3/4". 4. Per ASTM C645 & A1003, Table 1. 5. G60 and G90 available upon request. Will require extended lead time and upcharge.


Color Code (painted on ends): 30 mil: Pink

ASTM & Code Standards:

- ASTM A653/A653M, A924/A924M, A1003/1003, C645 & C754
- ICC-ES & SFIA Code Compliance Certification Program
- ICC ESR-2620
- ATI CCRR-0224
- IBC: 2012, 2015, 2018
- CBC: 2013, 2016
- AISI: S100-07, S100-12, S100-16, S220-11, S220-15

LEED v4 for Building and Design Construction

- MR Prerequisite: Construction and Demolition Waste Management Planning.
- MR Credit: Construction and Demolition Waste Management.
- MR Credit: Building Product Disclosure and Optimization – Sourcing of Raw Materials, Option 2.
- MR Credit: Building Product Disclosure and Optimization – Environmental Product Declarations, Options 1 & 2.
- MR Credit: Building Product Disclosure and Optimization – Material Ingredients, Option 1.
- MR Credit: Building Life-Cycle Impact Reduction, Option 4.



162VS125-30 ViperStud Properties

Design (in)	Min (in)	Yield (ksi)	Weight (lb/ft)	Gross Properties					Effective Properties		Moment				Critical Unbraced Length ⁷ Lu (in)
				Area (in ²)	Ix (in ⁴)	Iy (in ⁴)	rx (in)	ry (in)	Ixd (in ⁴)	Sx (in ³)	Allowable Moment Ma (in-k)	Local Buckling Nominal Moment ² Viper Mnl (in-k)	Distortional Buckling Nominal Moment ² Viper Mnd (in-k)	Nominal Moment for Conventional Studs ³ Mn (in-k)	
0.0312	0.0296	33	0.46	0.135	0.062	0.680	0.028	0.455	0.062	0.067	1.32	2.21	2.38	1.99 (30 mil)	30.8

Notes: 1. Section properties are in accordance with AISI S100-07/ S1-10. Viper 25 and Viper20 section properties are based on testing. Allowable moment (Ma) is calculated in accordance with Chapter F of AISI S100-07/ S1-10 specification. 2. Nominal moment for Viper

18 mil, Viper 30 mil, and Viper 33 mil conventional studs are based on calculations in accordance with AISI S100-07/ S1-10. Allowable moments (Ma) can be calculated with a 1.67 safety factor. 3. Section properties are in accordance with AISI S100-07 with S1-10 and AISI

S220-11. 4. Web depth-to-thickness ratio exceeds 200. 5. Web depth-to-thickness ratio exceeds 260. 6. ViperStud is considered fully braced when unbraced length is less than listed Lu. 7. KΦ assumed to be zero for distortional buckling moments.

Non-Composite Limiting Heights – Braced at 48" O.C.

Depth (in)	Gauge	Member Designation	Design (in)	Min (in)	Yield (ksi)	Spacing (o.c.)	5 PSF			7.5 PSF			10 PSF		
							L/120	L/240	L/360	L/120	L/240	L/360	L/120	L/240	L/360
1-5/8	20	162VS125-30	0.0312	0.0296	33	12	11'-10"	9'-4"	8'-2"	10'-4"	8'-2"	7'-1"	8'-11" f	7'-5"	6'-6"
		162VS125-30	0.0312	0.0296	33	16	10'-8"	8'-6"	7'-5"	8'-11" f	7'-5"	6'-6"	7'-8" f	6'-8"	--
		162VS125-30	0.0312	0.0296	33	24	8'-11" f	7'-5"	6'-6"	7'-4" f	6'-6"	--	6'-4" f	--	--

Notes: 1. Limiting heights are in accordance with AISI S100-07 using all steel non-composite design. 2. Limiting heights are established by considering flexure, shear, web crippling, and deflection. The web crippling values are based on testing with a bearing length of 1". 3. For bending, studs are assumed to be adequately braced to develop full allowable moment. Studs are considered fully braced when unbraced length is less than Lu. 4. Viper25 & Viper20 distortional & local buckling moments and stiffness are based on testing in

accordance with App. A of a non-structural code compliance program. 5. For web crippling, when h/t ≤ 200, the web crippling values are computed based on section C3.4.2 of AISI S100-07, when h/t > 200, the web crippling values are based on testing with a bearing length of 1" and fastened to support. 6. Web stiffeners are required for studs with h/t > 200, web crippling and shear values have been confirmed by testing. **Fully braced when unbraced length is less than Lu. See section properties table for Lu values.**

7. The factory punchouts are in accordance with section C5 of AISI S201-07. The distance from the center of the last punchout to the end of the stud is 12".

"f" - flexure controls; "s" - shear controls; "w" - web crippling controls. No letter next to the number means deflection controls.

162VS125-30 VIPERSTUD

PAGE 2

Non-Composite Limiting Heights – Fully Braced

Depth (in)	Gauge	Member Designation	Design (in)	Min (in)	Yield (ksi)	Spacing (o.c.)	5 PSF			7.5 PSF			10 PSF		
							L/120	L/240	L/360	L/120	L/240	L/360	L/120	L/240	L/360
1-5/8	20	162VS125-30	0.0312	0.0296	33	12	11'-8"	9'-4"	8'-1"	10'-2"	8'-1"	7'-1"	9'-4"	7'-5"	6'-6"
		162VS125-30	0.0312	0.0296	33	16	10'-8"	8'-6"	7'-5"	9'-4"	7'-5"	6'-6"	8'-1" f	6'-8"	--
		162VS125-30	0.0312	0.0296	33	24	9'-4"	7'-5"	6'-6"	7'-8" f	6'-6"	--	6'-7" f	--	--

Notes: 1. Limiting heights are in accordance with AISI S100-07 using all steel non-composite design. 2. Limiting heights are established by considering flexure, shear, web crippling, and deflection. The web crippling values are based on testing with a bearing length of 1".

3. For bending, studs are assumed to be adequately braced to develop full allowable moment. Studs are considered fully braced when unbraced length is less than Lu. 4. Viper25 & Viper20 distortional & local buckling moments and stiffness are based on testing in

accordance with App. A of a non-structural code compliance program.

5. For web crippling, when $h/t \leq 200$, the web crippling values are computed based on section C3.4.2 of AISI S100-07. When $h/t > 200$, the web crippling values are based on testing with a bearing length of 1" and fastened to support. 6. No web stiffeners are required for studs with $h/t > 200$, web crippling and shear values have been confirmed by testing. **Fully braced when unbraced length is less than Lu. See section properties table for Lu values.**

7. The factory punchouts are in accordance with section C5 of AISI S201-07. The distance from the center of the last punchout to the end of the stud is 12".

"f" - flexure controls; "s" - shear controls; "w" - web crippling controls. No letter next to the number means deflection controls.

Allowable Composite Heights for Non-Load Bearing Walls

Depth (in)	Gauge	Member Designation	Design (in)	Min (in)	Yield (ksi)	Spacing (o.c.)	5 PSF			7.5 PSF			10 PSF		
							L/120	L/240	L/360	L/120	L/240	L/360	L/120	L/240	L/360
1-5/8	20	162VS125-30	0.0312	0.0296	33	12	14'-7"	11'-6"	10'-0"	12'-9"	10'-0"	8'-6"	11'-7"	8'-11"	--
		162VS125-30	0.0312	0.0296	33	16	13'-3"	10'-5"	8'-11"	11'-7"	8'-11"	--	10'-6"	7'-10"	--
		162VS125-30	0.0312	0.0296	33	24	11'-7"	8'-11"	--	10'-1"	--	--	8'-10"	--	--

Notes: 1. Viper composite limiting heights are based on testing in accordance with ICC-ES acceptance criteria AC86-2012.

2. No screws are required between stud and track, except as required by ASTM C754. Composite heights are based on using standard top track. Screw fastening of stud to track is not required. Mechanically fastening of gypsum panel to the stud and track is required.

3. Viper composite limiting heights based on single layer of 5/8" Type X gypsum board applied vertically to both sides of the wall over fill height. 5/8" Type X wallboard from the following manufacturers are acceptable: USG, National, Georgia-Pacific, Temple Inland, CertainTeed, American, and LaFarge.

Allowable Ceiling Spans

L/240		4 PSF Lateral Support of Compression Flange						6 PSF Lateral Support of Compression Flange					
Member	Fy ksi	Unsupported Joist Spacing (in.) O.C.			Midspan Joist Spacing (in.) O.C.			Unsupported Joist Spacing (in.) O.C.			Midspan Joist Spacing (in.) O.C.		
		12	16	24	12	16	24	12	16	24	12	16	24
162VS125-30	33	9'-4" f	8'-7" f	7'-8" f	10'-1"	9'-2"	8'-0"	8'-4" f	7'-8" f	6'-10" f	8'-10"	8'-0"	7'-0"

L/360		4 PSF Lateral Support of Compression Flange						6 PSF Lateral Support of Compression Flange					
Member	Fy ksi	Unsupported Joist Spacing (in.) O.C.			Midspan Joist Spacing (in.) O.C.			Unsupported Joist Spacing (in.) O.C.			Midspan Joist Spacing (in.) O.C.		
		12	16	24	12	16	24	12	16	24	12	16	24
162VS125-30	33	8'-10"	8'-0"	7'-0"	8'-10"	8'-0"	7'-0"	7'-8"	7'-0"	6'-1"	7'-8"	7'-0"	6'-1"

Notes: 1. Ceiling Spans are in accordance with AISI S100-07/S1-10 using all steel non-composite design. 2. Ceiling Spans are established by considering flexure, shear, web crippling, and deflection. 3. For web crippling, when $h/t \leq 200$, the web crippling values are computed based on section C3.4.2 of AISI S100-07. When $h/t > 200$, the web crippling values are based on testing with a bearing length of 1". 4. No web stiffeners are required for studs with $h/t > 200$, web

cripping and shear values have been confirmed by testing. 5. All values are for simple spans, with compression flange either unbraced or braced at mid-span. 6. Ceiling spans are based on total load of assembly, not including storage or live load for accessible ceilings. 7. The factory punchouts are in accordance with section C5 of AISI S201-07. The distance from the center of the last punchout to the end of the stud is 12".

"f" - flexure controls; "s" - shear controls; "w" - web crippling controls. No letter next to the number means deflection controls.

CEMCO cold-formed steel framing products contain 30% to 37% recycled steel.

■ Total Recycled Content: 36.9% ■ Post-Consumer: 19.8% ■ Pre-Consumer: 14.4%

CSI Division:

■ 09.22.16 – Non-Structural Metal Framing



Expanding Your Solutions

Corporate Headquarters

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.775.2362
Fax: 626.330.7598
www.cemcosteel.com

Manufacturing Facility

City of Industry, CA
Denver, CO
Ft. Worth, TX
Pittsburg, CA

2.3.D Seismic/Wind Uplift Compression Struts

1001-A Pittsburgh Antioch Hwy
Pittsburg, CA 94565
Phone: 800.775.2362
Fax: 626.330.7598
www.cemcoengineering.com

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.416.2278
Fax: 626.249.5004

162VT125-30 VIPERTRACK

Geometric Properties

1-5/8" X 1-1/4" flange 30 mil ViperTracks are manufactured from standard G40 hot-dipped galvanized steel. G60 and G90 coatings are available through special order, and may require up-charges and extended lead times.

Steel Thickness

Model No.	Design Thickness (in)	Minimum Thickness (in)	Yield (ksi)	Web Depth (W) (in)	Coating ⁴	Flange (in)
162VT125-30	0.0312	0.0296	33	1-5/8	G40	1-1/4

Notes:

- Uncoated steel thickness. Thickness is for carbon sheet steel.
- Minimum thickness represents 95% of the design thickness and is the minimum acceptable thickness.
- Per ASTM C645 & A1003.
- G60 and G90 available upon request. Will require extended lead time and upcharge.

Color Code (painted on ends): 30 mil: Pink

ASTM & Code Standards:


- ASTM A653/A653M, A924/A924M, A1003/1003, C645 & C754
- ICC-ES & SFIA Code Compliance Certification Program
- ICC ESR-2620
- ATI CCRR-0154
- ATI CCRR-0224
- CBC: 2013, 2016
- IBC: 2012, 2015, 2018
- AISI: S100-07, S100-12, S100-16, S220-11, S220-15

LEED v4 for Building and Design Construction

- MR Prerequisite: Construction and Demolition Waste Management Planning.
- MR Credit: Construction and Demolition Waste Management.
- MR Credit: Building Product Disclosure and Optimization – Sourcing of Raw Materials, Option 2.
- MR Credit: Building Product Disclosure and Optimization – Environmental Product Declarations, Options 1 & 2.
- MR Credit: Building Product Disclosure and Optimization – Material Ingredients, Option 1.
- MR Credit: Building Life-Cycle Impact Reduction, Option 4.

CEMCO cold-formed steel framing products contain 30% to 37% recycled steel.

- Total Recycled Content: 36.9%
- Post-Consumer: 19.8%
- Pre-Consumer: 14.4%



Interior Non-Load Bearing Track Section Properties

Member	Leg Size (in)					Gross Properties							Effective Properties			Torsional Properties				
		Weight (lb/ft)	Design (in)	Min (in)	Yield (ksi)	Area (in ²)	I _x (in ⁴)	S _x (in ³)	R _x (in)	I _y (in ⁴)	S _y (in ³)	R _y (in)	I _{xd} (in ⁴)	S _{xe} (in ³)	Ma (in-k)	X _o (in)	J _{x103} (in ⁴)	C _w (in)	R _o (in)	β
162VT125-30	1.25	0.44	0.0312	0.0296	33	0.129	0.071	0.080	0.741	0.022	0.0249	0.409	0.056	0.051	1.00	-0.868	0.0419	0.012	1.21	0.488

Notes:

- Section properties are in accordance with AISI S100-16.
- Cold-work of forming is not included.
- The effective moment of inertia for deflection is calculated based on AISI S100-16 procedure 1 for serviceability determination.
- The center line bend radius is greater than 2 times the design thickness or 3/32".

Check the updated list of Certified Production Facilities at Intertek's website at <http://www.intertek.com/building/sfia>



This technical information reflects the most current information available and supersedes any and all previous publications effective December 12, 2018.

12-12-18 AT



Expanding Your Solutions

Corporate Headquarters

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.775.2362
Fax: 626.330.7598

Manufacturing

City of Industry, CA
Denver, CO
Ft. Worth, TX
Pittsburg, CA

2.3.D Seismic/Wind Uplift Compression Struts

1001-A Pittsburgh Antioch Hwy
Pittsburg, CA 94565
Phone: 800.775.2362
Fax: 626.330.7598

13191 Crossroads Pkwy N., Ste 325
City of Industry, CA 91746
Phone: 800.416.2278
Fax: 626.249.5004

"U" - UNPUNCHED U-SHAPED CHANNEL • 1-1/2" x 54 Mil.


Geometric Properties

1-1/2" "U" channels are fabricated in 1/2" legs. All CEMCO U-Shaped channels are produced from hot-dipped galvanized steel in standard G60 coating. G90 is available upon special request.

Steel Thickness

Thickness (mil)	Design Thickness (in) ¹	Minimum Thickness (in) ^{1,2}
54	0.0566 (1.44 mm)	0.0538 (1.37 mm)

Notes: 1. Uncoated Steel Thickness. Thickness is for carbon sheet steel. 2. Minimum Thickness represents 95% of the design thickness and is the minimum acceptable thickness delivered to the job site, based on Section A4.3 of the AISI S100-2007.



Color Code (painted on ends): 54-mil: Green

ASTM & Code Standards:

- ASTM A653/A653M, 924/A924M, A1003/1003, C955 & C1007
- ICC-ES & SFIA Code Compliance Certification Program
- ICC ESR-3016
- ATI CCRR-0224
- IBC: 2012, 2015, 2018
- CBC: 2013, 2016
- AISI: S100-07, S100-12, S100-16, S200-12, S240-15

CSI Division: 05.40.00 – Cold-Formed Metal Framing

LEED v4 for Building and Design Construction

- MR Prerequisite: Construction and Demolition Waste Management Planning.
- MR Credit: Construction and Demolition Waste Management.
- MR Credit: Building Product Disclosure and Optimization – Sourcing of Raw Materials, Option 2.
- MR Credit: Building Product Disclosure and Optimization – Environmental Product Declarations, Options 1 & 2.
- MR Credit: Building Product Disclosure and Optimization – Material Ingredients, Option 1.
- MR Credit: Building Life-Cycle Impact Reduction, Option 4.

CEMCO cold-formed steel framing products contain 30% to 37% recycled steel.

- Total Recycled Content: 36.9%
- Post-Consumer: 19.8%
- Pre-Consumer: 14.4%



U-Channel Section Properties

Section	Design Thickness (in)	Gross Properties						Effective Properties			
		Area (in ²)	Weight (lb/ft)	I _x (in ⁴)	R _x (in)	I _y (in ⁴)	R _y (in)	I _x (in ⁴)	S _x (in ³)	M _a (in-k)	V _a (lbs)
150U050-54	0.0566	0.129	0.44	0.039	0.547	0.003	0.144	0.039	0.052	1.22	840

Notes: 1. For Deflection calculations, use effective I_{xx}.

U-Shaped Channels Allowable Ceiling Spans

Section	Uniform Load																
			4 psf Channel Spacing o.c. (in)					6 psf Channel Spacing o.c. (in)					13 psf Channel Spacing o.c. (in)				
			24	36	48	60	72	24	36	48	60	72	24	36	48	60	72
150U050-54	L/240	Single	5'-6"	4'-10"	4'-5"	4'-1"	3'-10"	4'-10"	4'-3"	3'-10"	3'-7"	3'-5"	3'-9"	3'-3"	3'-0"	2'-9"	2'-7"
		Multiple	7'-1"	6'-2"	5'-8"	5'-3"	4'-11"	6'-2"	5'-5"	4'-11"	4'-7"	4'-4"	4'-10"	4'-2"	3'-9"	3'-4"	3'-0"
	L/360	Single	5'-6"	4'-10"	4'-5"	4'-1"	3'-10"	4'-10"	4'-3"	3'-10"	3'-7"	3'-5"	3'-9"	3'-3"	3'-0"	2'-9"	2'-7"
		Multiple	7'-1"	6'-2"	5'-8"	5'-3"	4'-11"	6'-2"	5'-5"	4'-11"	4'-7"	4'-4"	4'-10"	4'-2"	3'-9"	3'-4"	3'-0"

Notes:

1. F_y = 50 ksi for all sections.
2. Bearing Lengths = 0.75".
3. Allowable spans based on the compression flange laterally unbraced.

Technical Services

Technical Services: 800.416.2278
Structural Engineering/Design: 925.473.9340
www.cemcosteel.com



This technical information reflects the most current information available and supersedes any and all previous publications effective December 21, 2018.
12-21-18 AT



Spokane Washington Manufacturing Facility
2800 East Main Avenue, Spokane, WA 99202
Phone: 509.343.9000 Fax: 509-343-9060

Stockton California Manufacturing Facility
2525 South Airport Way, Stockton, CA 95206
Phone: 209.670.8053 Fax: 209.670.8057

362S200-43

Product Information


The structural stud is fabricated from prime mill certified steel with a true galvanized coating. Heavier coatings may be available upon request.

Steel Material Properties

43 Mil	Labeled Thickness
0.0451"	Design Thickness
0.0428"	Minimum Thickness
33 ksi	Yield Strength (Fy)
45 ksi	Tensile Strength (Fu)
G60	Galvanize Coating Thickness
Yellow	Color Code (Painted Ends)

Geometric Properties

3-5/8"	Web Width
2"	Flange Height
5/8"	Return Length



LEED - Contributing Credits

All SCAFCO materials have a high inherent recycled steel content.

- LEED 2009 - MRC2 (2 points) & MRC4 (2 points)
- LEED v4 - MR Credits - EPD (2 points) - Waste Management (2 points) - Sourcing of Raw Materials (1 point) - Material Ingredients (1 point) - Innovation (2 points)

Recycled Content of Steel

- 14.4% Pre-Consumer Scrap Recycled Content
- 19.8% Post-Consumer Scrap Recycled Content
- 36.9% Total Recycled Content

ASTM and AISI Code Standards

- ASTM A653/A653M, A924/A924M, A1003, C645, C754, C955, C1007
- AISI NASPEC 2007 Edition S100-07 (Supplement S2-10 for IBC 2012)
- 2012, 2015 International Building Codes and 2010, 2013 CBC

SCAFCO Technical Services

For additional information, visit www.SCAFCO.com or contact technical services at 509-343-9000 or technical@SCAFCO.com

Section Properties

Table Notes:

1. The centerline bend radius is based on inside corner radii.
2. Effective properties incorporate the strength increase from the cold work of forming as applicable per AISI S100 A7.2.
3. Tabulated gross properties are based on the full-unreduced cross section of the studs away from punch-out's.
4. For deflection calculations, use the effective moment of inertia.
5. Allowable moment is the lesser of M_{al} and M_{ad} . Stud distortional buckling is based on an assumed $K\phi = 0$.



Section	Gross Properties							Effective and Distortional Properties						Torsional Properties						Lu (in)
	Area (in ²)	Weight (lb/ft)	Ix (in ⁴)	Sx (in ³)	Rx (in)	Iy (in ⁴)	Ry (in)	Ixe (in ⁴)	Sxe (in ³)	Mal (in-k)	Mad (in-k)	Vag (lb)	VaNet (lb)	Jx1000 (in ⁴)	Cw (in ⁶)	Xo (in)	m (in)	Ro (in)	β	
362S200-43	0.385	1.31	0.836	0.461	1.474	0.227	0.767	0.836	0.427	8.43	8.70	1739	676	0.261	0.734	-1.729	1.024	2.398	0.480	53.5

Limiting Wall Heights

Table Notes:

1. Listed wind pressures represent calculated designed wind pressure (1.0 W based on 2009 or 0.6 W based on 2012 IBC). For deflection calculations, listed wind pressures have been reduced by 0.70 as allowed by IBC. The 5 psf pressure has not been reduced for deflection checks.
2. Studs must be braced against rotation and lateral movement at all supports.
3. Studs are assumed to be adequately braced at a maximum spacing of L_u to develop full allowable moment.
4. Web crippling check is based on 1" of bearing at end supports and 3" of bearing at interior support.
5. Shear and web crippling capacity at end supports have not been reduced for punch-out's. Shear and web crippling capacity at interior support have been reduced for the presence of punch-out adjacent to the support.
6. Combined bending and shear check at interior support is based on unreinforced web per AISI S100 (Eq. C3.3.1-1). Shear capacity and combined bending and shear check at interior support have been reduced for the presence of punch-out's adjacent to support.

Stud Spacing (in)	Non-Composite Fully Braced (5 psf)				Non-Composite Fully Braced (15 psf)				Non-Composite Fully Braced (20 psf)		
	L/120	L/240	L/360		L/240	L/360	L/600		L/240	L/360	L/600
12" o.c.	28' 0"	22' 3"	19' 5"		17' 4"	15' 2"	12' 9"		15' 9"	13' 9"	11' 7"
16" o.c.	25' 5"	20' 2"	17' 8"		15' 9"	13' 9"	11' 7"		14' 4"	12' 6"	10' 7"
24" o.c.	22' 3"	17' 8"	15' 5"		13' 8"	12' 0"	10' 2"		11' 10"	10' 11"	9' 3"

362S162-33

Product Information


The structural stud is fabricated from prime mill certified steel with a true galvanized coating. Heavier coatings may be available upon request.

Steel Material Properties

33 Mil	Labeled Thickness
0.0346"	Design Thickness
0.0329"	Minimum Thickness
33 ksi	Yield Strength (Fy)
45 ksi	Tensile Strength (Fu)
G60	Galvanize Coating Thickness
White	Color Code (Painted Ends)

Geometric Properties

3-5/8"	Web Width
1-5/8"	Flange Height
1/2"	Return Length



LEED - Contributing Credits

All SCAFCO materials have a high inherent recycled steel content.

- LEED 2009 - MRC2 (2 points) & MRC4 (2 points)
- LEED v4 - MR Credits - EPD (2 points) - Waste Management (2 points) - Sourcing of Raw Materials (1 point) - Material Ingredients (1 point) - Innovation (2 points)

Recycled Content of Steel

- 14.4% Pre-Consumer Scrap Recycled Content
- 19.8% Post-Consumer Scrap Recycled Content
- 36.9% Total Recycled Content

ASTM and AISI Code Standards

- ASTM A653/A653M, A924/A924M, A1003, C645, C754, C955, C1007
- AISI NASPEC 2007 Edition S100-07 (Supplement S2-10 for IBC 2012)
- 2012, 2015 International Building Codes and 2010, 2013 CBC

SCAFCO Technical Services

For additional information, visit www.SCAFCO.com or contact technical services at 509-343-9000 or technical@SCAFCO.com

Section Properties

Table Notes:

1. The centerline bend radius is based on inside corner radii.
2. Effective properties incorporate the strength increase from the cold work of forming as applicable per AISI S100 A7.2.
3. Tabulated gross properties are based on the full-unreduced cross section of the studs away from punch-out's.
4. For deflection calculations, use the effective moment of inertia.
5. Allowable moment is the lesser of M_{al} and M_{ad} . Stud distortional buckling is based on an assumed $K\phi = 0$.



Section	Gross Properties							Effective and Distortional Properties						Torsional Properties						Lu (in)
	Area (in ²)	Weight (lb/ft)	Ix (in ⁴)	Sx (in ³)	Rx (in)	Iy (in ⁴)	Ry (in)	Ixe (in ⁴)	Sxe (in ³)	Mal (in-k)	Mad (in-k)	Vag (lb)	VaNet (lb)	Jx1000 (in ⁴)	Cw (in ⁶)	Xo (in)	m (in)	Ro (in)	β	
362S162-33	0.262	0.89	0.551	0.304	1.450	0.099	0.616	0.551	0.268	5.29	5.43	1024	521	0.105	0.297	-1.308	0.789	2.048	0.592	42.6

Limiting Wall Heights

Table Notes:

1. Listed wind pressures represent calculated designed wind pressure (1.0 W based on 2009 or 0.6 W based on 2012 IBC). For deflection calculations, listed wind pressures have been reduced by 0.70 as allowed by IBC. The 5 psf pressure has not been reduced for deflection checks.
2. Studs must be braced against rotation and lateral movement at all supports.
3. Studs are assumed to be adequately braced at a maximum spacing of L_u to develop full allowable moment.
4. Web crippling check is based on 1" of bearing at end supports and 3" of bearing at interior support.
5. Shear and web crippling capacity at end supports have not been reduced for punch-out's. Shear and web crippling capacity at interior support have been reduced for the presence of punch-out adjacent to the support.
6. Combined bending and shear check at interior support is based on unreinforced web per AISI S100 (Eq. C3.3.1-1). Shear capacity and combined bending and shear check at interior support have been reduced for the presence of punch-out's adjacent to support.

Stud Spacing (in)	Non-Composite Fully Braced (5 psf)				Non-Composite Fully Braced (15 psf)				Non-Composite Fully Braced (20 psf)		
	L/120	L/240	L/360		L/240	L/360	L/600		L/240	L/360	L/600
12" o.c.	24' 4"	19' 4"	16' 11"		15' 1"	13' 2"	11' 1"		13' 3"	12' 0"	10' 1"
16" o.c.	22' 2"	17' 7"	15' 4"		13' 3"	12' 0"	10' 1"		11' 6"	10' 11"	9' 2"
24" o.c.	18' 9"	15' 4"	13' 5"		10' 10"	10' 6"	8' 10"		9' 5" e	9' 5" e	8' 0"

"e" web stiffeners required at ends.



Spokane Washington Manufacturing Facility
2800 East Main Avenue, Spokane, WA 99202
Phone: 509.343.9000 Fax: 509-343-9060

Stockton California Manufacturing Facility
2525 South Airport Way, Stockton, CA 95206
Phone: 209.670.8053 Fax: 209.670.8057

362S137-33

Product Information


The structural stud is fabricated from prime mill certified steel with a true galvanized coating. Heavier coatings may be available upon request.

Steel Material Properties

33 Mil	Labeled Thickness
0.0346"	Design Thickness
0.0329"	Minimum Thickness
33 ksi	Yield Strength (Fy)
45 ksi	Tensile Strength (Fu)
G60	Galvanize Coating Thickness
White	Color Code (Painted Ends)

Geometric Properties

3-5/8"	Web Width
1-3/8"	Flange Height
3/8"	Return Length



LEED - Contributing Credits

All SCAFCO materials have a high inherent recycled steel content.

- LEED 2009 - MRC2 (2 points) & MRC4 (2 points)
- LEED v4 - MR Credits - EPD (2 points) - Waste Management (2 points) - Sourcing of Raw Materials (1 point) - Material Ingredients (1 point) - Innovation (2 points)

Recycled Content of Steel

- 14.4% Pre-Consumer Scrap Recycled Content
- 19.8% Post-Consumer Scrap Recycled Content
- 36.9% Total Recycled Content

ASTM and AISI Code Standards

- ASTM A653/A653M, A924/A924M, A1003, C645, C754, C955, C1007
- AISI NASPEC 2007 Edition S100-07 (Supplement S2-10 for IBC 2012)
- 2012, 2015 International Building Codes and 2010, 2013 CBC

SCAFCO Technical Services

For additional information, visit www.SCAFCO.com or contact technical services at 509-343-9000 or technical@SCAFCO.com

Section Properties

Table Notes:

1. The centerline bend radius is based on inside corner radii.
2. Effective properties incorporate the strength increase from the cold work of forming as applicable per AISI S100 A7.2.
3. Tabulated gross properties are based on the full-unreduced cross section of the studs away from punch-out's.
4. For deflection calculations, use the effective moment of inertia.
5. Allowable moment is the lesser of M_{al} and M_{ad} . Stud distortional buckling is based on an assumed $K\phi = 0$.



Section	Gross Properties							Effective and Distortional Properties						Torsional Properties						Lu (in)
	Area (in ²)	Weight (lb/ft)	Ix (in ⁴)	Sx (in ³)	Rx (in)	Iy (in ⁴)	Ry (in)	Ixe (in ⁴)	Sxe (in ³)	Mal (in-k)	Mad (in-k)	Vag (lb)	VaNet (lb)	Jx1000 (in ⁴)	Cw (in ⁶)	Xo (in)	m (in)	Ro (in)	β	
362S137-33	0.236	0.80	0.479	0.264	1.424	0.059	0.501	0.479	0.232	4.59	4.73	1024	521	0.094	0.165	-1.003	0.615	1.813	0.694	34.7

Limiting Wall Heights

Table Notes:

1. Listed wind pressures represent calculated designed wind pressure (1.0 W based on 2009 or 0.6 W based on 2012 IBC). For deflection calculations, listed wind pressures have been reduced by 0.70 as allowed by IBC. The 5 psf pressure has not been reduced for deflection checks.
2. Studs must be braced against rotation and lateral movement at all supports.
3. Studs are assumed to be adequately braced at a maximum spacing of L_u to develop full allowable moment.
4. Web crippling check is based on 1" of bearing at end supports and 3" of bearing at interior support.
5. Shear and web crippling capacity at end supports have not been reduced for punch-out's. Shear and web crippling capacity at interior support have been reduced for the presence of punch-out adjacent to the support.
6. Combined bending and shear check at interior support is based on unreinforced web per AISI S100 (Eq. C3.3.1-1). Shear capacity and combined bending and shear check at interior support have been reduced for the presence of punch-out's adjacent to support.

Stud Spacing (in)	Non-Composite Fully Braced (5 psf)				Non-Composite Fully Braced (15 psf)				Non-Composite Fully Braced (20 psf)		
	L/120	L/240	L/360		L/240	L/360	L/600		L/240	L/360	L/600
12" o.c.	23' 3"	18' 5"	16' 1"		14' 3"	12' 7"	10' 7"		12' 4"	11' 5"	9' 8"
16" o.c.	21' 1"	16' 9"	14' 8"		12' 4"	11' 5"	9' 8"		10' 9"	10' 5"	8' 9"
24" o.c.	17' 6"	14' 8"	12' 10"		10' 1"	10' 0"	8' 5"		8' 9" e	8' 9" e	7' 8"

"e" web stiffeners required at ends.



Spokane Washington Manufacturing Facility
2800 East Main Avenue, Spokane, WA 99202
Phone: 509.343.9000 Fax: 509-343-9060

Stockton California Manufacturing Facility
2525 South Airport Way, Stockton, CA 95206
Phone: 209.670.8053 Fax: 209.670.8057

162S125-30

Product Information


The non-structural stud is fabricated from prime mill certified steel with a true galvanized coating. Heavier coatings may be available upon request.

Steel Material Properties

30 Mil	Labeled Thickness
0.0312"	Design Thickness
0.0296"	Minimum Thickness
33 ksi	Yield Strength (Fy)
45 ksi	Tensile Strength (Fu)
G40	Galvanize Coating Thickness
Red	Color Code (Painted Ends)

Geometric Properties

1-5/8"	Web Width
1-1/4"	Flange Height
3/16"	Return Length



LEED - Contributing Credits

All SCAFCO materials have a high inherent recycled steel content.

- LEED 2009 - MRc2 (2 points) & MRc4 (2 points)
- LEED v4 - MR Credits - EPD (2 points) - Waste Management (2 points) - Sourcing of Raw Materials (1 point) - Material Ingredients (1 point) - Innovation (2 points)

Recycled Content of Steel

- 14.4% Pre-Consumer Scrap Recycled Content
- 19.8% Post-Consumer Scrap Recycled Content
- 36.9% Total Recycled Content

ASTM and AISI Code Standards

- ASTM A653/A653M, A924/A924M, A1003, C645, C754
- AISI S100-07 with supplement S2-10 per 2012 IBC, AISI S100-12 per 2015 IBC
- 2012, 2015 International Building Codes and 2010, 2013 CBC

SCAFCO Technical Services

For additional information, visit www.SCAFCO.com or contact technical services at 509-343-9000 or technical@SCAFCO.com

Section Properties

Table Notes:

1. The centerline bend radius is based on inside corner radii.
2. Effective properties incorporate the strength increase from the cold work of forming as applicable per AISI S100 A7.2.
3. Tabulated gross properties are based on the full-unreduced cross section of the studs away from punch-outs.
4. For deflection calculations, use the effective moment of inertia.
5. Allowable moment is the lesser of M_{al} and M_{ad} . Stud distortional buckling is based on an assumed $K\phi = 0$.



Section	Gross Properties							Effective and Distortional Properties						Torsional Properties						Lu (in)
	Area (in ²)	Weight (lb/ft)	Ix (in ⁴)	Sx (in ³)	Rx (in)	Iy (in ⁴)	Ry (in)	Ixe (in ⁴)	Sxe (in ³)	Mal (in-k)	Mad (in-k)	Vag (lb)	VaNet (lb)	Jx1000 (in ⁴)	Cw (in ⁶)	Xo (in)	m (in)	Ro (in)	β	
162S125-30	0.131	0.45	0.061	0.075	0.681	0.026	0.441	0.060	0.060	1.19	1.29	543	106	0.043	0.014	-1.014	0.585	1.298	0.390	29.2

Limiting Wall Heights

Table Notes:

1. Allowable composite limiting heights are calculated using ICC-ES AC86-2012.
2. No fasteners are required for attaching the stud to the track.
3. Stud end bearing must be a minimum of 1 inch.
4. Composite limiting heights are based on a single layer of 5/8" type-X gypsum board installed in the vertical orientation to both sides of the wall over full height using minimum No. 6 type S drywall screws spaced a maximum of 12" oc for studs at 24" spacing, and 16" oc for studs at 16" and 12" spacing.

Table Notes:

1. Loads have not been reduced for strength or deflection checks; full lateral load is applied.
2. Limiting heights are based on steel properties only without the contribution of sheathing to strength and stiffness of the assembly. Properly fastened sheathing is still required for members to be considered fully braced.
3. Web crippling check based on 1" end bearing.
4. Studs are assumed to be adequately braced at maximum spacing of L_u to develop full allowable moment.

Table Notes:

1. Loads have not been reduced for strength or deflection checks; full lateral load is applied.
2. Limiting heights are based on studs braced at maximum spacing of 48" oc. Bracing can be placed at greater distances if deflection controls.
3. Web crippling check based on 1" end bearing.

Stud Spacing (in)	Composite Wall Heights (5 psf)				Non-Composite Fully Braced (5 psf)				Non-Composite Braced at 48" O.C. (5 psf)		
	L/120	L/240	L/360		L/120	L/240	L/360		L/120	L/240	L/360
12" o.c.	14' 11"	11' 10"	10' 4"		11' 8"	9' 3"	8' 1"		11' 8"	9' 3"	8' 1"
16" o.c.	13' 7"	10' 9"	9' 4"		10' 7"	8' 5"	-		10' 3"	8' 5"	-
24" o.c.	11' 10"	9' 4"	-		8' 11"	-	-		8' 4"	-	-



Spokane Washington Manufacturing Facility
2800 East Main Avenue, Spokane, WA 99202
Phone: 509.343.9000 Fax: 509-343-9060

Stockton California Manufacturing Facility
2525 South Airport Way, Stockton, CA 95206
Phone: 209.670.8053 Fax: 209.670.8057

362T150-33

Product Information


The framing track is fabricated from prime mill certified steel with a true galvanized coating. Heavier coatings may be available upon request.

Steel Material Properties

33 Mil	Labeled Thickness
0.0346"	Design Thickness
0.0329"	Minimum Thickness
33 ksi	Yield Strength (Fy)
45 ksi	Tensile Strength (Fu)
G60	Galvanize Coating Thickness
White	Color Code (Painted Ends)

Geometric Properties

3-5/8"	Web Width
1-1/2"	Leg Height



LEED - Contributing Credits

All SCAFCO materials have a high inherent recycled steel content.

- LEED 2009 - MRC2 (2 points) & MRC4 (2 points)
- LEED v4 - MR Credits - EPD (2 points) - Waste Management (2 points) - Sourcing of Raw Materials (1 point) - Material Ingredients (1 point) - Innovation (2 points)

Recycled Content of Steel

- 14.4% Pre-Consumer Scrap Recycled Content
- 19.8% Post-Consumer Scrap Recycled Content
- 36.9% Total Recycled Content

ASTM and AISI Code Standards

- ASTM A653/A653M, A924/A924M, A1003, C645, C754, C955, C1007
- AISI S100-07 with supplement S2-10 per 2012 IBC, AISI S100-12 per 2015 IBC
- 2012, 2015 International Building Codes and 2010, 2013 CBC

SCAFCO Technical Services

For additional information, visit www.SCAFCO.com or contact technical services at 509-343-9000 or technical@SCAFCO.com

Section Properties

Table Notes:

1. The centerline bend radius is based on inside corner radii.
2. Web depth for track section is equal to the nominal height plus 2 times the design thickness plus the bend radius.
3. Hems on nonstructural track sections are ignored. Not all track members are hemmed.
4. Effective properties incorporate the strength increase from the cold work of forming as applicable per AISI S100 Section A7.2.
5. For deflection calculations, use the effective moment of inertia.
6. Based on ASTM C645, the 18 Mil and 30 Mil track material is considered nonstructural.



Section	Gross Properties							Effective Properties				Torsional Properties						
	Area (in ²)	Weight (lb/ft)	I _x (in ⁴)	S _x (in ³)	R _x (in)	I _y (in ⁴)	R _y (in)	I _{xe} (in ⁴)	S _{xe} (in ³)	Ma (in-k)	V _{ag} (lb)	Jx1000 (in ⁴)	C _w (in ⁶)	X _o (in)	m (in)	R _o (in)	β	
362T150-33	0.229	0.78	0.499	0.264	1.475	0.050	0.467	0.414	0.180	3.56	1024	0.091	0.124	-0.854	0.522	1.767	0.766	



Spokane Washington Manufacturing Facility
2800 East Main Avenue, Spokane, WA 99202
Phone: 509.343.9000 Fax: 509-343-9060

Stockton California Manufacturing Facility
2525 South Airport Way, Stockton, CA 95206
Phone: 209.670.8053 Fax: 209.670.8057

162T125-30

Product Information


The framing track is fabricated from prime mill certified steel with a true galvanized coating. Heavier coatings may be available upon request.

Steel Material Properties

30 Mil	Labeled Thickness
0.0312"	Design Thickness
0.0296"	Minimum Thickness
33 ksi	Yield Strength (Fy)
45 ksi	Tensile Strength (Fu)
G40	Galvanize Coating Thickness
Red	Color Code (Painted Ends)

Geometric Properties

1-5/8"	Web Width
1-1/4"	Leg Height



LEED - Contributing Credits

All SCAFCO materials have a high inherent recycled steel content.

- LEED 2009 - MRC2 (2 points) & MRC4 (2 points)
- LEED v4 - MR Credits - EPD (2 points) - Waste Management (2 points) - Sourcing of Raw Materials (1 point) - Material Ingredients (1 point) - Innovation (2 points)

Recycled Content of Steel

- 14.4% Pre-Consumer Scrap Recycled Content
- 19.8% Post-Consumer Scrap Recycled Content
- 36.9% Total Recycled Content

ASTM and AISI Code Standards

- ASTM A653/A653M, A924/A924M, A1003, C645, C754, C955, C1007
- AISI S100-07 with supplement S2-10 per 2012 IBC, AISI S100-12 per 2015 IBC
- 2012, 2015 International Building Codes and 2010, 2013 CBC

SCAFCO Technical Services

For additional information, visit www.SCAFCO.com or contact technical services at 509-343-9000 or technical@SCAFCO.com

Section Properties

Table Notes:

1. The centerline bend radius is based on inside corner radii.
2. Web depth for track section is equal to the nominal height plus 2 times the design thickness plus the bend radius
3. Hems on nonstructural track sections are ignored. Not all track members are hemmed.
4. Effective properties incorporate the strength increase from the cold work of forming as applicable per AISI S100 Section A7.2.
5. For deflection calculations, use the effective moment of inertia.
6. Based on ASTM C645, the 18 Mil and 30 Mil track material is considered nonstructural.



Section	Gross Properties							Effective Properties				Torsional Properties					
	Area (in ²)	Weight (lb/ft)	I _x (in ⁴)	S _x (in ³)	R _x (in)	I _y (in ⁴)	R _y (in)	I _{xe} (in ⁴)	S _{xe} (in ³)	Ma (in-k)	V _{ag} (lb)	Jx1000 (in ⁴)	C _w (in ⁶)	X _o (in)	m (in)	R _o (in)	β
162T125-30	0.129	0.44	0.070	0.079	0.735	0.022	0.409	0.057	0.050	1.00	597	0.042	0.012	-0.870	0.500	1.210	0.483

150U050-54

Product Information


The u-channel or cold rolled channel (CRC) is often used as bracing through the punch out of the studs.
The CRC can also be used for ceiling spans and soffit framing.

Steel Material Properties

54 Mil	Labeled Thickness
0.0566"	Design Thickness
0.05338"	Minimum Thickness
50 ksi	Yield Strength (Fy)
65 ksi	Tensile Strength (Fu)
G60	Galvanize Coating Thickness

Geometric Properties

1-1/2"	Web Width
1/2"	Flange Height



LEED - Contributing Credits

All SCAFCO materials have a high inherent recycled steel content.

- LEED 2009 - MRC2 (2 points) & MRC4 (2 points)
- LEED v4 - MR Credits - EPD (2 points) - Waste Management (2 points) - Sourcing of Raw Materials (1 point) - Material Ingredients (1 point) - Innovation (2 points)

Recycled Content of Steel

- 14.4% Pre-Consumer Scrap Recycled Content
- 19.8% Post-Consumer Scrap Recycled Content
- 34.2% Total Recycled Content

ASTM and AISI Code Standards

- ASTM A653/A653M, A924/A924M, A1003, C645, C754, C955, C1007
- AISI NASPEC 2007 Edition S100-07 (Supplement S2-10 for IBC 2012)
- 2012, 2015 International Building Codes and 2013, 2016 CBC

SCAFCO Technical Services

For additional information, visit www.SCAFCO.com or contact technical services at 509-343-9000 or technical@SCAFCO.com

Section Properties

Table Notes:

- Inside bend radius taken as 3/32"

Section	Gross Properties					Effective and Distortional Properties				
	Area (in ²)	Weight (lb/ft)	Ix (in ⁴)	Rx (in)	Iy (in ⁴)	Ry (in)	Ixe (in ⁴)	Sxe (in ³)	Mal (in-k)	Vag (lb)
150U050-54	0.129	0.44	0.039	0.547	0.003	0.144	0.039	0.052	1.81	1273

Limiting Wall Heights

Table Notes:

- Multiple span indicates two or more equal spans with channel continuous over interior supports.
- Listed spans are based on unbraced compression flanges.
- Web crippling check is based on 1/4" bearing at end and interior supports. No bearing stiffeners are required.

Allowable Ceiling Spans (U-Sections) - L/240


	4 psf					6 psf					13 psf					15 psf				
	Channel Spacing (in) on center					Channel Spacing (in) on center					Channel Spacing (in) on center					Channel Spacing (in) on center				
	24	36	48	60	72	24	36	48	60	72	24	36	48	60	72	24	36	48	60	72
Single	5' 6"	4' 10"	4' 5"	4' 1"	3' 10"	4' 10"	4' 3"	3' 10"	3' 7"	3' 5"	3' 9"	3' 4"	3' 0"	2' 10"	2' 8"	3' 7"	3' 2"	2' 11"	2' 8"	2' 6"
Multiple	7' 1"	6' 2"	5' 8"	5' 3"	4' 11"	6' 2"	5' 5"	4' 11"	4' 7"	4' 4"	4' 10"	4' 3"	3' 10"	3' 7"	3' 4"	4' 7"	4' 0"	3' 8"	3' 5"	3' 2"

Allowable Ceiling Spans (U-Sections) - L/360

	4 psf					6 psf					13 psf					15 psf				
	Channel Spacing (in) on center					Channel Spacing (in) on center					Channel Spacing (in) on center					Channel Spacing (in) on center				
	24	36	48	60	72	24	36	48	60	72	24	36	48	60	72	24	36	48	60	72
Single	5' 6"	4' 10"	4' 5"	4' 1"	3' 10"	4' 10"	4' 3"	3' 10"	3' 7"	3' 5"	3' 9"	3' 4"	3' 0"	2' 10"	2' 8"	3' 7"	3' 2"	2' 11"	2' 8"	2' 6"
Multiple	7' 1"	6' 2"	5' 8"	5' 3"	4' 11"	6' 2"	5' 5"	4' 11"	4' 7"	4' 4"	4' 10"	4' 3"	3' 10"	3' 7"	3' 4"	4' 7"	4' 0"	3' 8"	3' 5"	3' 2"

UNISTRUT®

P1000T



Slots are 1 1/8" (29) X 3/16" (14)
2" (51) on Center
1 3/16" (30)
1/8" (22)

Materials & Finishes - Standard:

- **Pregalvanized (PG):** Conforms to ASTM A653 SS GR 33, G90.
- **Unistrut Defender (DF):** Conforms to ASTM A1046 SS GR 33
- **Hot Dip Galvanized (HG):** Steel conforms to ASTM A1011 SS GR 33, Finish conforms to ASTM A123
- **Perma-Green (GR):** Steel conforms to ASTM A1011 SS GR 33, E-Coat finish
- **Perma-Gold (ZD):** Steel conforms to ASTM A1011 SS GR 33, Finish conforms to ASTM B633, Type II SC3
- **Plain (PL):** Conforms to ASTM A1011 SS GR 33

Materials & Finishes - Special Metals:

- **Stainless Steel, Type 304 (SS):** ASTM A240, Type 304 *
- **Stainless Steel, Type 316 (ST):** ASTM A240, Type 316 *
- **Aluminum (EA):** ASTM B221, Type 6063-T6 (Extruded) *

* These materials have different physical properties and performance characteristics. Please [contact us](#) for design support.

Part No.	Length (ft)	Finish	Product Weight / Ft (lbs/ft)
P1000T	10	PG	1.85
P1000T	20	PG	1.85
P1000T	10	DF	1.961
P1000T	20	DF	1.961
P1000T	20	HG	1.961
P1000T	10	HG	1.961
P1000T	20	GR	1.85
P1000T	10	GR	1.85
P1000T	10	PL	1.85
P1000T	20	PL	1.85
P1000T	10	ZD	1.85
P1000T	20	ZD	1.85
P1000T	20	SS	1.85
P1000T	10	SS	1.88
P1000T	20	ST	1.85
P1000T	10	EA	0.76
P1000T	20	EA	0.76

Beam Loading - P1000T						
Span (in)	Max Allow. Uniform Load (lbs)	Deflection at Uniform load (in)	Uniform Loading at Deflection			Lateral Bracing Reduction Factor
			Span/180 (lbs)	Span/240 (lbs)	Span/360 (lbs)	
24	1,437	0.06	1,437	1,437	1,437	1.00
36	961	0.13	961	961	765	0.94
48	723	0.22	723	646	425	0.88
60	578	0.35	553	408	272	0.82
72	476	0.50	383	289	187	0.78
84	408	0.68	281	213	136	0.75
96	357	0.89	213	162	111	0.71
108	323	1.14	170	128	85	0.69
120	289	1.40	136	102	68	0.66
144	238	2.00	94	68	51	0.61
168	204	2.72	68	51	34	0.55
192	179	3.55	51	43	NR	0.51
216	162	4.58	43	34	NR	0.47
240	145	5.62	34	NR	NR	0.44
Note	NR - Not Recommended					

Refer to the General Specifications for loading information.

Column Loading - P1000T					
Unbraced Height (in)	Allowable Load at Slot Face (lbs)	Max Column Load Applied at C.G.			
		K=0.65 (lbs)	K=0.80 (lbs)	K=1.0 (lbs)	K=1.2 (lbs)
24	3,550	10,740	9,890	8,770	7,740
36	3,190	8,910	7,740	6,390	5,310
48	2,770	7,260	6,010	4,690	3,800
60	2,380	5,910	4,690	3,630	2,960
72	2,080	4,840	3,800	2,960	2,400
84	1,860	4,040	3,200	2,480	1,980
96	1,670	3,480	2,750	2,110	1,660
108	1,510	3,050	2,400	1,810	KL/r>200
120	1,380	2,700	2,110	KL/r>200	KL/r>200
144	1,150	2,180	1,660	KL/r>200	KL/r>200

Refer to the General Specifications for loading information.





Project:	<input type="text"/>
Architect / Engineer:	<input type="text"/>
Date:	<input type="text"/>
Phone:	<input type="text"/>
Contractor:	<input type="text"/>
Address:	<input type="text"/>
Notes:	<input type="text"/>


Approval Stamp:

KWIK HUS-EZ SCREW ANCHOR


PRODUCT DESCRIPTION

KWIK HUS EZ carbon steel anchors


Anchor System	Features and Benefits
 <p>Carbon Steel KH-EZ C 1/4" & 3/8"</p>	<ul style="list-style-type: none"> • OSHA Table 1926.1153 Table 1 compliant installation when installed with Hilti vacuum and DRS system or Hilti SafeSet™ hollow drill bit technology • Easy installation using impact tool or torque wrench
 <p>Carbon Steel 1/4" KH-EZ P, PM, PL</p>	<ul style="list-style-type: none"> • Product and length identification marks helps facilitate quality control after installation • Through fixture installation improves productivity and more accurate installation. • Thread design helps enable quality setting and exceptional load values in wide variety of base material strengths.
 <p>Carbon Steel KH-EZ 1/4"-3/4"</p>	<ul style="list-style-type: none"> • 1/4" diameter available in hex head countersunk head and pan head styles. • Anchor is fully removable. • Anchor diameter is same as drill bit diameter. No special diameter bit required. • Suitable for reduced edge distances and spacing.
 <p>Carbon Steel KH-EZ CRC 3/8"-3/4"</p>	<ul style="list-style-type: none"> • Corrosion resistant coating allows for use in outdoor moderate corrosive environments (KH-EZ CRC only). • Installation process allows for adjustability.




Uncracked concrete



Cracked concrete



Grout-filled concrete masonry



Seismic Design Categories A-F



SafeSet™ System with Hollow Drill Bit



Profis Anchor design software

Approvals/Listings	
ICC-ES (International Code Council)	ESR-3027 in concrete per ACI 318-14 Ch. 17 / ACI 355.2/ ICC-ES AC193 ESR-3056 in grout-filled CMU per ICC-ES AC106
City of Los Angeles	City of Los Angeles 2017 LABC Supplement (within ESR-3027 and ESR-3056)
Florida Building Code	2017 FBC w/ HVHZ (within ESR-3027 and ESR-3056)
FM (Factory Mutual)	Pipe hanger components for automatic sprinkler systems for KH-EZ I and KH-EZ E



MATERIAL SPECIFICATIONS

Heat treated carbon steel with a minimum zinc coating of 0.0003 inch (8 µm) thick in accordance with DIN EN ISO 4042.

KH-EZ CRC has mechanically deposited zinc coating with a minimum thickness of 0.0021 inch (53 µm) in accordance with ASTM B695, Class 55.

INSTALLATION PARAMETERS

Table 1 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC specifications

Setting information	Symbol	Units	Nominal anchor diameter														
			1/4		3/8				1/2			5/8			3/4		
Head style and coating			Hex, P, PM, PL, C head		Hex, C head		Hex, C head (Including CRC)		Hex head (Including CRC)			Hex head (Including CRC)			Hex head (Including CRC)		
Nominal bit diameter	d _{bit}	in.	1/4		3/8				1/2			5/8			3/4		
Minimum nominal embedment	h _{nom}	in.	1-5/8	2-1/2	1-5/8	2-1/8	2-1/2	3-1/4	2-1/4	3	4-1/4	3-1/4	4	5	4	6-1/4	
Minimum effective embedment	h _{ef}	in.	1.18	1.92	1.11	1.54	1.86	2.50	1.50	2.16	3.22	2.39	3.03	3.88	2.92	4.84	
Minimum hole depth	h _o	in.	2	2-7/8	1-7/8	2-3/8	2-3/4	3-1/2	2-5/8	3-3/8	4-5/8	3-5/8	4-3/8	5-3/8	4-3/8	6-5/8	
Minimum fixture hole diameter	d _h	in.	3/8		1/2				5/8			3/4			7/8		
Anchor Length = h _{nom} + t	ℓ				See ordering information												
Installation torque concrete ¹	T _{inst}	ft-lb (Nm)	18 (24)		19 (26)	40 (54)			45 (61)			85 (115)			95 ⁴ (129)		
Maximum impact wrench torque rating concrete ²	T _{impact,max}	ft-lb (Nm)	157 (213)		157 (213)	450 (610)			137 (186)	450 (610)		590 (800)			590 (800)		
Installation torque masonry KH-EZ (P, PM, PL, C)	T _{inst}	ft-lb (Nm)	21 (28)		22 (30)				34 (46)			38 (52)			70 (95)		
Installation torque masonry for KH-EZ CRC	T _{inst}	ft-lb (Nm)					20 (27)		25 (34)			35 (48)			45 (61)		
Maximum impact wrench torque rating masonry for KH-EZ (P, PM, PL, C) ^{2,3}	T _{impact,max}	ft-lb (Nm)	114 (155)		114 (155)			332 (450)		332 (450)			332 (450)			332 (450)	
Maximum impact wrench torque rating masonry for KH-EZ CRC ^{2,3}	T _{impact,max}	ft-lb (Nm)						100 (136)		100 (136)			332 (450)			332 (450)	
Wrench size		in.	7/16		9/16				3/4			15/16			1-1/8		


¹ T_{inst} is the maximum installation torque that may be applied with a torque wrench.

² Because of variability in measurement procedures, the published torque of an impact tool may not correlate properly with the above setting torques. Over torquing can damage the anchor and/or reduce its holding capacity.

³ For more information on KWIK HUS-EZ installed in masonry, see ESR-3056 and Design Information for Masonry in this section.

⁴ Maximum installation torque in concrete for 3/4-in diameter KH-EZ CRC is 85 ft-lbs. (115 Nm).

Figure 1 - Hilti KWIK HUS-EZ specifications



DESIGN INFORMATION IN CONCRETE PER ACI 318

ACI 318-14 Chapter 17 design

The load values contained in this section are Hilti Simplified Design Tables. The load tables in this section were developed using the Strength Design parameters and variables of ESR-3027 and the equations within ACI 318-14 Chapter 17. For a detailed explanation of the Hilti Simplified Design Tables, refer to section 3.1.8 of the North American Product Technical Guide, Volume 2: Anchor Fastening Technical Guide, Edition 19 (PTG Ed. 19). Data tables from ESR-3027 are not contained in this section, but can be found at www.icc-es.org or at www.hilti.com.

Table 2 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC design Strength with concrete / pullout failure in uncracked concrete^{1,2,3,4}

Nominal anchor diameter in. (mm)	Nominal Embed. Depth in. (mm)	Tension - ϕN_n				Shear - ϕV_n			
		$f'_c = 2,500$ psi (17.2 MPa) lb (kN)	$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)	$f'_c = 6,000$ psi (41.4 MPa) lb (kN)	$f'_c = 2,500$ psi (17.2 MPa) lb (kN)	$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)	$f'_c = 6,000$ psi (41.4 MPa) lb (kN)
1/4 (6.4)	1-5/8 (41)	585 (2.6)	620 (2.8)	675 (3.0)	765 (3.4)	1,075 (4.8)	1,180 (5.2)	1,360 (6.0)	1,670 (7.4)
	2-1/2 (64)	1,525 (6.8)	1,670 (7.4)	1,930 (8.6)	2,365 (10.5)	2,235 (9.9)	2,450 (10.9)	2,825 (12.6)	3,460 (15.4)
3/8 (9.5)	1-5/8 (41)	910 (4.0)	1,000 (4.4)	1,155 (5.1)	1,415 (6.3)	980 (4.4)	1,075 (4.8)	1,245 (5.5)	1,520 (6.8)
	2-1/8 (54)	1,490 (6.6)	1,635 (7.3)	1,885 (8.4)	2,310 (10.3)	1,605 (7.1)	1,760 (7.8)	2,030 (9.0)	2,485 (11.1)
	2-1/2 (64)	1,980 (8.8)	2,165 (9.6)	2,505 (11.1)	3,065 (13.6)	2,130 (9.5)	2,335 (10.4)	2,695 (12.0)	3,300 (14.7)
	3-1/4 (83)	3,085 (13.7)	3,375 (15.0)	3,900 (17.3)	4,775 (21.2)	6,640 (29.5)	7,275 (32.4)	8,400 (37.4)	10,290 (45.8)
1/2 (12.7)	2-1/4 (57)	1,645 (7.3)	1,800 (8.0)	2,080 (9.3)	2,550 (11.3)	1,770 (7.9)	1,940 (8.6)	2,240 (10.0)	2,745 (12.2)
	3 (76)	2,785 (12.4)	3,050 (13.6)	3,525 (15.7)	4,315 (19.2)	3,000 (13.3)	3,285 (14.6)	3,795 (16.9)	4,645 (20.7)
	4-1/4 (108)	5,070 (22.6)	5,555 (24.7)	6,415 (28.5)	7,855 (34.9)	10,920 (48.6)	11,965 (53.2)	13,815 (61.5)	16,920 (75.3)
5/8 (15.9)	3-1/4 (83)	3,240 (14.4)	3,550 (15.8)	4,100 (18.2)	5,025 (22.4)	3,490 (15.5)	3,825 (17.0)	4,415 (19.6)	5,410 (24.1)
	4 (102)	4,630 (20.6)	5,070 (22.6)	5,855 (26.0)	7,170 (31.9)	9,970 (44.3)	10,920 (48.6)	12,610 (56.1)	15,445 (68.7)
	5 (127)	6,705 (29.8)	7,345 (32.7)	8,485 (37.7)	10,390 (46.2)	14,445 (64.3)	15,825 (70.4)	18,270 (81.3)	22,380 (99.6)
3/4 (19.1)	4 (102)	4,380 (19.5)	4,795 (21.3)	5,540 (24.6)	6,785 (30.2)	9,430 (41.9)	10,330 (45.9)	11,930 (53.1)	14,610 (65.0)
	6-1/4 (159)	9,345 (41.6)	10,235 (45.5)	11,820 (52.6)	14,475 (64.4)	20,125 (89.5)	22,045 (98.1)	25,455 (113.2)	31,175 (138.7)

Table 3 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC design Strength with concrete / pullout failure in cracked concrete^{1,2,3,4,5}

Nominal anchor diameter in. (mm)	Nominal embed. in. (mm)	Tension - ϕN_n				Shear - ϕV_n			
		$f'_c = 2,500$ psi (17.2 MPa) lb (kN)	$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)	$f'_c = 6,000$ psi (41.4 MPa) lb (kN)	$f'_c = 2,500$ psi (17.2 MPa) lb (kN)	$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)	$f'_c = 6,000$ psi (41.4 MPa) lb (kN)
1/4 (6.4)	1-5/8 (41)	300 (1.3)	315 (1.4)	345 (1.5)	390 (1.7)	765 (3.4)	835 (3.7)	965 (4.3)	1,180 (5.2)
	2-1/2 (64)	760 (3.4)	830 (3.7)	960 (4.3)	1,175 (5.2)	1,585 (7.1)	1,735 (7.7)	2,000 (8.9)	2,450 (10.9)
3/8 (9.5)	1-5/8 (41)	475 (2.1)	520 (2.3)	600 (2.7)	730 (3.2)	695 (3.1)	760 (3.4)	880 (3.9)	1,080 (4.8)
	2-1/8 (54)	1,055 (4.7)	1,155 (5.1)	1,335 (5.9)	1,635 (7.3)	1,135 (5.0)	1,245 (5.5)	1,440 (6.4)	1,760 (7.8)
	2-1/2 (64)	1,400 (6.2)	1,535 (6.8)	1,775 (7.9)	2,170 (9.7)	1,510 (6.7)	1,655 (7.4)	1,910 (8.5)	2,340 (10.4)
	3-1/4 (83)	2,185 (9.7)	2,390 (10.6)	2,765 (12.3)	3,385 (15.1)	4,705 (20.9)	5,155 (22.9)	5,950 (26.5)	7,285 (32.4)
1/2 (12.7)	2-1/4 (57)	1,035 (4.6)	1,135 (5.0)	1,310 (5.8)	1,605 (7.1)	1,115 (5.0)	1,220 (5.4)	1,410 (6.3)	1,725 (7.7)
	3 (76)	1,755 (7.8)	1,920 (8.5)	2,220 (9.9)	2,715 (12.1)	1,890 (8.4)	2,070 (9.2)	2,390 (10.6)	2,925 (13.0)
	4-1/4 (108)	3,190 (14.2)	3,495 (15.5)	4,040 (18.0)	4,945 (22.0)	6,875 (30.6)	7,530 (33.5)	8,695 (38.7)	10,650 (47.4)
5/8 (15.9)	3-1/4 (83)	2,040 (9.1)	2,235 (9.9)	2,580 (11.5)	3,165 (14.1)	2,200 (9.8)	2,410 (10.7)	2,780 (12.4)	3,405 (15.1)
	4 (102)	3,140 (14.0)	3,510 (15.6)	3,845 (17.1)	4,515 (20.1)	6,760 (30.1)	7,560 (33.6)	8,280 (36.8)	9,725 (43.3)
	5 (127)	4,225 (18.8)	4,625 (20.6)	5,340 (23.8)	6,540 (29.1)	9,095 (40.5)	9,965 (44.3)	11,505 (51.2)	14,090 (62.7)
3/4 (19.1)	4 (102)	2,755 (12.3)	3,020 (13.4)	3,485 (15.5)	4,270 (19.0)	5,940 (26.4)	6,505 (28.9)	7,510 (33.4)	9,200 (40.9)
	6-1/4 (159)	5,885 (26.2)	6,445 (28.7)	7,440 (33.1)	9,115 (40.5)	12,670 (56.4)	13,880 (61.7)	16,030 (71.3)	19,630 (87.3)

1 See PTG Ed. 19 Section 3.1.8 to convert design strength value to ASD value.

2 Linear interpolation between embedment depths and concrete compressive strengths is not permitted.

3 Apply spacing, edge distance, and concrete thickness factors in Tables 6 through 15 as necessary. Compare to the steel values in Table 4. The lesser of the values is to be used for the design.

4 Tabular values are for normal weight concrete only. For lightweight concrete multiply design strength by λ_a as follows:

For sand-lightweight, $\lambda_a = 0.68$. For all-lightweight, $\lambda_a = 0.60$.

5 Tabular values are for static loads only. For seismic tension loads, multiply cracked concrete tabular values in tension by the following reduction factors:

1/4-in diameter by 1-5/8-in nominal embedment depth - $a_{N,seis} = 0.60$

All other sizes - $a_{N,seis} = 0.75$

No reduction needed for seismic shear. See PTG Ed. 19 Section 3.1.8 for additional information on seismic applications.

Table 4 - Steel design strength for Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC anchors^{1,2}

Anchor diameter in. (mm)	Nominal embedment depth in. (mm)			Tensile ³ φN _{sa} lb (kN)	Shear ⁴ φV _{sa} lb (kN)	Seismic shear ⁵ φV _{sa,eq} lb (kN)
1/4 (6.4)	1-5/8 (41)	2-1/2 (64)		3,945 (17.5)	930 (4.1)	835 (3.7)
3/8 (9.5)	1-5/8 (41)	2-1/8 (54)		5,980 (26.6)	2,200 (9.8)	2,200 (9.8)
	2-1/2 (64)	3-1/4 (83)		6,720 (29.9)	3,110 (13.8)	1,865 (8.3)
1/2 (12.7)	2-1/4 (57)	3 (76)	4-1/4 (108)	11,780 (52.4)	5,545 (24.7)	3,330 (14.8)
5/8 (15.9)	3-1/4 (83)	4 (102)	5 (127)	15,735 (70.0)	6,735 (30.0)	4,040 (18.0)
3/4 (19.1)	4 (102)	6-1/4 (159)		20,810 (92.6)	9,995 (44.5)	6,935 (30.8)


1 See PTG Ed. 19 Section 3.1.8 to convert design strength value to ASD value.

2 Hilti KWIK HUS-EZ anchors are to be considered brittle steel elements.

3 Tensile φN_{sa} = φ A_{se,N} f_{uta} as noted in ACI 318 Chapter 17.


4 Shear values determined by static shear tests with φV_{sa} < φ 0.60 A_{se,V} f_{uta} as noted in ACI 318 Chapter 17.

5 Seismic shear values determined by seismic shear tests with φV_{sa} ≤ φ 0.60 A_{se,V} f_{uta} as noted in ACI 318 Chapter 17.
See PTG Ed. 19 Section 3.1.8 for additional information on seismic applications.

Figure 2


For a specific edge distance, the permitted spacing is calculated as follows:

$$s \geq s_{\min,2} + \frac{(s_{\min,1} - s_{\min,2})}{(c_{\min,1} - c_{\min,2})} (c - c_{\min,2})$$


Table 5 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC specifications¹

Setting information	Symbol	Units	Nominal anchor diameter													
			1/4		3/8				1/2			5/8			3/4	
Effective minimum embedment	h_{ef}	in.	1.18	1.92	1.11	1.54	1.86	2.50	1.50	2.16	3.22	2.39	3.03	3.88	2.92	4.84
Minimum member thickness	h_{min}	in.	3-1/4	4-1/8	3-1/4	3-2/3	4	4-7/8	4-1/2	4-3/4	6-3/4	5	6	7	6	8-1/8
Case 1	$c_{min,1}$	in.	1.50						1.75							
	for $s_{min,1} \geq$	in.	3									4				
Case 2	$c_{min,2}$	in.	2	2.78	2.63	2.75	2.92	3.75	2.75	3.75	5.25	3.63	4.57	5.81	4.41	7.28
	for $s_{min,2} \geq$	in.	1.50		2.25				3							

1 Linear interpolation is permitted to establish an edge distance and spacing combination between Case 1 and Case 2.
Linear interpolation for a specific edge distance c, where c_{min,1} < c < c_{min,2} will determine the permissible spacings.

Table 8 - Load Adjustment Factors for 3/8-in. diameter Hilti KH-EZ, KH-EZ C and KH-EZ CRC in uncracked ^{1,2}

3/8-in. KH-EZ uncracked concrete		Spacing factor in tension f_{AN}				Edge distance factor in tension f_{RN}				Spacing factor in shear ³ f_{AV}				Edge distance in shear								Conc. thickness factor in shear ⁴ f_{HV}				
														⊥ toward edge f_{RV}				to and away from edge f_{RV}								
		Embedment	in.	1-5/8	2-1/8	2-1/2	3-1/4	1-5/8	2-1/8	2-1/2	3-1/4	1-5/8	2-1/8	2-1/2	3-1/4	1-5/8	2-1/8	2-1/2	3-1/4	1-5/8	2-1/8	2-1/2	3-1/4	1-5/8	2-1/8	2-1/2
h_{nom}	(mm)	(41)	(54)	(64)	(83)	(41)	(54)	(64)	(83)	(41)	(54)	(64)	(83)	(41)	(54)	(64)	(83)	(41)	(54)	(64)	(83)	(41)	(54)	(64)	(83)	
Spacing (s)/edge distance (c)/concrete thickness (h) - in. (mm)	1-1/2 (38)	n/a	n/a	n/a	n/a	0.58	0.62	0.63	0.57	n/a	n/a	n/a	n/a	0.49	0.32	0.25	0.08	0.58	0.62	0.50	0.17	n/a	n/a	n/a	n/a	
	2 (51)	n/a	n/a	n/a	n/a	0.76	0.75	0.75	0.66	n/a	n/a	n/a	n/a	0.75	0.49	0.38	0.13	0.76	0.75	0.75	0.26	n/a	n/a	n/a	n/a	
	2-1/4 (57)	0.84	0.74	0.70	0.65	0.86	0.82	0.81	0.70	0.65	0.62	0.60	0.55	0.90	0.59	0.46	0.16	0.90	0.82	0.81	0.31	n/a	n/a	n/a	n/a	
	2-1/2 (64)	0.88	0.77	0.72	0.67	0.95	0.91	0.88	0.75	0.67	0.63	0.61	0.55	1.00	0.69	0.54	0.18	1.00	0.91	0.88	0.37	n/a	n/a	n/a	n/a	
	3 (76)	0.95	0.82	0.77	0.70	1.00	1.00	1.00	0.85	0.71	0.66	0.63	0.56		0.90	0.71	0.24		1.00	1.00	0.48	n/a	n/a	n/a	n/a	
	3-1/4 (83)	0.99	0.85	0.79	0.72				0.90	0.72	0.67	0.64	0.57		1.00	0.80	0.27				0.54	0.95	n/a	n/a	n/a	
	3-1/2 (89)	1.00	0.88	0.81	0.73				0.95	0.74	0.68	0.65	0.58			0.89	0.30				0.61	0.98	n/a	n/a	n/a	
	4 (102)		0.93	0.86	0.77				1.00	0.78	0.71	0.68	0.59			1.00	0.37				0.74	1.00	0.91	0.84	n/a	
	4-1/2 (114)		0.99	0.90	0.80					0.81	0.73	0.70	0.60				0.44				0.88			0.89	n/a	
	4-3/4 (121)		1.00	0.93	0.82					0.83	0.75	0.71	0.60				0.48				0.96			0.91	0.639	
	5 (127)			0.95	0.83					0.84	0.76	0.72	0.61				0.52				1.00			0.94	0.655	
	6 (152)			1.00	0.90					0.91	0.81	0.76	0.63				0.68							1.00	0.718	
	7 (178)				0.97					0.98	0.86	0.81	0.65				0.86								0.775	
	8 (203)				1.00					1.00	0.91	0.85	0.67				1.00									0.829
	9 (229)										0.97	0.90	0.69													0.879
	10 (254)										1.00	0.94	0.71													0.927
	11 (279)											0.98	0.74													0.972
	12 (305)											1.00	0.76													1.000
	14 (356)												0.80													
	16 (406)												0.84													
	18 (457)												0.89													
	20 (508)												0.93													
	24 (610)												1.000													

Table 9 - Load Adjustment Factors for 3/8-in. diameter Hilti KH-EZ, KH-EZ C and KH-EZ CRC in cracked ^{1,2}

3/8-in. KH-EZ cracked concrete		Spacing factor in tension f_{AN}				Edge distance factor in tension f_{RN}				Spacing factor in shear ³ f_{AV}				Edge distance in shear								Conc. thickness factor in shear ⁴ f_{HV}			
														⊥ toward edge f_{RV}				to and away from edge f_{RV}							
		Embedment h_{nom}	in. (mm)	1-5/8 (41)	2-1/8 (54)	2-1/2 (64)	3-1/4 (83)	1-5/8 (41)	2-1/8 (54)	2-1/2 (64)	3-1/4 (83)	1-5/8 (41)	2-1/8 (54)	2-1/2 (64)	3-1/4 (83)	1-5/8 (41)	2-1/8 (54)	2-1/2 (64)	3-1/4 (83)	1-5/8 (41)	2-1/8 (54)	2-1/2 (64)	3-1/4 (83)		
Spacing (s)/edge distance (c)/concrete thickness (h) - in. (mm)	1-1/2 (38)	n/a	n/a	n/a	n/a	0.92	0.74	0.66	0.57	n/a	n/a	n/a	n/a	0.49	0.32	0.25	0.09	0.92	0.64	0.50	0.17	n/a	n/a	n/a	n/a
	2 (51)	n/a	n/a	n/a	n/a	1.00	0.90	0.79	0.66	n/a	n/a	n/a	n/a	0.76	0.50	0.39	0.13	1.00	0.90	0.77	0.26	n/a	n/a	n/a	n/a
	2-1/4 (57)	0.84	0.74	0.70	0.65	1.00	0.98	0.85	0.70	0.66	0.62	0.60	0.55	0.90	0.59	0.46	0.16	1.00	0.98	0.85	0.31	n/a	n/a	n/a	n/a
	2-1/2 (64)	0.88	0.77	0.72	0.67	1.00	1.00	0.92	0.75	0.67	0.63	0.61	0.55	1.00	0.69	0.54	0.18	1.00	1.00	0.92	0.37	n/a	n/a	n/a	n/a
	3 (76)	0.95	0.82	0.77	0.70	1.00		1.00	0.85	0.71	0.66	0.63	0.56	1.00	0.91	0.71	0.24	1.00	1.00	1.00	0.48	n/a	n/a	n/a	n/a
	3-1/4 (83)	0.99	0.85	0.79	0.72				0.90	0.73	0.67	0.64	0.57		1.00	0.80	0.27				0.55	0.95	n/a	n/a	n/a
	3-1/2 (89)	1.00	0.88	0.81	0.73				0.95	0.74	0.68	0.65	0.58			0.90	0.31				0.61	0.98	n/a	n/a	n/a
	4 (102)		0.93	0.86	0.77				1.00	0.78	0.71	0.68	0.59			1.00	0.37				0.75	1.00	0.91	0.84	n/a
	4-1/2 (114)		0.99	0.90	0.80					0.81	0.73	0.70	0.60				0.44				0.89		0.97	0.89	n/a
	4-3/4 (121)		1.00	0.93	0.82					0.83	0.75	0.71	0.60				0.48				0.97		1.00	0.92	0.64
	5 (127)			0.95	0.83					0.85	0.76	0.72	0.61				0.52				1.00			0.94	0.66
	6 (152)			1.00	0.90					0.92	0.81	0.77	0.63				0.69							1.00	0.72
	7 (178)				0.97					0.98	0.87	0.81	0.65				0.86								0.78
	8 (203)				1.00					1.00	0.92	0.85	0.67				1.00								0.83
	9 (229)										0.97	0.90	0.69												0.88
	10 (254)											1.00	0.94	0.72											0.93
	11 (279)												0.99	0.74											0.97
	12 (305)												1.00	0.76											1.00
	14 (356)													0.80											
	16 (406)													0.85											
	18 (457)													0.89											
	20 (508)													0.93											
	24 (610)													1.00											

1 Linear interpolation not permitted.

2 When combining multiple load adjustment factors (e.g. for a 4 anchor pattern in a corner with thin concrete member) the design can become very conservative. To optimize the design, use Hilti PROFIS Engineering software or perform anchor calculation using design equations from ACI 318-14 Chapter 17.

3 Spacing factor reduction in shear, f_{AV} , assumes an influence of a nearby edge. If no edge exists, then $f_{AV} = f_{AN}$.

4 Concrete thickness reduction factor in shear, f_{HV} , assumes an influence of a nearby edge. If no edge exists, then $f_{HV} = 1.0$.

If a reduction factor value is in a shaded cell, this indicates that this specific edge distance may not be permitted with a certain spacing (or vice versa). Check table 5 and figure 2 of this section to calculate permissible edge distance, spacing and concrete thickness combinations.

Table 16 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the soffit of uncracked lightweight concrete over metal deck^{1,2,3,4,5,6}


Nominal anchor diameter in.	Nominal embedment in. (mm)	Installation in lower flute				Installation in upper flute			
		Tension - ϕN_n		Shear - ϕV_n		Tension - ϕN_n		Shear - ϕV_n	
		$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)	$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)	$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)	$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)
1/4	1-5/8 (41)	545 (2.4)	595 (2.6)	725 (3.2)	725 (3.2)	670 (3.0)	730 (3.2)	725 (3.2)	725 (3.2)
	2-1/2 (64)	1,220 (5.4)	1,410 (6.3)	1,325 (5.9)	1,325 (5.9)	1,275 (5.7)	1,470 (6.5)	1,960 (8.7)	1,960 (8.7)
3/8	1-5/8 (41)	845 (3.8)	975 (4.3)	905 (4.0)	905 (4.0)	970 (4.3)	1,120 (5.0)	2,200 (9.8)	2,200 (9.8)
	2-1/2 (64)	1,455 (6.5)	1,680 (7.5)	905 (4.0)	905 (4.0)	1,900 (8.5)	2,195 (9.8)	3,655 (16.3)	3,655 (16.3)
	3-1/4 (83)	2,550 (11.3)	2,945 (13.1)	2,165 (9.6)	2,165 (9.6)	n/a	n/a	n/a	n/a
1/2	2-1/4 (57)	850 (3.8)	980 (4.4)	965 (4.3)	965 (4.3)	905 (4.0)	1,045 (4.6)	4,710 (21.0)	4,710 (21.0)
	3 (76)	1,990 (8.9)	2,300 (10.2)	1,750 (7.8)	1,750 (7.8)	n/a	n/a	n/a	n/a
	4-1/4 (108)	3,485 (15.5)	4,025 (17.9)	2,155 (9.6)	2,155 (9.6)	n/a	n/a	n/a	n/a
5/8	3-1/4 (83)	2,715 (12.1)	3,135 (13.9)	2,080 (9.3)	2,080 (9.3)	n/a	n/a	n/a	n/a
	5 (127)	6,170 (27.4)	7,125 (31.7)	2,515 (11.2)	2,515 (11.2)	n/a	n/a	n/a	n/a
3/4	4 (102)	2,715 (12.1)	3,135 (13.9)	2,255 (10.0)	2,255 (10.0)	n/a	n/a	n/a	n/a

Table 17 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the soffit of cracked lightweight concrete over metal deck^{1,2,3,4,5,6}

Nominal anchor diameter in.	Nominal embedment in. (mm)	Installation in lower flute				Installation in upper flute			
		Tension - ϕN_n ⁷		Shear - ϕV_n ⁸		Tension - ϕN_n ⁷		Shear - ϕV_n ⁸	
		$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)	$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)	$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)	$f'_c = 3,000$ psi lb (kN)	$f'_c = 4,000$ psi lb (kN)
1/4	1-5/8 (41)	280 (1.2)	305 (1.4)	725 (3.2)	725 (3.2)	340 (1.5)	370 (1.6)	725 (3.2)	725 (3.2)
	2-1/2 (64)	605 (2.7)	700 (3.1)	1,325 (5.9)	1,325 (5.9)	635 (2.8)	735 (3.3)	1,960 (8.7)	1,960 (8.7)
3/8	1-5/8 (41)	525 (2.3)	605 (2.7)	905 (4.0)	905 (4.0)	770 (3.4)	890 (4.0)	2,200 (9.8)	2,200 (9.8)
	2-1/2 (64)	1,035 (4.6)	1,195 (5.3)	905 (4.0)	905 (4.0)	1,345 (6.0)	1,555 (6.9)	3,655 (16.3)	3,655 (16.3)
	3-1/4 (83)	1,805 (8.0)	2,085 (9.3)	2,165 (9.6)	2,165 (9.6)	n/a	n/a	n/a	n/a
1/2	2-1/4 (57)	535 (2.4)	620 (2.8)	965 (4.3)	965 (4.3)	640 (2.8)	740 (3.3)	4,710 (21.0)	4,710 (21.0)
	3 (76)	1,255 (5.6)	1,450 (6.4)	1,750 (7.8)	1,750 (7.8)	n/a	n/a	n/a	n/a
	4-1/4 (108)	2,195 (9.8)	2,535 (11.3)	2,155 (9.6)	2,155 (9.6)	n/a	n/a	n/a	n/a
5/8	3-1/4 (83)	1,710 (7.6)	1,975 (8.8)	2,080 (9.3)	2,080 (9.3)	n/a	n/a	n/a	n/a
	5 (127)	3,885 (17.3)	4,485 (20.0)	2,515 (11.2)	2,515 (11.2)	n/a	n/a	n/a	n/a
3/4	4 (102)	1,710 (7.6)	1,975 (8.8)	2,255 (10.0)	2,255 (10.0)	n/a	n/a	n/a	n/a

- 1 See PTG Ed. 19 Section 3.1.8 to convert design strength value to ASD value.
- 2 Linear interpolation between embedment depths and concrete compressive strengths is not permitted.
- 3 Tabular value is for one anchor per flute. Minimum spacing along the length of the flute is $3 \times h_{nom}$ (nominal embedment).
- 4 Tabular values are lightweight concrete and no additional reduction factor is needed.
- 5 No additional reduction factors for spacing or edge distance need to be applied.
- 6 Comparison to steel values in table 4 is not required. Values in tables 16 and 17 control.
- 7 Tabular values are for static loads only. Seismic design is not permitted for uncracked concrete. For seismic tension loads, multiply cracked concrete tabular values in tension only by $\alpha_{N,seis} = 0.75$.
See PTG Ed. 19 Section 3.1.8 for additional information on seismic applications.
- 8 For the following anchor sizes, an additional factor for seismic shear must be applied to the cracked concrete tabular values for seismic conditions:
1/4-inch diameter - $\alpha_{V,seis} = 0.75$
3/8-inch diameter - $\alpha_{V,seis} = 0.60$
1/2-inch diameter - $\alpha_{V,seis} = 0.60$
5/8-inch diameter - $\alpha_{V,seis} = 0.60$
3/4-inch diameter - $\alpha_{V,seis} = 0.70$

Figure 3 – Installation of Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in soffit of concrete over steel deck floor and roof assemblies¹



- 1 Anchors may be placed in the upper or lower flute of the steel deck profile provided the minimum concrete cover above the drilled hole is satisfied. Anchors in the lower flute may be installed with a maximum 1-inch offset in either direction from the center of the flute. The offset distance may be increased proportionally for profiles with lower flute widths greater than those shown provided the minimum lower flute edge distance is also satisfied.

Figure 4 – Installation of Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC on the top of sand-lightweight concrete over metal floor and roof assemblies




Table 18 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the top of uncracked concrete over metal deck^{1,2,3,4,5}

Nominal anchor diameter in.	Nominal embedment depth in. (mm)	Tension - ϕN_n		Shear - ϕV_n	
		$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)	$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)
1/4	1-5/8 (41)	620 (2.8)	675 (3.0)	1,180 (5.2)	1,360 (6.0)
3/8	1-5/8 (41)	1,000 (4.4)	1,155 (5.1)	1,075 (4.8)	1,245 (5.5)

Table 19 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the top of cracked concrete over metal deck^{1,2,3,4,5}

Nominal anchor diameter in.	Nominal embed. depth in. (mm)	Tension - ϕN_n		Shear - ϕV_n	
		$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)	$f'_c = 3,000$ psi (20.7 MPa) lb (kN)	$f'_c = 4,000$ psi (27.6 MPa) lb (kN)
1/4	1-5/8 (41)	315 (1.4)	345 (1.5)	835 (3.7)	965 (4.3)
3/8	1-5/8 (41)	520 (2.3)	600 (2.7)	760 (3.4)	880 (3.9)

- See PTG Ed. 19 Section 3.1.8 to convert design strength value to ASD value.
- Linear interpolation between embedment depths and concrete compressive strengths is not permitted.
- Apply spacing, edge distance, and concrete thickness factors in tables 20 and 21 as necessary. Compare to the steel values in table 4. The lesser of the values is to be used for the design.
- Tabular values are for normal weight concrete only. For lightweight concrete multiply design strength by λ_a as follows:
for sand-lightweight, $\lambda_a = 0.68$; for all-lightweight, $\lambda_a = 0.60$
- Tabular values are for static loads only. Seismic design is not permitted for uncracked concrete. For seismic tension loads, multiply cracked concrete tabular values in tension by the following reduction factors:
1/4-inch diameter - $\alpha_{N,seis} = 0.60$
3/8-inch diameter - $\alpha_{N,seis} = 0.75$.
No reduction needed for seismic shear. See PTG Ed. 19 Section 3.1.8 for additional information on seismic applications.

Table 20 - Load adjustment factors for Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the top of uncracked concrete over metal deck^{1,2}

1/4-in. and 3/8-in. KH-EZ uncracked concrete over metal deck		Spacing factor in tension f_{AN}		Edge distance factor in tension f_{RN}		Spacing factor in shear ³ f_{AV}		Edge distance in shear				Conc. thickness factor in shear ⁴ f_{HV}	
								⊥ toward edge f_{RV}		to and away from edge f_{RV}			
Anchor diameter d_a	in. (mm)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)
Nominal embed. h_{nom}	in. (mm)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)
Spacing (s)/edge distance (c_e)/concrete thickness (h) - in. (mm)	1-3/4 (44)	n/a	n/a	0.44	0.58	n/a	n/a	0.44	0.58	0.44	0.58	n/a	n/a
	2 (51)	n/a	n/a	0.50	0.67	n/a	n/a	0.50	0.67	0.50	0.67	n/a	n/a
	2-1/2 (64)	n/a	n/a	0.63	0.83	n/a	n/a	0.63	0.83	0.63	0.83	0.78	0.83
	3 (76)	0.92	0.95	0.75	1.00	0.68	0.71	0.75	1.00	0.75	1.00	0.85	0.91
	3-1/4 (83)	0.96	0.99	0.81		0.70	0.72	0.81		0.81			
	3-1/2 (89)	0.99	1.00	0.88		0.71	0.74	0.88		0.88			
	4 (102)	1.00		1.00		0.74	0.78	1.00		1.00			
	4-1/2 (114)					0.77	0.81						
	5 (127)					0.80	0.84						
	5-1/2 (140)					0.83	0.88						
	6 (152)					0.86	0.91						
	6-1/2 (165)					0.89	0.95						
	7 (178)					0.92	0.98						
	7-1/2 (191)					0.95	1.00						
	8 (203)					0.98							
9 (229)					1.00								

Table 21 - Load adjustment factors for Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the top of cracked concrete over metal deck^{1,2}

1/4-in. and 3/8-in. KH-EZ cracked concrete over metal deck		Spacing factor in tension f_{AN}		Edge distance factor in tension f_{RN}		Spacing factor in shear ³ f_{AV}		Edge distance in shear				Conc. thickness factor in shear ⁴ f_{HV}	
								⊥ toward edge f_{RV}		to and away from edge f_{RV}			
Anchor diameter d_a	in. (mm)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)	1/4 (6.4)	3/8 (9.5)
Nominal embed. h_{nom}	in. (mm)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)	1-5/8 (41)
Spacing (s)/edge distance (c_e)/concrete thickness (h) - in. (mm)	1-3/4 (44)	n/a	n/a	0.99	1.00	n/a	n/a	0.51	0.62	0.99	1.00	n/a	n/a
	2 (51)	n/a	n/a	1.00		n/a	n/a	0.62	0.76	1.00		n/a	n/a
	2-1/2 (64)	n/a	n/a			n/a	n/a	0.87	1.00			0.78	0.83
	3 (76)	0.92	0.95			0.68	0.71	1.00				0.85	0.91
	3-1/4 (83)	0.96	0.99			0.70	0.73						
	3-1/2 (89)	0.99	1.00			0.71	0.74						
	4 (102)	1.00				0.74	0.78						
	4-1/2 (114)					0.77	0.81						
	5 (127)					0.80	0.85						
	5-1/2 (140)					0.83	0.88						
	6 (152)					0.86	0.92						
	6-1/2 (165)					0.89	0.95						
	7 (178)					0.92	0.98						
	7-1/2 (191)					0.95	1.00						
	8 (203)					0.98							
9 (229)					1.00								

1 Linear interpolation not permitted.

2 When combining multiple load adjustment factors (e.g. for a 4 anchor pattern in a corner with thin concrete member) the design can become very conservative. To optimize the design, use Hilti PROFIS Engineering software or perform anchor calculation using design equations from ACI 318-14 Chapter 17.

3 Spacing factor reduction in shear, f_{AV} , assumes an influence of a nearby edge. If no edge exists, then $f_{AV} = f_{AN}$.

4 Concrete thickness reduction factor in shear, f_{HV} , assumes an influence of a nearby edge. If no edge exists, then $f_{HV} = 1.0$.

- For concrete thickness greater than or equal to 3-1/4-inches, the anchor can be designed using either table 2 or table 3 of this section.

DESIGN INFORMATION IN CONCRETE PER CSA A23.3

Limit State Design of anchors is described in the provisions of CSA A23.3-14 Annex D for post-installed anchors tested and assessed in accordance with ACI 355.2 for mechanical anchors and ACI 355.4 for adhesive anchors. This section contains the Limit State Design tables with unfactored characteristic loads that are based on the published loads in ICC Evaluation Services ESR-3027. These tables are followed by factored resistance tables. The factored resistance tables have characteristic design loads that are prefactored by the applicable reduction factors for a single anchor with no anchor-to-anchor spacing or edge distance adjustments for the convenience of the user of this document. All the figures in the previous ACI 318-14 Chapter 17 design section are applicable to Limit State Design and the tables will reference these figures.

For a detailed explanation of the tables developed in accordance with CSA A23.3-14 Annex D, refer to Section 3.1.8. Technical assistance is available by contacting Hilti Canada at (800) 363-4458 or at www.hilti.com.

Table 22 - Steel resistance for Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC carbon steel screw anchor^{1,2}



Nominal anchor diameter in.	Nominal embedment in. (mm)			Tensile ³ N_{sar} lb (kN)	Shear ⁴ V_{sar} lb (kN)	Seismic shear ⁵ $V_{sar,eq}$ lb (kN)
1/4	1-5/8 (41)	2-1/2 (64)		3,370 (15.0)	855 (3.8)	770 (3.4)
3/8	1-5/8 (41)	2-1/8 (54)		5,475 (24.4)	2,030 (9.0)	2,030 (9.0)
	2-1/2 (64)	3-1/4 (83)		6,150 (27.4)	2,865 (12.7)	1,720 (7.7)
1/2	2-1/4 (57)	3 (76)	4-1/4 (108)	10,780 (48.0)	5,110 (22.7)	3,065 (13.6)
5/8	3-1/4 (83)	4 (102)	5 (127)	14,405 (64.1)	6,200 (27.6)	3,720 (16.5)
3/4	4 (102)	6-1/4 (159)		19,050 (84.7)	9,205 (40.9)	6,385 (28.4)

1 See PTG Ed. 19 Section 3.1.8 to convert design strength value to ASD value.

2 Hilti KWIK HUS-EZ carbon steel screw anchors are to be considered brittle steel elements.

3 Tensile $N_{sar} = A_{se,N} \phi_s f_{uta} R$ as noted in CSA A23.3-14 Annex D.

4 Shear determined by static shear tests with $V_{sar} < 0.6 A_{se,V} \phi_s f_{uta} R$ as noted in CSA A23.3-14 Annex D.

5 Seismic shear values determined by seismic shear tests with $V_{sar,eq} \leq 0.60 A_{se,V} \phi_s f_{uta} R$ as noted in CSA A23.3-14 Annex D. See PTG Ed. 19 Section 3.1.9 for additional information on seismic applications.

Table 23 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC design information in accordance with CSA A23.3-14 Annex D1¹

Design parameter	Symbol	Units	Nominal anchor diameter														Ref		
			1/4		3/8				1/2			5/8			3/4				
Head Style and coating			Hex, P, PM, PL, C head		Hex, C head		Hex, C head (Including CRC)		Hex head (Including CRC)			Hex head (Including CRC)			Hex head (Including CRC)				
Nominal anchor diameter	d _a	in. (mm)	0.25 (6.4)		0.375 (9.5)				0.5 (12.7)			0.625 (15.9)			0.75 (19.1)				
Effective embedment ²	h _{ef}	in. (mm)	1.18 (30)	1.92 (49)	1.11 (28)	1.54 (39)	1.86 (47)	2.50 (64)	1.52 (39)	2.16 (55)	3.22 (82)	2.39 (61)	3.03 (77)	3.88 (99)	2.92 (74)	4.84 (123)			
Min. nominal embedment ²	h _{nom}	in. (mm)	1-5/8 (41)	2-1/2 (64)	1-5/8 (41)	2-1/8 (54)	2-1/2 (64)	3-1/4 (83)	2-1/4 (57)	3 (76)	4-1/4 (108)	3-1/4 (83)	4 (102)	5 (127)	4 (102)	6-1/4 (159)			
Minimum concrete thickness ³	h _{min}	in. (mm)	3-1/4 (83)	4-1/8 (105)	3-1/4 (83)	3-2/3 (93)	4 (102)	4-3/4 (121)	4-1/2 (114)	4-3/4 (121)	6-3/4 (171)	5 (127)	6 (152)	7 (178)	6 (152)	8-1/8 (206)			
Critical edge distance	c _{ac}	in. (mm)	2 (51)	2.78 (71)	2.63 (67)	2.75 (70)	2.92 (74)	3.75 (95)	2.75 (70)	3.75 (95)	5.25 (133)	3.63 (92)	4.57 (116)	5.82 (148)	4.41 (112)	7.28 (185)			
Minimum spacing at critical edge distance	s _{min,cac}	in. (mm)	1.5 (38)		2.25 (57)							3 (76)							
Minimum edge distance	c _{min}	in. (mm)	1.50 (38)						1.75 (44)										
Minimum anchor spacing at minimum edge distance	for s >	in. (mm)	3.0 (76)									4 (102)							
Minimum hole depth in concrete	h ₀	in. (mm)	2 (51)	2-7/8 (73)	1-7/8 (48)	2-3/8 (60)	2-3/4 (70)	3-1/2 (89)	2-5/8 (67)	3-3/8 (86)	4-5/8 (117)	3-5/8 (92)	4-3/8 (111)	5-3/8 (137)	4-3/8 (111)	6-5/8 (168)			
Minimum specified ultimate strength	f _{uta}	psi (N/mm ²)	125,000 (860)		106,975 (738)		120,300 (830)		112,540 (776)			90,180 (622)			81,600 (563)				
Effective tensile stress area	A _{se,N}	in ² (mm ²)	0.045 (29.0)		0.086 (55.5)				0.161 (103.9)			0.268 (172.9)			0.392 (252.9)				
Steel embed. material resistance factor for reinforcement	Φ _s	-	0.85														8.4.3		
Resistance modification factor for tension, steel failure modes ⁴	R	-	0.70														D.5.3		
Resistance modification factor for shear, steel failure modes ⁴	R	-	0.65														D.5.3		
Factored steel resistance in tension	N _{sar}	lb (kN)	3,370 (15.0)		5,475 (24.4)		6,150 (27.4)		10,780 (48.0)			14,405 (64.1)			19,050 (84.7)		D.6.1.2		
Factored steel resistance in shear	V _{sar}	lb (kN)	855 (3.8)		2,030 (9.0)		2,865 (12.7)		5,110 (22.7)			6,200 (27.6)			9,205 (40.9)		D.7.1.2		
Factored steel resistance in shear, seismic	V _{sar,eq}	lb (kN)	770 (3.4)		2,030 (9.0)		1,720 (7.7)		3,065 (13.6)			3,720 (16.5)			6,385 (28.4)				
Coeff. for factored conc. breakout resistance, uncracked concrete	k _{c,uncr}	lb	10						11.25								D.6.2.2		
Coeff. for factored conc. breakout resistance, cracked concrete	k _{c,cr}	-	7														D.6.2.2		
Modification factor for anchor resistance, tension, uncracked concrete ⁵	Ψ _{c,N}	-	1.0														D.6.2.6		
Anchor category	-	-	3	1														D.5.3 (c)	
Concrete material resistance factor	Φ _c	-	0.65														8.4.2		
Resistance modification factor for tension and shear, concrete failure modes, Condition B ⁶	R	-	0.75	1.00														D.5.3 (c)	
Factored pullout resistance in 20 MPa uncracked concrete ⁷	N _{pr,uncr}	lb (kN)	665 (3.0)	1,645 (7.3)	NA													D.6.3.2	
Factored pullout resistance in 20 MPa cracked concrete ⁷	N _{pr,cr}	lb (kN)	340 (1.5)	815 (3.6)	510 (2.3)	NA												D.6.3.2	
Factored seismic pullout resistance in 20 MPa cracked concrete ⁷	N _{pr,eq}	lb (kN)	275 (1.2)	815 (3.6)	510 (2.3)	NA												D.6.3.2	

1 Design information in this table is taken from ICC-ES ESR-3027, dated February, 2016, tables 2, 3, and 4, and converted for use with CSA A23.3-14 Annex D.

2 See Figure 1 on Page 2 of this document.

3 For concrete over metal deck applications where the concrete thickness over the top flute is less than h_{min} in this table, see figure 4 and tables 20 and 21 of this document.

4 The KWIK HUS-EZ is considered a brittle steel element as defined by CSA A23.3-14 Annex D section D.2.

5 For all design cases, $\psi_{c,N} = 1.0$. The appropriate coefficient for breakout resistance for cracked concrete ($k_{c,cr}$) or uncracked concrete ($k_{c,uncr}$) must be used.

6 For use with the load combinations of CSA A23.3-14 chapter 8. Condition B applies where supplementary reinforcement in conformance with CSA A23.3-14 section D.5.3 is not provided, or where pullout or pryout strength governs. For cases where the presence of supplementary reinforcement can be verified, the resistance modification factors associated with Condition A may be used.

7 For all design cases, $\psi_{c,p} = 1.0$. NA (not applicable) denotes that this value does not control for design. See section 4.1.4 of ESR-3027 for additional information.

KWIK HUS-EZ Screw Anchor Technical Supplement

Table 24 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC carbon steel screw anchor factored resistance with concrete/pullout failure in uncracked concrete^{1,2,3,4}



Nominal anchor diameter in.	Effective embed. in. (mm)	Nominal embed. in. (mm)	Tension - N_t				Shear - V_s			
			$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)
1/4	1.18 (30)	1-5/8 (41)	665 (3.0)	710 (3.2)	750 (3.3)	820 (3.6)	805 (3.6)	900 (4.0)	985 (4.4)	1,135 (5.1)
	1.92 (49)	2-1/2 (64)	1,645 (7.3)	1,840 (8.2)	2,015 (9.0)	2,325 (10.4)	2,225 (9.9)	2,490 (11.1)	2,725 (12.1)	3,145 (14.0)
3/8	1.11 (28)	1-5/8 (41)	980 (4.4)	1,095 (4.9)	1,200 (5.3)	1,385 (6.2)	980 (4.4)	1,095 (4.9)	1,200 (5.3)	1,385 (6.2)
	1.54 (39)	2-1/8 (54)	1,600 (7.1)	1,785 (8.0)	1,960 (8.7)	2,260 (10.1)	1,600 (7.1)	1,785 (8.0)	1,960 (8.7)	2,260 (10.1)
	1.86 (47)	2-1/2 (64)	2,120 (9.4)	2,375 (10.6)	2,600 (11.6)	3,000 (13.3)	2,120 (9.4)	2,375 (10.6)	2,600 (11.6)	3,000 (13.3)
	2.50 (64)	3-1/4 (83)	3,305 (14.7)	3,695 (16.4)	4,050 (18.0)	4,675 (20.8)	3,305 (14.7)	3,695 (16.4)	4,050 (18.0)	4,675 (20.8)
	1.52 (39)	2-1/4 (57)	1,765 (7.8)	1,970 (8.8)	2,160 (9.6)	2,495 (11.1)	1,765 (7.8)	1,970 (8.8)	2,160 (9.6)	2,495 (11.1)
1/2	2.16 (55)	3 (76)	2,990 (13.3)	3,340 (14.9)	3,660 (16.3)	4,225 (18.8)	2,990 (13.3)	3,340 (14.9)	3,660 (16.3)	4,225 (18.8)
	3.22 (82)	4-1/4 (108)	5,440 (24.2)	6,080 (27.0)	6,660 (29.6)	7,690 (34.2)	10,875 (48.4)	12,160 (54.1)	13,320 (59.3)	15,380 (68.4)
	2.39 (61)	3-1/4 (83)	3,475 (15.5)	3,890 (17.3)	4,260 (18.9)	4,920 (21.9)	3,475 (15.5)	3,890 (17.3)	4,260 (18.9)	4,920 (21.9)
5/8	3.03 (77)	4 (102)	4,985 (22.2)	5,573 (24.8)	6,105 (27.2)	7,049 (31.4)	10,736 (47.8)	12,004 (53.4)	13,149 (58.5)	15,183 (67.5)
	3.88 (99)	5 (127)	7,195 (32.0)	8,040 (35.8)	8,810 (39.2)	10,170 (45.2)	14,385 (64.0)	16,085 (71.5)	17,620 (78.4)	20,345 (90.5)
	2.92 (74)	4 (102)	4,695 (20.9)	5,250 (23.4)	5,750 (25.6)	6,640 (29.5)	9,390 (41.8)	10,500 (46.7)	11,505 (51.2)	13,280 (59.1)
3/4	4.84 (123)	6-1/4 (159)	10,020 (44.6)	11,205 (49.8)	12,275 (54.6)	14,170 (63.0)	20,040 (89.2)	22,410 (99.7)	24,545 (109.2)	28,345 (126.1)

Table 25 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC carbon steel screw anchor factored resistance with concrete/pullout failure in cracked concrete^{1,2,3,4,5}



Nominal anchor diameter in.	Effective embed. in. (mm)	Nominal embed. in. (mm)	Tension - N_t				Shear - V_s			
			$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)
1/4	1.18 (30)	1-5/8 (41)	340 (1.5)	360 (1.6)	385 (1.7)	415 (1.9)	565 (2.5)	630 (2.8)	690 (3.1)	795 (3.5)
	1.92 (49)	2-1/2 (64)	815 (3.6)	910 (4.1)	1,000 (4.4)	1,155 (5.1)	1,560 (6.9)	1,740 (7.7)	1,910 (8.5)	2,205 (9.8)
3/8	1.11 (28)	1-5/8 (41)	510 (2.3)	570 (2.5)	620 (2.8)	720 (3.2)	685 (3.0)	765 (3.4)	840 (3.7)	970 (4.3)
	1.54 (39)	2-1/8 (54)	1,120 (5.0)	1,250 (5.6)	1,370 (6.1)	1,585 (7.0)	1,120 (5.0)	1,250 (5.6)	1,370 (6.1)	1,585 (7.0)
	1.86 (47)	2-1/2 (64)	1,485 (6.6)	1,660 (7.4)	1,820 (8.1)	2,100 (9.3)	1,485 (6.6)	1,660 (7.4)	1,820 (8.1)	2,100 (9.3)
	2.50 (64)	3-1/4 (83)	2,315 (10.3)	2,590 (11.5)	2,835 (12.6)	3,275 (14.6)	2,315 (10.3)	2,590 (11.5)	2,835 (12.6)	3,275 (14.6)
	1.52 (39)	2-1/4 (57)	1,095 (4.9)	1,225 (5.5)	1,345 (6.0)	1,550 (6.9)	1,095 (4.9)	1,225 (5.5)	1,345 (6.0)	1,550 (6.9)
1/2	2.16 (55)	3 (76)	1,860 (8.3)	2,080 (9.2)	2,275 (10.1)	2,630 (11.7)	1,860 (8.3)	2,080 (9.2)	2,275 (10.1)	2,630 (11.7)
	3.22 (82)	4-1/4 (108)	3,385 (15.1)	3,785 (16.8)	4,145 (18.4)	4,785 (21.3)	6,765 (30.1)	7,565 (33.7)	8,290 (36.9)	9,570 (42.6)
	2.39 (61)	3-1/4 (83)	2,165 (9.6)	2,420 (10.8)	2,650 (11.8)	3,060 (13.6)	2,165 (9.6)	2,420 (10.8)	2,650 (11.8)	3,060 (13.6)
5/8	3.03 (77)	4 (102)	3,139 (14.0)	3,509 (15.6)	3,844 (17.1)	4,439 (19.7)	6,760 (30.1)	7,558 (33.6)	8,279 (36.8)	9,560 (42.5)
	3.88 (99)	5 (127)	4,475 (19.9)	5,005 (22.3)	5,480 (24.4)	6,330 (28.2)	8,950 (39.8)	10,005 (44.5)	10,965 (48.8)	12,660 (56.3)
	2.92 (74)	4 (102)	2,920 (13.0)	3,265 (14.5)	3,580 (15.9)	4,130 (18.4)	5,845 (26.0)	6,535 (29.1)	7,155 (31.8)	8,265 (36.8)
3/4	4.84 (123)	6-1/4 (159)	6,235 (27.7)	6,970 (31.0)	7,635 (34.0)	8,820 (39.2)	12,470 (55.5)	13,945 (62.0)	15,275 (67.9)	17,635 (78.4)

1 See PTG Ed. 19 Section 3.1.8 to convert factored resistance value to ASD value.

2 Linear interpolation between embedment depths and concrete compressive strengths is not permitted.

3 Apply spacing, edge distance, and concrete thickness factors in tables 6 to 15 as necessary. Compare to the steel values in table 22. The lesser of the values is to be used for the design.

4 Tabular values are for normal-weight concrete only. For lightweight concrete multiply design strength by λ_a as follows: for sand-lightweight, $\lambda_a = 0.68$; for all-lightweight, $\lambda_a = 0.60$

5 Tabular values are for static loads only. Seismic design is not permitted for uncracked concrete. For seismic tension loads, multiply cracked concrete tabular values in tension by the following reduction factors:

1/4-in diameter by 1-5/8-in nominal embedment depth - $\alpha_{N,seis} = 0.60$ All other sizes - $\alpha_{N,seis} = 0.75$

No reduction needed for seismic shear. See PTG Ed. 19 Section 3.1.8 for additional information on seismic applications.

Table 26 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the soffit of uncracked lightweight concrete over metal deck^{1,2,3,4,5,6}



Nominal anchor diameter in.	Nominal embedment in. (mm)	Installation in lower flute				Installation in upper flute			
		Tension - N_r		Shear - V_r		Tension - N_r		Shear - V_r	
		$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)
1/4	1-5/8 (41)	585 (2.6)	660 (2.9)	665 (3.0)	665 (3.0)	720 (3.2)	810 (3.6)	665 (3.0)	665 (3.0)
	2-1/2 (64)	1,200 (5.3)	1,470 (6.5)	1,220 (5.4)	1,220 (5.4)	1,255 (5.6)	1,535 (6.8)	1,805 (8.0)	1,805 (8.0)
3/8	1-5/8 (41)	830 (3.7)	1,020 (4.5)	835 (3.7)	835 (3.7)	950 (4.2)	1,165 (5.2)	2,030 (9.0)	2,030 (9.0)
	2-1/2 (64)	1,430 (6.4)	1,755 (7.8)	835 (3.7)	835 (3.7)	1,865 (8.3)	2,285 (10.2)	3,365 (15.0)	3,365 (15.0)
	3-1/4 (83)	2,505 (11.1)	3,070 (13.7)	1,990 (8.9)	1,990 (8.9)	n/a	n/a	n/a	n/a
1/2	2-1/4 (57)	835 (3.7)	1,020 (4.5)	885 (3.9)	885 (3.9)	890 (4.0)	1,090 (4.8)	4,335 (19.3)	4,335 (19.3)
	3 (76)	1,955 (8.7)	2,395 (10.7)	1,615 (7.2)	1,615 (7.2)	n/a	n/a	n/a	n/a
	4-1/4 (108)	3,425 (15.2)	4,195 (18.7)	1,985 (8.8)	1,985 (8.8)	n/a	n/a	n/a	n/a
5/8	3-1/4 (83)	2,670 (11.9)	3,270 (14.5)	1,915 (8.5)	1,915 (8.5)	n/a	n/a	n/a	n/a
	5 (127)	6,070 (27.0)	7,430 (33.1)	2,315 (10.3)	2,315 (10.3)	n/a	n/a	n/a	n/a
3/4	4 (102)	2,670 (11.9)	3,270 (14.5)	2,075 (9.2)	2,075 (9.2)	n/a	n/a	n/a	n/a

Table 27 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC in the soffit of cracked lightweight concrete over metal deck^{1,2,3,4,5,6}



Nominal anchor diameter in.	Nominal embedment in. (mm)	Installation in lower flute				Installation in upper flute			
		Tension - N_r^7		Shear - V_r^8		Tension - N_r^7		Shear - V_r^8	
		$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350psi) lb (kN)
1/4	1-5/8 (41)	300 (1.3)	340 (1.5)	665 (3.0)	665 (3.0)	365 (1.6)	445 (2.0)	665 (3.0)	665 (3.0)
	2-1/2 (64)	595 (2.6)	730 (3.2)	1,220 (5.4)	1,220 (5.4)	625 (2.8)	765 (3.4)	1,805 (8.0)	1,805 (8.0)
3/8	1-5/8 (41)	520 (2.3)	635 (2.8)	835 (3.7)	835 (3.7)	755 (3.4)	930 (4.1)	2,030 (9.0)	2,030 (9.0)
	2-1/2 (64)	1,015 (4.5)	1,245 (5.5)	835 (3.7)	835 (3.7)	1,325 (5.9)	1,620 (7.2)	3,365 (15.0)	3,365 (15.0)
	3-1/4 (83)	1,775 (7.9)	2,175 (9.7)	1,990 (8.9)	1,990 (8.9)	n/a	n/a	n/a	n/a
1/2	2-1/4 (57)	525 (2.3)	640 (2.8)	885 (3.9)	885 (3.9)	630 (2.8)	770 (3.4)	4,335 (19.3)	4,335 (19.3)
	3 (76)	1,235 (5.5)	1,510 (6.7)	1,615 (7.2)	1,615 (7.2)	n/a	n/a	n/a	n/a
	4-1/4 (108)	2,155 (9.6)	2,640 (11.7)	1,985 (8.8)	1,985 (8.8)	n/a	n/a	n/a	n/a
5/8	3-1/4 (83)	1,680 (7.5)	2,060 (9.2)	1,915 (8.5)	1,915 (8.5)	n/a	n/a	n/a	n/a
	5 (127)	3,820 (17.0)	4,680 (20.8)	2,315 (10.3)	2,315 (10.3)	n/a	n/a	n/a	n/a
3/4	4 (102)	1,680 (7.5)	2,060 (9.2)	2,075 (9.2)	2,075 (9.2)	n/a	n/a	n/a	n/a

- See PTG Ed. 19 Section 3.1.8 to convert design strength value to ASD value.
- Linear interpolation between embedment depths and concrete compressive strengths is not permitted.
- Tabular value is for one anchor per flute. Minimum spacing along the length of the flute is $3 \times h_{nom}$ (nominal embedment).
- Tabular values are lightweight concrete and no additional reduction factor is needed.
- No additional reduction factors for spacing or edge distance need to be applied.
- Comparison of the tabular values to the steel strength is not necessary. Tabular values control.
- Tabular values are for static loads only. Seismic design is not permitted for uncracked concrete. For seismic tension loads, multiply cracked concrete tabular values in tension by the following reduction factors:
1/4-in diameter by 1-5/8-in nominal embedment depth - $\alpha_{N,seis} = 0.60$
All other sizes - $\alpha_{N,seis} = 0.75$.
See PTG Ed. 19 Section 3.1.8 for additional information on seismic applications.
- For the following anchor sizes, an additional factor for seismic shear must be applied to the cracked concrete tabular values for seismic conditions:
1/4-inch diameter - $\alpha_{V,seis} = 0.75$
3/8-inch diameter - $\alpha_{V,seis} = 0.60$
1/2-inch diameter - $\alpha_{V,seis} = 0.60$
5/8-inch diameter - $\alpha_{V,seis} = 0.60$
3/4-inch diameter - $\alpha_{V,seis} = 0.70$

Table 28 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC steel screw anchor factored resistance in the top of uncracked concrete over metal deck^{1,2,3,4,5}



Nominal anchor diameter in.	Effective embed. in. (mm)	Nominal embed. in. (mm)	Tension - N_r		Shear - V_r	
			$f'_c = 20$ MPa (2,900psi) lb (kN)	$f'_c = 30$ MPa (4,350 psi) lb (kN)	$f'_c = 20$ MPa (2,900 psi) lb (kN)	$f'_c = 30$ MPa (4,350 psi) lb (kN)
1/4	1.18 (30)	1-5/8 (41)	665 (3.0)	750 (3.3)	805 (3.6)	985 (4.4)
3/8	1.11 (28)	1-5/8 (41)	980 (4.4)	1,200 (5.3)	980 (4.4)	1,200 (5.3)

Table 29 - Hilti KH-EZ, KH-EZ P, KH-EZ PM, KH-EZ PL, KH-EZ C and KH-EZ CRC steel anchor factored resistance in the top of cracked concrete over metal deck^{1,2,3,4,5}



Nominal anchor diameter in.	Effective embed. in. (mm)	Nominal embed. in. (mm)	Tension - N_r		Shear - V_r	
			$f'_c = 20$ MPa (2,900psi) lb (kN)	$f'_c = 30$ MPa (4,350 psi) lb (kN)	$f'_c = 20$ MPa (2,900 psi) lb (kN)	$f'_c = 30$ MPa (4,350 psi) lb (kN)
1/4	1.18 (30)	1-5/8 (41)	340 (1.5)	385 (1.7)	565 (2.5)	690 (3.1)
3/8	1.11 (28)	1-5/8 (41)	510 (2.3)	620 (2.8)	685 (3.0)	840 (3.7)

- 1 See PTG Ed. 19 Section 3.1.8 to convert design strength value to ASD value.
- 2 Linear interpolation between embedment depths and concrete compressive strengths is not permitted.
- 3 Apply spacing, edge distance, and concrete thickness factors in tables 20 and 21 as necessary. Compare to the steel values in table 22. The lesser of the values is to be used for the design.
- 4 Tabular values are for normal-weight concrete only. For lightweight concrete multiply design strength by λ_a as follows:
for sand-lightweight, $\lambda_a = 0.68$; for all-lightweight, $\lambda_a = 0.60$
- 5 Tabular values are for static loads only. Seismic design is not permitted for uncracked concrete. For seismic tension loads, multiply cracked concrete tabular values in tension by the following reduction factors:
1/4-inch diameter - $\alpha_{N,seis} = 0.60$
3/8-inch diameter - $\alpha_{N,seis} = 0.75$.
No reduction needed for seismic shear. See PTG Ed. 19 Section 3.1.8 for additional information on seismic applications.

Titen HD® Heavy-Duty Screw Anchor

A high-strength screw anchor for use in cracked and uncracked concrete, as well as uncracked masonry. The Titen HD offers low installation torque and outstanding performance. Designed for use in dry, interior, non-corrosive environments or temporary outdoor applications.

Features

- Tested in accordance with ACI 355.2, AC193 and AC106
- Qualified for static and seismic loading conditions
- Thread design undercuts to efficiently transfer the load to the base material
- Standard fractional sizes
- Specialized heat-treating process creates tip hardness for better cutting without compromising the ductility
- No special drill bit required — designed to install using standard-sized ANSI tolerance drill bits
- Hex-washer head requires no separate washer, unless required by code, and provides a clean installed appearance
- Removable — ideal for temporary anchoring (e.g. formwork, bracing) or applications where fixtures may need to be moved
- Reuse of the anchor will not achieve listed loads and is not recommended

Codes: ICC-ES ESR-2713 (concrete);

ICC-ES ESR-1056 (masonry);

City of LA Supplement within ESR-2713 (concrete);

City of LA Supplement within ESR-1056 (masonry);

Florida FL15730 (concrete and masonry);

FM 3017082, 3035761 and 3043442;

Multiple DOT listings

Material: Carbon steel

Coating: Zinc plated or mechanically galvanized.

Not recommended for permanent exterior use or highly corrosive environments.

Installation



Holes in steel fixtures to be mounted should match the diameter specified in the table below.

Use a Titen HD screw anchor one time only — installing the anchor multiple times may result in excessive thread wear and reduce load capacity.



Do not use impact wrenches to install into hollow CMU.



Caution: Oversized holes in base material will reduce or eliminate the mechanical interlock of the threads with the base material and reduce the anchor's load capacity.

1. Drill a hole in the base material using a carbide drill bit the same diameter as the nominal diameter of the anchor to be installed. Drill the hole to the specified embedment depth plus minimum hole depth overdrill (see table below) to allow the thread tapping dust to settle, and blow it clean using compressed air. (Overhead installations need not be blown clean.) Alternatively, drill the hole deep enough to accommodate embedment depth and the dust from drilling and tapping.
2. Insert the anchor through the fixture and into the hole.
3. Tighten the anchor into the base material until the hex-washer head contacts the fixture.

Additional Installation Information

Titen HD® Diameter (in.)	Wrench Size (in.)	Recommended Steel Fixture Hole Size (in.)	Minimum Hole Depth Overdrill (in.)
1/4	3/8	3/8 to 7/16	1/8
3/8	9/16	1/2 to 9/16	1/4
1/2	3/4	5/8 to 11/16	1/2
5/8	15/16	3/4 to 13/16	1/2
3/4	1 1/8	7/8 to 15/16	1/2



Suggested fixture hole sizes are for structural steel thicker than 12 gauge only. Larger holes are not required for wood or thinner cold-formed steel members.



Serrated teeth on the tip of the Titen HD® screw anchor facilitate cutting and reduce installation torque.

**Titen HD
Screw Anchor**

Installation Sequence



Minimum overdrill. See table.

Titen HD® Heavy-Duty Screw Anchor

Titen HD Anchor Product Data — Zinc Plated

Size (in.)	Model No.	Thread Length (in.)	Drill Bit Diameter (in.)	Wrench Size (in.)	Quantity	
					Box	Carton
¼ x 1½	THDB25178H	1½	¼	⅜	100	500
¼ x 2¾	THDB25234H	2¾	¼	⅜	50	250
¼ x 3	THDB25300H	2¾	¼	⅜	50	250
¼ x 3½	THDB25312H	3½	¼	⅜	50	250
¼ x 4	THDB25400H	3¾	¼	⅜	50	250
⅜ x 1¾	THD37134H†	1¾	⅜	⅞	50	250
⅜ x 2½	THD37212H†	2	⅜	⅞	50	200
⅜ x 3	THD37300H	2½	⅜	⅞	50	200
⅜ x 4	THD37400H	3½	⅜	⅞	50	200
⅜ x 5	THD37500H	4½	⅜	⅞	50	100
⅜ x 6	THD37600H	5½	⅜	⅞	50	100
½ x 3	THD50300H	2½	½	¾	25	100
½ x 4	THD50400H	3½	½	¾	20	80
½ x 5	THD50500H	4½	½	¾	20	80
½ x 6	THD50600H	5½	½	¾	20	80
½ x 6½	THD50612H	5½	½	¾	20	40
½ x 8	THD50800H	5½	½	¾	20	40
½ x 12	THD501200H	5½	½	¾	5	25
½ x 13	THD501300H	5½	½	¾	5	25
½ x 14	THD501400H	5½	½	¾	5	25
½ x 15	THD501500H	5½	½	¾	5	25
⅝ x 4	THDB62400H	3½	⅝	1⅝	10	40
⅝ x 5	THDB62500H	4½	⅝	1⅝	10	40
⅝ x 6	THDB62600H	5½	⅝	1⅝	10	40
⅝ x 6½	THDB62612H	5½	⅝	1⅝	10	40
⅝ x 8	THDB62800H	5½	⅝	1⅝	10	20
⅝ x 10	THDB62100H	5½	⅝	1⅝	10	20
¾ x 4	THD75400H	3½	¾	1⅞	10	40
¾ x 5	THD75500H	4½	¾	1⅞	5	20
¾ x 6	THD75600H	4½	¾	1⅞	5	20
¾ x 7	THD75700H	5½	¾	1⅞	5	10
¾ x 8½	THD75812H	5½	¾	1⅞	5	10
¾ x 10	THD75100H	5½	¾	1⅞	5	10

† These models do not meet minimum embedment depth requirements for strength design and require maximum installation torque of 25 ft. – lb. using a torque wrench, driver drill or cordless ¼" impact driver with a maximum permitted torque rating of 100 ft. – lb.

1. Length of anchor is measured from underside of head to end of anchor.

Titen HD® Heavy-Duty Screw Anchor



Titen HD Anchor Product Data — Mechanically Galvanized

Size (in.)	Model No.	Thread Length (in.)	Drill Bit Diameter (in.)	Wrench Size (in.)	Quantity	
					Box	Carton
3/8 x 3	THD37300HMG	2 1/2	3/8	9/16	50	200
3/8 x 4	THD37400HMG	3 1/2			50	200
3/8 x 5	THD37500HMG	4 1/2			50	100
3/8 x 6	THD37600HMG	5 1/2			50	100
1/2 x 4	THD50400HMG	3 1/2	1/2	3/4	20	80
1/2 x 5	THD50500HMG	4 1/2			20	80
1/2 x 6	THD50600HMG	5 1/2			20	80
1/2 x 6 1/2	THD50612HMG	5 1/2			20	40
1/2 x 8	THD50800HMG	5 1/2			20	40
1/2 x 12	THD501200HMG	5 1/2			5	20
5/8 x 5	THDB62500HMG	4 1/2	5/8	1 5/16	10	40
5/8 x 6	THDB62600HMG	5 1/2			10	40
5/8 x 6 1/2	THDB62612HMG	5 1/2			10	40
5/8 x 8	THDB62800HMG	5 1/2			10	20
3/4 x 5	THD75500HMG	4 1/2	3/4	1 1/8	5	20
3/4 x 6	THD75600HMG	4 1/2			5	20
3/4 x 8 1/2	THD75812HMG	5 1/2			5	10
3/4 x 10	THD75100HMG	5 1/2			5	10

Mechanical galvanizing meets ASTM B695, Class 65, Type 1. Intended for some pressure-treated wood sill plate applications. Not for use in other corrosive or outdoor environments. See p. 261 or visit strongtie.com/info for more corrosion information.

Titen HD Installation Information and Additional Data¹


Characteristic	Symbol	Units	Nominal Anchor Diameter, d _a (in.)											
			¼		⅜		½		⅝		¾			
Installation Information														
Drill Bit Diameter	d _{bit}	in.	¼		⅜		½		⅝		¾			
Baseplate Clearance Hole Diameter	d _c	in.	⅜		½		⅝		¾		⅞			
Maximum Installation Torque	T _{inst,max}	ft.-lbf	24 ²		50 ²		65 ²		100 ²		150 ²			
Maximum Impact Wrench Torque Rating	T _{impact,max}	ft.-lbf	125 ³		150 ³		340 ³		340 ³		385 ³			
Minimum Hole Depth	h _{hole}	in.	1¾	2⅝	2¾	3½	3¾	4½	4½	6	4½	6	6¾	
Nominal Embedment Depth	h _{nom}	in.	1⅝	2½	2½	3¼	3¼	4	4	5½	4	5½	6¼	
Critical Edge Distance	c _{ac}	in.	3	6	2⅞	3⅝	3⅞	4½	4½	6⅝	6	6⅝	7⅞	
Minimum Edge Distance	c _{min}	in.	1½		1¾									
Minimum Spacing	s _{min}	in.	1½		3						2¾		3	
Minimum Concrete Thickness	h _{min}	in.	3¼	3½	4	5	5	6¼	6	8½	6	8¼	10	
Additional Data														
Anchor Category	Category	—	1											
Yield Strength	f _{ya}	psi	100,000			97,000								
Tensile Strength	f _{uta}	psi	125,000			110,000								
Minimum Tensile and Shear Stress Area	A _{se}	in ²	0.042			0.099		0.183		0.276		0.414		
Axial Stiffness in Service Load Range — Uncracked Concrete	β _{uncr}	lb./in.	202,000			672,000								
Axial Stiffness in Service Load Range — Cracked Concrete	β _{cr}	lb./in.	173,000			345,000								

- The information presented in this table is to be used in conjunction with the design criteria of ACI 318-14 Chapter 17 and ACI 318-11 Appendix D.
- T_{inst,max} is the maximum permitted installation torque for the embedment depth range covered by this table using a torque wrench.
- T_{impact,max} is the maximum permitted torque rating for impact wrenches for the embedment depth range covered by this table.

* See p. 12 for an explanation of the load table icons.

Titen HD® Design Information — Concrete

Strong-Tie

Titen HD Tension Strength Design Data¹


Characteristic	Symbol	Units	Nominal Anchor Diameter, d _a (in.)										
			¼		⅜		½		⅝		¾		
Nominal Embedment Depth	<i>h_{nom}</i>	in.	1⅝	2½	2⅞	3¼	3¼	4	4	5½	4	5½	6¼
Steel Strength in Tension — ACI 318-14 Section 17.4.1 or ACI 318-11 Section D.5.1													
Tension Resistance of Steel	<i>N_{sa}</i>	lb.	5,195		10,890		20,130		30,360		45,540		
Strength Reduction Factor — Steel Failure	<i>ϕ_{sa}</i>	—	0.65 ²										
Concrete Breakout Strength in Tension ⁶ — ACI 318-14 Section 17.4.2 or ACI 318-11 Section D.5.2													
Effective Embedment Depth	<i>h_{ef}</i>	in.	1.19	1.94	1.77	2.40	2.35	2.99	2.97	4.24	2.94	4.22	4.86
Critical Edge Distance ⁶	<i>c_{ac}</i>	in.	3	6	2⅞⅓	3⅝	3⅞⅓	4½	4½	6⅝	6	6⅝	7⅝⅓
Effectiveness Factor — Uncracked Concrete	<i>k_{uncr}</i>	—	30	24							27	24	
Effectiveness Factor — Cracked Concrete	<i>k_{cr}</i>	—	17										
Modification Factor	<i>ψ_{c,N}</i>	—	1.0										
Strength Reduction Factor — Concrete Breakout Failure	<i>ϕ_{cb}</i>	—	0.65 ⁷										
Pullout Strength in Tension — ACI 318-14 Section 17.4.3 or ACI 318-11 Section D.5.3													
Pullout Resistance, Uncracked Concrete (f' _c = 2,500 psi)	<i>N_{p,uncr}</i>	lb.	— ³	— ³	2,700 ⁴	— ³	— ³	— ³	— ³	9,810 ⁴	— ³	— ³	— ³
Pullout Resistance, Cracked Concrete (f' _c = 2,500 psi)	<i>N_{p,cr}</i>	lb.	— ³	1,905 ⁴	1,235 ⁴	2,700 ⁴	— ³	— ³	3,040 ⁴	5,570 ⁴	— ³	6,070 ⁴	7,195 ⁴
Strength Reduction Factor — Concrete Pullout Failure	<i>ϕ_p</i>	—	0.65 ⁵										
Tension Strength for Seismic Applications — ACI 318-14 Section 17.4.2.3.3 or ACI 318-11 Section D.3.3.3													
Nominal Pullout Strength for Seismic Loads (f' _c = 2,500 psi)	<i>N_{p,eq}</i>	lb.	— ³	1,905 ⁴	1,235 ⁴	2,700 ⁴	— ³	— ³	3,040 ⁴	5,570 ⁴	3,840 ⁴	6,070 ⁴	7,195 ⁴
Strength Reduction Factor — Breakout or Pullout Failure	<i>ϕ_{eq}</i>	—	0.65 ⁵										

- The information presented in this table is to be used in conjunction with the design criteria of ACI 318-14 Chapter 17 and ACI 318-11 Appendix D, except as modified below.
- The tabulated value of ϕ_{sa} applies when the load combinations of Section 1605.2.1 of the IBC, ACI 318-14 Section 5.3 or ACI 318-11 Section 9.2 are used. If the load combinations of ACI 318-11 Appendix C are used, the appropriate value of ϕ_{sa} must be determined in accordance with ACI 318-11 D.4.4. Anchors are considered brittle steel elements.
- Pullout strength is not reported since concrete breakout controls.
- Adjust the characteristic pullout resistance for other concrete compressive strengths by multiplying the tabular value by $(f'_{c,specified} / 2,500)^{0.5}$.
- The tabulated value of ϕ_p or ϕ_{eq} applies when the load combinations of Section 1605.2.1 of the IBC, ACI 318-14 Section 5.3 or ACI 318-11 Section 9.2 are used and the requirements of ACI 318-14 17.3.3(c) or ACI 318-11 D.4.3(c) for Condition B are met. If the load combinations of ACI 318-11 Appendix C are used, appropriate value of ϕ must be determined in accordance with ACI 318-11 Section D.4.4(c).
- The modification factor $\psi_{cp,N} = 1.0$ for cracked concrete. Otherwise, the modification factor for uncracked concrete without supplementary reinforcement to control splitting is either:
 (1) $\psi_{cp,N} = 1.0$ if $c_{a,min} \geq c_{ac}$ or (2) $\psi_{cp,N} = \frac{c_{a,min}}{c_{ac}} \geq \frac{1.5h_{ef}}{c_{ac}}$ if $c_{a,min} < c_{ac}$
 The modification factor, $\psi_{cp,N}$ is applied to the nominal concrete breakout strength, N_{cb} or N_{cbg} .
- The tabulated value of ϕ_{cb} applies when both the load combinations of Section 1605.2.1 of the IBC, ACI 318-14 Section 5.3 or ACI 318-11 Section 9.2 are used and the requirements of ACI 318-14 17.3.3(c) or ACI 318-11 D.4.3(c) for Condition B are met. Condition B applies where supplementary reinforcement is not provided. For installations where complying supplementary reinforcement can be verified, the ϕ_{cb} factors described in ACI 318-14 17.3.3(c) or ACI 318-11 D.4.3(c) for Condition A are allowed. If the load combinations of ACI 318-11 Appendix C are used, the appropriate value of ϕ_{cb} must be determined in accordance with ACI 318-11 D.4.4(c).

* See p. 12 for an explanation of the load table icons.

Titen HD® Design Information — Concrete

Strong-Tie®

Titen HD Shear Strength Design Data¹

Characteristic	Symbol	Unit	Nominal Anchor Diameter, d _a (in.)											
			¼		⅜		½		⅝		¾			
Nominal Embedment Depth	<i>h_{nom}</i>	in.	1⅝	2½	2½	3¼	3¼	4	4	5½	4	5½	6¼	
Steel Strength in Shear														
Shear Resistance of Steel	<i>V_{sa}</i>	lb.	2,020		4,460		7,455		10,000		14,950		16,840	
Strength Reduction Factor — Steel Failure	<i>ϕ_{sa}</i>	—	0.60 ²											
Concrete Breakout Strength in Shear														
Outside Diameter	<i>d_a</i>	in.	0.25		0.375		0.500		0.625		0.750			
Load Bearing Length of Anchor in Shear	<i>ℓ_e</i>	in.	1.19	1.94	1.77	2.40	2.35	2.99	2.97	4.24	2.94	4.22	4.86	
Strength Reduction Factor — Concrete Breakout Failure	<i>ϕ_{cb}</i>	—	0.70 ³											
Concrete Pryout Strength in Shear														
Coefficient for Pryout Strength	<i>k_{cp}</i>	lb.	1.0					2.0						
Strength Reduction Factor — Concrete Pryout Failure	<i>ϕ_{cp}</i>	—	0.70 ⁴											
Steel Strength in Shear for Seismic Applications														
Shear Resistance for Seismic Loads	<i>V_{eq}</i>	lb.	1,695		2,855		4,790		8,000		9,350			
Strength Reduction Factor — Steel Failure	<i>ϕ_{eq}</i>	—	0.60 ²											

- The information presented in this table is to be used in conjunction with the design criteria of ACI 318-14 Chapter 17 and ACI 318-11 Appendix D, except as modified below.
- The tabulated value of ϕ_{sa} and ϕ_{eq} applies when the load combinations of Section 1605.2.1 of the IBC, ACI 318-14 Section 5.3 or ACI 318-11 Section 9.2 are used. If the load combinations of ACI 318-11 Appendix C are used, the appropriate value of ϕ_{sa} and ϕ_{eq} must be determined in accordance with ACI 318 D.4.4.
- The tabulated value of ϕ_{cb} applies when both the load combinations of Section 1605.2.1 of the IBC, ACI 318-14 Section 5.3 or ACI 318-11 Section 9.2 are used and the requirements of ACI 318-14 17.3.3(c) or ACI 318-11 D.4.3(c) for Condition B are met. Condition B applies where supplementary reinforcement is not provided. For installations where complying supplementary reinforcement can be verified, the ϕ_{cb} factors described in ACI 318-14 17.3.3(c) or ACI 318-11 D.4.3(c) for Condition A are allowed. If the load combinations of ACI 318-11 Appendix C are used, the appropriate value of ϕ_{cb} must be determined in accordance with ACI 318-11 D.4.4(c).
- The tabulated value of ϕ_{cp} applies when both the load combinations of IBC Section 1605.2, ACI 318-14 5.3 or ACI 318-11 Section 9.2 are used and the requirements of ACI 318-14 17.3.3(c) or ACI 318-11 D.4.3(c) for Condition B are met. If the load combinations of ACI 318-11 Appendix C are used, appropriate value of ϕ_{cp} must be determined in accordance with ACI 318-11 Section D.4.4(c).

Titen HD Tension and Shear Strength Design Data for the Soffit of Normal-Weight or Sand-Lightweight Concrete over Steel Deck^{1,6,7}

Characteristic	Symbol	Units	Nominal Anchor Diameter, d _a (in.)									
			Lower Flute						Upper Flute			
			Figure 2			Figure 1			Figure 2		Figure 1	
			1/4	3/8	1/2	3/8	1/2	3/4	1/4	3/8	1/2	3/4
Nominal Embedment Depth	h_{nom}	in.	1 5/8	2 1/2	1 5/8	2 1/2	2	3 1/2	1 5/8	2 1/2	1 5/8	2
Effective Embedment Depth	h_{ef}	in.	1.19	1.94	1.23	1.77	1.29	2.56	1.19	1.94	1.23	1.29
Pullout Resistance, concrete on steel deck (cracked) ^{2,3,4}	$N_{p,deck,cr}$	lb.	420	535	375	870	905	2,040	655	1,195	500	1,700
Pullout Resistance, concrete on steel deck (uncracked) ^{2,3,4}	$N_{p,deck,uncr}$	lb.	995	1,275	825	1,905	1,295	2,910	1,555	2,850	1,095	2,430
Steel Strength in Shear, concrete on steel deck ⁵	$V_{sa,deck}$	lb.	1,335	1,745	2,240	2,395	2,435	4,430	2,010	2,420	4,180	7,145
Steel Strength in Shear, Seismic	$V_{sa,deck,eq}$	lb.	870	1,135	1,434	1,533	1,565	2,846	1,305	1,575	2,676	4,591

- The information presented in this table is to be used in conjunction with the design criteria of ACI 318-14 Chapter 17 and ACI 318-11 Appendix D, except as modified below.
- Concrete compressive strength shall be 3,000 psi minimum. The characteristic pullout resistance for greater compressive strengths shall be increased by multiplying the tabular value by $(f'_{c,specified}/3,000)^{0.5}$.
- For anchors installed in the soffit of sand-lightweight or normal-weight concrete over steel deck floor and roof assemblies, as shown in Figure 1 and Figure 2, calculation of the concrete breakout strength may be omitted.
- In accordance with ACI 318-14 Section 17.4.3.2 or ACI 318-11 Section D.5.3.2, the nominal pullout strength in cracked concrete for anchors installed in the soffit of sand-lightweight or normal-weight concrete over steel deck floor and roof assemblies $N_{p,deck,cr}$ shall be substituted for $N_{p,cr}$. Where analysis indicates no cracking at service loads, the nominal pullout strength in uncracked concrete $N_{p,deck,uncr}$ shall be substituted for $N_{p,uncr}$.
- In accordance with ACI 318-14 Section 17.5.1.2(C) or ACI 318-11 Section D.6.1.2(c), the shear strength for anchors installed in the soffit of sand-lightweight or normal-weight concrete over steel deck floor and roof assemblies $V_{sa,deck}$ and $V_{sa,deck,eq}$ shall be substituted for V_{sa} .
- Minimum edge distance to edge of panel is $2h_{ef}$.
- The minimum anchor spacing along the flute must be the greater of $3h_{ef}$ or 1.5 times the flute width.

* See p. 12 for an explanation of the load table icons.

Titen HD® Design Information — Concrete

Strong-Tie

Titen HD Anchor Tension and Shear Strength Design Data in the Topside of Normal-Weight Concrete or Sand-Lightweight Concrete over Steel Deck



Design Information	Symbol	Units	Nominal Anchor Diameter, d_a (in.)	
			Figure 3	Figure 3
			1/4	3/8
Nominal Embedment Depth	h_{nom}	in.	1 5/8	2 1/2
Effective Embedment Depth	h_{ef}	in.	1.19	1.77
Minimum Concrete Thickness	$h_{min, deck}$	in.	2 1/2	3 1/4
Critical Edge Distance	$c_{ac, deck, top}$	in.	3 3/4	7 1/4
Minimum Edge Distance	$c_{min, deck, top}$	in.	3 1/2	3
Minimum Spacing	$s_{min, deck, top}$	in.	3 1/2	3

1. For anchors installed in the topside of concrete-filled deck assemblies, as shown in Figures 2 and 3, the nominal concrete breakout strength of a single anchor or group of anchors in shear, V_{cb} or V_{cbg} , respectively, must be calculated in accordance with ACI 318-14 Section 17.5.2 or ACI 318-11 Section D.6.2, using the actual member thickness, $h_{min, deck}$, in the determination of A_{vc} .
2. Design capacity shall be based on calculations according to values in the tables featured on p. 84.
3. Minimum flute depth (distance from top of flute to bottom of flute) is 1 1/2" (see Figures 2 and 3).
4. Steel deck thickness shall be minimum 20 gauge.
5. Minimum concrete thickness ($h_{min, deck}$) refers to concrete thickness above upper flute (see Figures 2 and 3).




Figure 1. Installation of 3/8"- and 1/2"-Diameter Anchors in the Soffit of Concrete over Steel Deck




Figure 2. Installation of ¼"-Diameter Anchors in the Soffit of Concrete over Steel Deck




Figure 3. Installation of 1/4"- and 3/8"-Diameter Anchors in the Topside of Concrete over Steel Deck

* See p. 12 for an explanation of the load table icons.

2.4 Accessory Materials (Fasteners)

PRODUCT DESCRIPTION

Product Features

- Flush anchor with optimized length for reliable fastenings in post-tensioned cable concrete slabs
- Shallow drilling for fast installations
- Lip provides flush installation, consistent anchor depth, and easy rod alignment
- Suitable for uncracked and cracked concrete including seismic areas
- Productive installation with HDI-P TZ automatic setting tool with hammer drill
- Used with Hilti Dust Removal System (DRS) for compliance with Table 1 of OSHA 1926.1153 regulations for silica dust exposure




Carbon steel HDI-P TZ




Auto-setting tool HDI-P TZ




Hand-setting tool HDI-P TZ



Uncracked
concrete



Cracked concrete



Seismic Design
Categories
A-F

Approvals/ Listings

ICC-ES (International Code Council)
- 2018 International Building Code / International
Residential Code (IBC/IRC)

ESR-4236 in concrete per ACI 318-14 Ch. 17 / ACI 355.2
/ ICC-ES AC193

City of Los Angeles

2017 LABC Supplement (within ESR-4236)

Florida Building Code

2017 FBC Supplement (within ESR-4236)

FM (Factory Mutual)

Pipe hanger components for automatic sprinkler systems
3/8 (4-inch nominal pipe diameter)

UL and cUL (Underwriters Laboratory)

Pipe hanger equipment for fire protection services for 3/8
(4-inch nominal pipe diameter)



MATERIAL SPECIFICATIONS

HDI-P TZ flush anchors are manufactured from carbon steel with zinc plating per DIN EN ISO 4042 A2K.

INSTALLATION PARAMETERS

Figure 1 - Hilti HDI-P TZ installation parameters




Table 1 - Hilti HDI-P TZ Setting Information

Setting information	Symbol	Unit	Nominal anchor size / internal thread dia. (in)
			3/8
Internal thread diameter	d	in.	3/8
Nominal bit diameter	d _{bit}	in.	9/16
Nominal embedment	h _{nom}	in. (mm)	3/4 (19)
Hole depth in concrete	h ₀	in. (mm)	3/4 (19)
Minimum concrete thickness	h _{min}	in. (mm)	2-1/2 (64)
Thread engagement length	h _s	in. (mm)	3/8 (10)
Minimum edge distance	c _{min}	in. (mm)	6 (153)
Minimum anchor spacing	s _{min}	in. (mm)	8 (204)

Installation Instructions

Installation Instructions For Use (IFU) are included with each product package. They can also be viewed or downloaded online at www.hilti.com or www.hilti.ca. Because of the possibility of changes, always verify that downloaded IFU are current when used. Proper installation is critical to achieve full performance. Training is available on request. Contact Hilti Technical Services for applications and conditions not addressed in the IFU.

2.4 Accessory Materials (Fasteners)

DESIGN DATA IN CONCRETE PER ACI 318

ACI 318-14 Chapter 17 Design

The design tables in Tables 2 to 4 are Hilti Simplified Design Tables. The load values were developed using the design parameters and variables of ICC Evaluation Services ESR-4236 and the equations within ACI 318-14 Chapter 17 as amended by ICC-ES AC193. The strength design capacities calculated from the tables below are to be compared to the factored loads determined from strength design load combinations. For a detailed explanation of the Hilti Simplified Design Tables, refer to Section 3.1.8 of the Hilti North American Product Technical Guide Volume 2 - Anchor Fastening Ed. 17 [Anchor Tech Guide Ed. 17]. Data tables from ESR-4236 are not contained in this section, but can be found at www.hilti.com or www.icc-es.org.

Table 2 - Hilti HDI-P TZ design strength based on concrete failure modes in uncracked concrete per ACI 318 14 Ch. 17^{1,2,3,4,5}

Nominal anchor diameter in.	Nominal embed. in. (mm)	Tension (lesser of concrete breakout / pullout) - ϕN_n				Shear (lesser of concrete breakout or pryout) - ϕV_n			
		$f'_c = 2500$ psi (17.2 MPa) lb (kN)	$f'_c = 3000$ psi (20.7 MPa) lb (kN)	$f'_c = 4000$ psi (27.6 MPa) lb (kN)	$f'_c = 6000$ psi (41.4 MPa) lb (kN)	$f'_c = 2500$ psi (17.2 MPa) lb (kN)	$f'_c = 3000$ psi (20.7 MPa) lb (kN)	$f'_c = 4000$ psi (27.6 MPa) lb (kN)	$f'_c = 6000$ psi (41.4 MPa) lb (kN)
3/8	3/4 (19)	310 (1.4)	340 (1.5)	395 (1.8)	485 (2.1)	350 (1.6)	385 (1.7)	445 (2.0)	545 (2.4)

Table 3 - Hilti HDI-P TZ design strength based on concrete failure modes in cracked concrete per ACI 318 14 Ch. 17^{1,2,3,4,5,6,7}

Nominal anchor diameter in.	Nominal embed. in. (mm)	Tension (lesser of concrete breakout / pullout) - ϕN_n				Shear (lesser of concrete breakout or pryout) - ϕV_n			
		$f'_c = 2500$ psi (17.2 MPa) lb (kN)	$f'_c = 3000$ psi (20.7 MPa) lb (kN)	$f'_c = 4000$ psi (27.6 MPa) lb (kN)	$f'_c = 6000$ psi (41.4 MPa) lb (kN)	$f'_c = 2500$ psi (17.2 MPa) lb (kN)	$f'_c = 3000$ psi (20.7 MPa) lb (kN)	$f'_c = 4000$ psi (27.6 MPa) lb (kN)	$f'_c = 6000$ psi (41.4 MPa) lb (kN)
3/8	3/4 (19)	190 (0.8)	200 (0.9)	220 (1.0)	255 (1.1)	250 (1.1)	270 (1.2)	315 (1.4)	385 (1.7)

The following footnotes apply to both Table 2 and 3:

¹ See Section 3.1.8.6 of the Anchor Tech Guide Ed. 17 to convert design strength value to ASD value.

² Linear interpolation between concrete compressive strengths is not permitted.

³ Tabular values are for a single anchor with a minimum edge distance of 6-1/2-in (166mm) and a minimum spacing of 8-in (204mm). For a 6-in (153mm) edge distance multiply uncracked concrete tension and shear values by 0.92. No reduction needed for cracked concrete.

⁴ Compare to the steel values in Table 4. The lesser of the values is to be used for the design.

⁵ Tabular values are for normal weight concrete only. For lightweight concrete multiply design strength by λ_a as follows: For sand-lightweight, $\lambda_a = 0.68$. For all-lightweight, $\lambda_a = 0.60$.

⁶ Tabular values are for static loads only. For seismic tension loads, multiply cracked concrete tabular values in tension by $\alpha_{N,seis} = 0.74$.

⁷ No additional reduction needed for seismic shear for concrete breakout or pryout failure. See Section 3.1.8.7 of the Anchor Tech Guide Ed. 17 for additional information on seismic applications.

Table 4 - Hilti HDI-P TZ design strength based on steel failure per ACI 318-14 Ch. 17^{1,2,3}

Nominal anchor diameter in.	Steel strength of HDI-P TZ anchor			Steel strength of ASTM A36 threaded rod		
	Tensile ⁴ ϕN_{sa} lb (kN)	Shear ⁵ ϕV_{sa} lb (kN)	Seismic Shear ^{6,9} ϕV_{sa} lb (kN)	Tensile ⁴ $\phi N_{sa,rod}$ lb (kN)	Shear ⁷ $\phi V_{sa,rod}$ lb (kN)	Seismic Shear ^{8,9} $\phi V_{sa,rod,eq}$ lb (kN)
3/8	4,065 (18.1)	585 (2.6)	585 (2.6)	3,370 (15.0)	1,885 (8.4)	1,320 (5.9)

¹ See Section 3.1.8.6 of the Anchor Tech Guide Ed. 17 to convert design strength value to ASD value.

² Steel strength in tension and shear determined from the lesser of the HDI-P TZ or the inserted threaded rod.

³ Hilti HDI-P TZ anchors are considered a brittle steel element. ASTM A36 threaded rod is considered a ductile steel element.

⁴ Tensile $\phi N_{sa} = \phi A_{sa,N} f_{uta}$ as noted in ACI 318-14 Ch. 17.

⁵ Shear values for HDI-P TZ determined by static shear tests with $\phi V_{sa} \leq \phi 0.60 A_{sa,V} f_{uta}$ as noted in ACI 318-14 Ch. 17.

⁶ Seismic shear values for HDI-P TZ determined by seismic shear tests with $\phi V_{sa} < \phi 0.60 A_{sa,V} f_{uta}$ as noted in ACI 318-14 Ch. 17.

⁷ Shear values for threaded rod determined by $\phi V_{sa,rod} = \phi 0.60 A_{sa,V} f_{uta}$ as noted in ACI 318-14 Ch. 17.

⁸ Seismic shear values for threaded rod determined by $\phi V_{sa,rod,eq} = \phi 0.70 V_{sa,rod}$.

⁹ See Section 3.1.8.7 of the Anchor Tech Guide Ed. 17 for additional information on seismic applications.



DESIGN DATA IN CONCRETE PER CSA A23.3

CSA A23.3-14 Annex D Design

Limit State Design of anchors is described in the provisions of CSA A23.3-14 Annex D for post-installed anchors tested and assessed in accordance with ACI 355.2 for mechanical anchors and ACI 355.4 for adhesive anchors. Tables 8 and 9 in this section contains the Limit State Design tables that are based on the published loads in ICC Evaluation Services ESR-4236 and converted for use with CSA A23.3-14 Annex D. Tables 5 to 7 below are Hilti Simplified Design Tables which are pre-factored resistance tables based on the design parameters and variables in Tables 8 and 9. All the figures in the previous ACI 318 14 Chapter 17 design section are applicable to Limit State Design and the tables will reference these figures.

For a detailed explanation of the tables developed in accordance with CSA A23.3-14 Annex D, refer to Section 3.1.8 of the Hilti North American Product Technical Guide Volume 2 - Anchor Fastening Ed. 17 [Anchor Tech Guide Ed. 17]. Technical assistance is available by contacting Hilti Canada at (800) 363-4458 or at www.hilti.ca.

Table 5 - Hilti HDI-P TZ factored resistance based on concrete failure modes in uncracked concrete per CSA A23.3-14 Annex D^{1,2,3,4,5}

Nominal anchor diameter in.	Nominal embed. in. (mm)	Tension (lesser of concrete breakout / pullout) - N_t				Shear (lesser of concrete breakout or pryout) - V_r			
		$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)
3/8	3/4 (19)	325 (1.5)	365 (1.6)	400 (1.8)	460 (2.1)	380 (1.7)	425 (1.9)	465 (2.1)	540 (2.4)

Table 6 - Hilti HDI-P TZ factored resistance based on concrete failure modes in cracked concrete per CSA A23.3-14 Annex D^{1,2,3,4,5,6,7}

Nominal anchor diameter in.	Nominal embed. in. (mm)	Tension (lesser of concrete breakout / pullout) - N_t				Shear (lesser of concrete breakout or pryout) - V_r			
		$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)	$f'_c = 20 \text{ MPa}$ (2,900 psi) lb (kN)	$f'_c = 25 \text{ MPa}$ (3,625 psi) lb (kN)	$f'_c = 30 \text{ MPa}$ (4,350 psi) lb (kN)	$f'_c = 40 \text{ MPa}$ (5,800 psi) lb (kN)
3/8	3/4 (19)	195 (0.9)	210 (0.9)	220 (1.0)	245 (1.1)	270 (1.2)	300 (1.3)	330 (1.5)	380 (1.7)

The following footnotes apply to both Table 5 and 6:

¹ See Section 3.1.8.6 of the Anchor Tech Guide Ed. 17 to convert design strength value to ASD value.

² Linear interpolation between concrete compressive strengths is not permitted.

³ Tabular values are for a single anchor with a minimum edge distance of 6-1/2-in (166mm) and a minimum spacing of 8-in (204mm). For a 6-in (153mm) edge distance multiply uncracked concrete tension and shear values by 0.92. No reduction needed for cracked concrete.

⁴ Compare to the steel values in Table 7. The lesser of the values is to be used for the design.

⁵ Tabular values are for normal weight concrete only. For lightweight concrete multiply design strength by λ_s as follows: For sand-lightweight, $\lambda_s = 0.68$. For all-lightweight, $\lambda_s = 0.60$.

⁶ Tabular values are for static loads only. For seismic tension loads, multiply cracked concrete tabular values in tension by $\alpha_{N,seis} = 0.74$.

⁷ No additional reduction needed for seismic shear for concrete breakout or pryout failure. See Section 3.1.8.7 of the Anchor Tech Guide Ed. 17 for additional information on seismic applications.

Table 7 - Hilti HDI-P TZ factored resistance based on steel failure per CSA A23.3-14 Annex D^{1,2,3}

Nominal anchor diameter in.	Steel strength of HDI-P TZ anchor			Steel strength of ASTM A36 threaded rod		
	Tensile ⁴ N_{sar} lb (kN)	Shear ⁵ V_{sar} lb (kN)	Seismic Shear ^{6,9} $V_{sar,eq}$ lb (kN)	Tensile ⁴ N_{sar} lb (kN)	Shear ⁷ V_{sar} lb (kN)	Seismic Shear ^{8,9} $V_{sar,eq}$ lb (kN)
3/8	3,720 (16.5)	540 (2.4)	540 (2.4)	3,055 (13.6)	1,720 (7.7)	1,200 (5.3)

¹ See Section 3.1.8.6 of the Anchor Tech Guide Ed. 17 to convert design strength value to ASD value.

² Steel strength in tension and shear determined from the lesser of the HDI-P TZ or the inserted threaded rod.

³ Hilti HDI-P TZ anchors are considered a brittle steel element. ASTM A36 threaded rod is considered a ductile steel element.

⁴ Tensile $N_{sar} = A_{se,N} \phi_s f_{uts}$ as noted in CSA A23.3-14 Annex D.

⁵ Shear values for HDI-P TZ determined by static shear tests with $V_{sar} \leq 0.6 A_{se,V} \phi_s f_{uts}$ R as noted in CSA A23.3-14 Annex D.

⁶ Seismic shear values for HDI-P TZ determined by seismic shear tests with $V_{sar,eq} \leq 0.60 A_{se,V} \phi_s f_{uts}$ R as noted in CSA A23.3-14 Annex D.

⁷ Shear values for threaded rod determined by $V_{sar} = 0.6 A_{se,V} \phi_s f_{uts}$ R as noted in CSA A23.3-14 Annex D.

⁸ Seismic shear values for threaded rod determined by $V_{sar,eq} = 0.70 V_{sar,rod}$.

⁹ See Section 3.1.8.7 of the Anchor Tech Guide Ed. 17 for additional information on seismic applications.

Table 8 - Design information, Hilti HDI-P TZ, in accordance with CSA A23.3-14 ¹

Setting information	Symbol	Unit	Nominal anchor size / internal thread dia. (in)	Ref
			3/8	
Anchor O.D.	d_a	in. (mm)	0.561 (14.25)	
Effective embedment	h_{ef}	in. (mm)	3/4 (19)	
Steel embed. material resistance factor for reinforcement	ϕ_s	-	0.85	8.4.3
Resistance modification factor for tension, steel failure modes ^{2,3}	$R_{s,N}$	-	0.70	D.5.3 b)
Min. specified yield strength	f_{ya}	psi (N/mm ²)	70,400 (484)	
Min. specified ultimate strength	f_{uta}	psi (N/mm ²)	88,000 (605)	
Effective-cross sectional steel area in tension	$A_{se,N}$	in ² (mm ²)	0.071 (45.8)	
Factored steel resistance in tension ⁴	N_{sa}	lb (kN)	6,250 (27.8)	D.6.1.2 Eq. D.2
Concrete material resistance factor	ϕ_c	-	0.65	8.4.2
Anchor category	-	-	1	D.5.3 c)
Resistance modification factor for tension, concrete failure ³	$R_{c,N}$	-	0.60	
Coeff. for factored conc. breakout resistance, uncracked concrete	$k_{c,uncr}$	in-lb (SI)	24 (10.0)	D.6.2.2
Coeff. for factored conc. breakout resistance, cracked concrete	$k_{c,cr}$	in-lb (SI)	17 (7.1)	D.6.2.2
Modification factor for anchor resistance, tension, uncracked conc. ⁵	$\psi_{c,N}$	-	1.0	D.6.2.6
Critical edge distance	c_{ac}	in. (mm)	6 (152)	
Factored pullout resistance in 20 MPa uncracked concrete ⁶	$N_{pr,uncr}$	lb (kN)	N/A	D.6.3.2
Factored pullout resistance in 20 MPa cracked concrete ⁶	$N_{pr,cr}$	lb (kN)	495 (2.2)	D.6.3.2
Factored pullout resistance in 20 MPa cracked concrete, seismic ⁶	$N_{pr,eq}$	lb (kN)	490 (2.2)	D.6.3.2
Resistance modification factor for shear, steel failure modes ^{2,3}	$R_{s,V}$	-	0.65	D.5.3 b)
Factored steel resistance in shear ⁷	V_{sa}	lb (kN)	975 (4.3)	D7.1.2
Factored steel resistance in shear, seismic ⁷	$V_{sa,eq}$	lb (kN)	975 (4.3)	
Resistance modification factor for shear, concrete failure modes ³	$R_{c,V}$	-	0.70	
Coefficient for pryout resistance	k_{cp}	-	1.0	D.7.3

¹ Design information is taken from ICC-ES ESR-4236, dated July 2018, table 2, and converted for use with CSA A23.3-14 Annex D.

² The HDI-P TZ is considered a brittle steel element as defined by CSA A23.3-14 Annex D Section D.2.

³ All values of R are applicable with the load combinations of CSA A23.3-14 Chapter 8. For concrete failure modes, no increase for Condition A is permitted.

⁴ $N_{sa} = N_{sa} \phi_s R_{s,N}$ where N_{sa} tabular value above is precalculated from $A_{se,N} f_{uta}$.

⁵ For all design cases, $\psi_{c,N} = 1.0$. The appropriate effectiveness factor for cracked concrete ($k_{c,cr}$) or uncracked concrete ($k_{c,uncr}$) must be used.

⁶ For all design cases, $\psi_{c,P} = 1.0$. Tabular value for pullout resistance is for a concrete compressive strength of 20 MPa (2,900 psi). Pullout resistance for concrete compressive strength greater than 20 MPa (2,900 psi) may be increased by multiplying the tabular pullout resistance by $(f'_c / 20)^{0.35}$ for MPa or $(f'_c / 2,900)^{0.35}$ for psi. NA (not applicable) denotes that pullout strength does not need to be considered for design.

⁷ Shear and seismic shear tests are all performed in cracked concrete member per ICC-ES AC193 section 9.4 and 9.6 respectively. Value of $V_{sa,eq} < 0.6 A_{se,V} f_{uta}$ for all cases. Multiply V_{sa} tabular value above by $\phi_s R_{s,V}$ to get V_{sa} and $V_{sa,eq}$.


Table 9 - Steel design information for inserted threaded rod, in accordance with CSA A23.3-14 ¹

Setting information	Symbol	Unit	Nominal anchor size / internal thread dia. (in)
			3/8
Nominal rod diameter	d_{rod}	in.	0.375
Steel embed. material resistance factor for reinforcement	ϕ_s	-	0.85
Resistance modification factor for tension, steel failure modes ²	$R_{s,N}$	-	0.80
Min. specified ult. strength	f_{uta}	psi (MPa)	58,000 (400)
Rod effective cross-sectional area	$A_{se,rod}$	in. ² (mm ²)	0.0775 (50)
Factored steel resistance in tension ASTM A36 steel material ³	$N_{sa,rod}$	lb (kN)	4,495 (20.0)
Factored steel resistance in tension, seismic ASTM A36 steel material ³	$N_{sa,rod,eq}$	lb (kN)	4,495 (20.0)
Resistance modification factor for steel in shear ASTM A36 steel material ²	$R_{sa,rod,V}$	-	0.75
Factored steel resistance in shear ASTM A36 steel material ⁴	$V_{sa,rod}$	lb (kN)	2,695 (12.0)
Factored steel resistance, seismic ASTM A36 steel material ⁴	$V_{sa,rod,eq}$	lb (kN)	1,885 (8.4)

¹ Values provided for steel element material types, or equivalent, based on minimum specified strengths and calculated in accordance with CSA A23.3 14 Eq. D.2 and Eq. D.30, as applicable.

² All values of R are applicable with the load combinations of CSA A23.3-14 Chapter 8. Values correspond to a ductile steel element.

³ $N_{sa,rod,eq} = N_{sa,rod} \phi_s R_{s,N}$ where $N_{sa,rod}$ tabular value above is precalculated from $A_{se,rod} f_{uta}$. N_{sa} shall be the lower of $N_{sa,rod}$ or $N_{sa,HDI-P\ TZ}$ for static steel strength in tension; for seismic loads, $N_{sa,eq}$ shall be the lower of $N_{sa,rod,eq}$ or $N_{sa,HDI-P\ TZ}$.

⁴ $V_{sa,rod,eq} = V_{sa,rod} \phi_s R_{s,V}$ where $V_{sa,rod}$ tabular value above is precalculated from $0.6 A_{se,rod} f_{uta}$, and $V_{sa,rod,eq}$ must be taken as $0.7 V_{sa,rod}$. V_{sa} shall be the lower of $V_{sa,rod}$ or $V_{sa,HDI-P\ TZ}$ for static steel strength in tension; for seismic loading, $V_{sa,eq}$ shall be the lower of $V_{sa,rod,eq}$ or $V_{sa,HDI-P\ TZ}$.

3.6.1 Self-Drilling Screw Fastener Selection and Design

3.6.1.3 Head Style Selection



HWH (HHWH)
(High) Hex Washer Head : Washer face provides a bearing surface for the driving sockets.



PPH (PPFH)
Phillips Pan (Framing) Head: Conventional head for general applications and provides low profile fastening.



PFH
Phillips Flat Head: Used primarily in wood to countersink and seat flush without splintering the wood.



PWH
Phillips Wafer Head: Large head provides the bearing surface necessary to seat flush in soft materials.



PBH
Phillips Bugle Head: Used primarily for fastening drywall, plywood or insulation board to steel studs.



PTH (MPTH)
(Modified) Phillips Truss Head: Large head and low profile provides surface area needed to attach wire lath to metal stud.




PPCH
Phillips Pancake Conventional Head: Head for general applications and provides low and flat profile.



PFTH
Phillips Flat Truss Head: Lowest profile head available for attaching metal to metal.



PFHUC
Pancake Framing Head Undercut: Used for countersinking where a full head taper would cause stand-off of the screw.



SHWH
Slotted Hex Washer Head: Hex washer head with slot in center to provide additional drive connection.

3.6.1.4 Sealing Criteria

Sealing washer screws offer weather resistant fastenings where moisture or condensation is a factor. The washer helps seal the hole to help prevent moisture from dripping into the fastener threads from the fastened material side, reducing corrosive build-up. As added protection against corrosion, all sealing washer screws come standard with Kwik-Cote coating. The torque control or depth gauge of the electric screwdrivers help ensure that the optimal seal is applied (Reference Section 3.6.1.7).




3.6.1.5 Length Selection

Length of the screw (L)

Depending on the screwhead, there are two different ways to measure the overall length of a screw.

For HWH/HHWH, PPH, PTH, PFTH, SHWH and PPCH screws, the overall length is measured from the bottom of the washer under the head to the point of the screw.


For PWH, PFH, PBH and PFHUC screws, the overall length is measured from the top of the head to the point of the screw.



Maximum Total Thickness (MT)

The maximum total thickness (MT) for all screws is the length of the threads reduced by the first three threads (protruding past the back-side of the base material). See drawings above and below.

The maximum total thickness (MT) describes the maximum thickness of all attachments to be fastened plus the base material.



Self-Drilling Screws 3.6.2

3.6.2.1 Product Description

Hilti self-drilling screws are designed to drill their own hole in steel base materials up to 1/2" thick. These screws are available in a variety of head styles, thread lengths and drill-flute lengths for screw diameters #6 through 1/4". Hilti self-drilling screws meet ASTM C1513, ASTM C954 and SAE J78 standards, as applicable.

Product Features:

- Hex head for metal-to-metal applications
- Flush head for wood-to-metal applications
- For metal from 0.035" to 0.500" thick
- Winged reamers for wood over 1/2" thick
- Stitch screws for light gauge metal-to-metal
- Sealing screws for water resistant fastenings

3.6.2.1 Product Description

3.6.2.2 Material Specifications

3.6.2.3 Technical Data

3.6.2.4 Installation Instructions

3.6.2.5 Ordering Information



3.6.2.2 Material Specifications

Material	ASTM A510 Grade 1018-1022
Heat Treatment	Case hardened and tempered <ul style="list-style-type: none"> • Sizes 8, 10 and 12: 0.004" to 0.009" case depth • Size 1/4": 0.005" to 0.011" case depth
Plating	Refer to Section 3.6.2.5 for screw coating information.

Listings/Approvals

ICC-ES (International Code Council)
ESR-2196
COLA (City of Los Angeles)
RR 25678



Warning: Because of the potential for delayed hydrogen assisted stress corrosion cracking, many hardened steel fasteners are not recommended for use with dissimilar metals or chemically treated wood when moisture may be present or in corrosive environments. For further information, contact Hilti Technical Support at 1-877-749-6337.

ICC-ES ESR-2196, provides IBC recognition of Hilti's Self-Drilling Screw fasteners for most common applications (e.g. CFS connections, gypsum to CFS, etc.), including HWH, HHWH, PPH, PPFH, PBH, PWH, PTH, PPCH, TPCH and PFTH head style screws.

3.6.2.3 Technical Data

Ultimate Tensile Strengths – Pullout (Tension), lb (kN)^{1,2,3,4,5,6,7}

Screw Designation	Nominal Diameter in.	Thickness of steel member not in contact with the screw head, ga (in.)					
		20 (0.036)	18 (0.048)	16 (0.060)	14 (0.075)	12 (0.105)	10 (0.135)
#6	0.138	190 (0.85)	250 (1.11)	320 (1.42)	395 (1.76)	555 (2.47)	715 (3.18)
#7	0.151	210 (0.93)	275 (1.22)	345 (1.53)	435 (1.93)	605 (2.69)	780 (3.47)
#8	0.164	225 (1.00)	300 (1.33)	375 (1.67)	470 (2.09)	660 (2.94)	845 (3.76)
#10	0.190	260 (1.16)	350 (1.56)	435 (1.93)	545 (2.42)	765 (3.40)	980 (4.36)
#12	0.216	295 (1.31)	395 (1.76)	495 (2.20)	620 (2.76)	870 (3.87)	1120 (4.98)
1/4 in.	0.250	345 (1.53)	460 (2.05)	575 (2.56)	715 (3.18)	1000 (4.45)	1290 (5.74)

1 The lower of the ultimate pullout, pullover, and tension fastener strength of screw should be used for design.

2 Load values based upon calculations done in accordance with Section E4 of the AISI S100.

3 AISI S100 recommends a safety factor of 3.0 be applied for allowable strength design, a Φ factor of 0.5 be applied for LRFD design or a Φ factor of 0.4 be applied for LSD design.

4 ANSI/ASME standard screw diameters were used in the calculations and are listed in the tables.

5 The screw diameters in the table above are available in head styles of pan, hex washer, pancake, flat, wafer and bugle.

6 The load data in the table is based upon sheet steel with $F_u = 45$ ksi. For $F_u = 55$ ksi steel, multiply values by 1.22. For $F_u = 65$ ksi steel, multiply values by 1.44.

7 Refer to Section 3.6.2.5 to ensure drilling capacities.

3.6.2 Self-Drilling Screws

Ultimate Tensile Strengths – Pullover (Tension), lb (kN)^{1,2,3,4,5,6,7}

Screw Designation	Washer or Head Diameter in.	Thickness of steel member in contact with the screw head, ga (in.)						
		22 (0.030)	20 (0.036)	18 (0.048)	16 (0.060)	14 (0.075)	12 (0.105)	10 (0.135)
Hex Washer Head (HWH)								
#8	0.335	675 (3.00)	815 (3.63)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)
#10	0.399	805 (3.58)	970 (4.31)	1290 (5.74)	1370 (6.09)	1370 (6.09)	1370 (6.09)	1370 (6.09)
#12-14	0.415	835 (3.71)	1010 (4.49)	1340 (5.96)	1680 (7.47)	2100 (9.34)	2325 (10.34)	2325 (10.34)
#12-24	0.415	835 (3.71)	1010 (4.49)	1340 (5.96)	1680 (7.47)	2100 (9.34)	2940 (13.08)	3780 (16.81)
1/4 in.	0.500	1010 (4.49)	1220 (5.43)	1620 (7.21)	2030 (9.03)	2530 (11.25)	3540 (13.75)	4560 (20.28)
Phillips Pan Head (PPH)								
#7	0.303	615 (2.74)	735 (3.27)	980 (4.36)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)
#8	0.311	630 (2.80)	755 (3.36)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)
#10	0.364	740 (3.29)	885 (3.94)	1180 (5.25)	1370 (6.09)	1370 (6.09)	1370 (6.09)	1370 (6.09)
Phillips Truss Head (PTH)								
#8	0.433	875 (3.89)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)	1000 (4.45)
#10	0.411	830 (3.69)	1000 (4.45)	1330 (5.92)	1390 (6.18)	1390 (6.18)	1390 (6.18)	1390 (6.18)
Phillips Pancake Head (PPCH)								
#10, #12	0.409	830 (3.69)	995 (4.43)	1325 (5.89)	1370 (6.09)	1370 (6.09)	1370 (6.09)	1370 (6.09)
Phillips Flat Truss Head (PFTH)								
#10	0.364	740 (3.29)	885 (3.94)	1180 (5.25)	1475 (6.56)	1840 (8.18)	2170 (9.65)	2170 (9.65)

1. The lower of the ultimate pullout, pullover, and tension fastener strength of screw should be used for design.
2. Load values based upon calculations done in accordance with Section E4 of the AISI S100.
3. AISI S100 recommends a safety factor of 3.0 be applied for allowable strength design, a Φ factor of 0.5 be applied for LRFD design or a Φ factor of 0.4 be applied for LSD design.
4. ANSI/ASME standard screw head diameters were used in the calculations and are listed in the tables.
5. Phillips Bugle Head (PBH) and Phillips Wafer Head (PWH) styles are not covered by this table because they are not intended for attachment of steel to steel.
6. The load data in the table is based upon sheet steel with $F_u = 45$ ksi. For $F_u = 55$ ksi steel, multiply values by 1.22. For $F_u = 65$ ksi steel, multiply values by 1.44.
7. Refer to Section 3.6.2.5 for drilling capacities.

Nominal Ultimate Fastener Strength of Screw

Screw Designation	Nominal Diameter (in.)	Nominal Fastener Strength	
		Tension, P_{ts} lb (kN) ¹	Shear, P_{ss} lb (kN) ^{2,3,4}
#6-20	0.138	1000 (4.45)	890 (3.96)
#7-18	0.151	1000 (4.45)	890 (3.96)
#8-18	0.164	1000 (4.45)	1170 (5.20)
#10-12	0.190	2170 (9.65)	1645 (7.32)
#10-16	0.190	1370 (6.09)	1215 (5.40)
#10-18	0.190	1390 (6.18)	1645 (7.32)
#12-14	0.216	2325 (10.34)	1880 (8.36)
#12-24	0.216	3900 (17.35)	2285 (10.16)
1/4 in.	0.250	4580 (20.37)	2440 (10.85)

- 1 The lower of the ultimate pullout, pullover, and tension fastener strength of screw should be used for design. The Pullout and Pullover tables in this section have already been adjusted where screw strength governs.
- 2 The lower of the ultimate shear fastener strength and shear bearing should be used for design. The Shear Bearing table in this section has already been adjusted where screw strength governs.
- 3 AISI S100 recommends a safety factor of 3.0 be applied for allowable strength design, a Φ factor of 0.5 be applied for LRFD design or a Φ factor of 0.4 be applied for LSD design.
- 4 When the distance to the end of the connected part is parallel to the line of the applied force the allowable shear fastener strength must be reduced for end distance, when necessary, in accordance with E4.3.2 of Appendix A of AISI S100.

Torsional Strength^{1,2}

Size	Min. Torsional Strength in-lb (Nm)
6-20	24 (2.7)
7-18	38 (4.3)
8-18	42 (4.8)
10-12	61 (6.9)
10-16	61 (6.9)
10-18	61 (6.9)
10-24	65 (7.3)
12-14	92 (10.4)
12-24	100 (11.3)
1/4-14	150 (17.0)
1/4-20	156 (17.6)

- 1 Based on screw only. Does not consider base material limitations.
- 2 Values in table are ultimate torsional strengths. To obtain maximum setting torque, multiply values in table by 0.66.

Self-Drilling Screws 3.6.2

Ultimate Shear Strengths – Bearing (Shear), lb (kN)^{1,2,3,4,5,6,7}

Screw Designation	Nominal Diameter in.	Thickness of steel member in contact with screw head ga (in.)	Thickness of steel member not in contact with the screw head, ga (in.)				
			20 (0.036)	18 (0.048)	16 (0.060)	14 (0.075)	≥ 12 (0.105)
#7	0.151	20 (0.036)	500 (2.22)	660 (2.94)	660 (2.94)	660 (2.94)	660 (2.94)
		18 (0.048)	500 (2.22)	660 (2.94)	880 (3.91)	880 (3.91)	880 (3.91)
		≥ 16 (0.060)	500 (2.22)	660 (2.94)	890 (3.96)	890 (3.96)	890 (3.96)
#8	0.164	20 (0.036)	525 (2.34)	715 (3.18)	715 (3.18)	715 (3.18)	715 (3.18)
		18 (0.048)	525 (2.34)	805 (3.58)	955 (4.25)	955 (4.25)	955 (4.25)
		≥ 16 (0.060)	525 (2.34)	805 (3.58)	1120 (4.98)	1170 (5.20)	1170 (5.20)
#10-12	0.190	20 (0.036)	565 (2.51)	830 (3.69)	830 (3.69)	830 (3.69)	830 (3.69)
		18 (0.048)	565 (2.51)	865 (3.85)	1110 (4.94)	1110 (4.94)	1110 (4.94)
		16 (0.060)	565 (2.51)	865 (3.85)	1210 (5.38)	1390 (6.18)	1390 (6.18)
		≥ 14 (0.075)	565 (2.51)	865 (3.85)	1210 (5.38)	1645 (7.32)	1645 (7.32)
#10-16	0.190	20 (0.036)	565 (2.51)	830 (3.69)	830 (3.69)	830 (3.69)	830 (3.69)
		18 (0.048)	565 (2.51)	865 (3.85)	1110 (4.94)	1110 (4.94)	1110 (4.94)
		≥ 16 (0.060)	565 (2.51)	865 (3.85)	1210 (5.38)	1215 (5.40)	1215 (5.40)
#10-18	0.190	20 (0.036)	565 (2.51)	830 (3.69)	830 (3.69)	830 (3.69)	830 (3.69)
		18 (0.048)	565 (2.51)	865 (3.85)	1110 (4.94)	1110 (4.94)	1110 (4.94)
		16 (0.060)	565 (2.51)	865 (3.85)	1210 (5.38)	1390 (6.18)	1390 (6.18)
		≥ 14 (0.075)	565 (2.51)	865 (3.85)	1210 (5.38)	1645 (7.32)	1645 (7.32)
#12-14	0.216	20 (0.036)	600 (2.67)	930 (4.14)	945 (4.20)	945 (4.20)	945 (4.20)
		18 (0.048)	600 (2.67)	925 (4.11)	1260 (5.60)	1260 (5.60)	1260 (5.60)
		16 (0.060)	600 (2.67)	925 (4.11)	1290 (5.74)	1570 (6.98)	1570 (6.98)
		≥ 14 (0.075)	600 (2.67)	925 (4.11)	1290 (5.74)	1800 (8.00)	1880 (8.36)
#12-24	0.216	20 (0.036)	600 (2.67)	930 (4.14)	945 (4.20)	945 (4.20)	945 (4.20)
		18 (0.048)	600 (2.67)	925 (4.11)	1260 (5.60)	1260 (5.60)	1260 (5.60)
		16 (0.060)	600 (2.67)	925 (4.11)	1290 (5.74)	1570 (6.98)	1570 (6.98)
		14 (0.075)	600 (2.67)	925 (4.11)	1290 (5.74)	1800 (8.00)	1970 (8.76)
		≥ 12 (0.090)	600 (2.67)	925 (4.11)	1290 (5.74)	1800 (8.00)	2285 (10.16)
1/4 in.	0.250	20 (0.036)	645 (2.87)	1020 (4.54)	1090 (4.85)	1090 (4.85)	1090 (4.85)
		18 (0.048)	645 (2.87)	995 (4.43)	1400 (6.23)	1460 (6.49)	1460 (6.49)
		16 (0.060)	645 (2.87)	995 (4.43)	1390 (6.18)	1820 (8.10)	1820 (8.10)
		14 (0.075)	645 (2.87)	995 (4.43)	1390 (6.18)	1940 (8.63)	2280 (10.14)
		≥ 12 (0.090)	645 (2.87)	995 (4.43)	1390 (6.18)	1940 (8.63)	2440 (10.85)

- The lower of the ultimate shear bearing and shear fastener strength of screw should be used for design.
- Load values based upon calculations done in accordance with Section E4 of AISI S100.
- AISI S100 recommends a safety factor of 3.0 be applied for allowable strength design, a Φ factor of 0.5 be applied for LRFD design or a Φ factor of 0.4 be applied for LSD design.
- ANSI/ASME standard screw diameters were used in the calculations and are listed in the tables.
- Load values in table are for Hex Washer Head (HWH and HHWH), Phillips Pan Head (PPH), Phillips Truss Head (PTH), Phillips Pancake Head (PPCH), and Phillips Flat Truss Head (PFTH) style screws. Phillips Bugle Head (PBH) and Phillips Wafer Head (PWH) styles are not covered by this table because they are not intended for attachment of steel to steel.
- The load data in the table is based upon sheet steel with $F_u = 45$ ksi. For $F_u = 55$ ksi steel, multiply values by 1.22. For $F_u = 65$ ksi steel, multiply values by 1.44.
- Refer to Section 3.6.2.5 to ensure drilling capacities.

3.6.2.4 Installation Instructions

For general discussion of Hilti screw fastener installation, reference Section 3.6.1.7.

For allowable diaphragm shear loads and stiffness values for steel roof or floor deck utilizing Hilti self-drilling screws as frame or sidelap fasteners, reference Section 3.5 and

download Hilti's Profis DF software at www.us.hilti.com/decking (US), or www.hilti.ca (Canada).



To estimate the number of sidelap screws on a steel roof or floor deck project, reference Section 3.5.1.6.

Warning: Because of the potential for delayed hydrogen assisted stress corrosion cracking, many hardened steel fasteners are not recommended for use with dissimilar metals or chemically treated wood when moisture may be present or in corrosive environments. For further information, contact Hilti Technical Support at 1-877-749-6337.




MODIFIED TRUSS HEAD SELF- PIERCING SHEET METAL SCREW

Expanded wire to wood or 25-20 gauge steel



Meets
ASTM C-1002
Reduced #2 Phillips

Product Specifications



Part #	Dia.	Length	TPI	Bulk Qty	Finish	Corrosion	Head Diameter	Thread	Point
MT812	8	1/2	15	10M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT834	8	3/4	15	8M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT100	8	1	15	5M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT114	8	1-1/4	15	5M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT158	8	1-5/8	15	5M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT178	8	1-7/8	15	4M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT200	8	2	15	2.5M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT212	8	2-1/2	15	2M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°
MT300	8	3	15	1.5M	Zinc	24 hr. min. B-117	10.8mm~ 11.4mm	Double lead	Piercing 25°

Pro-Twist sheet metal screws meet or exceed ASTM C-1002 and/or ASTM C-1513

Self Piercing Screws Ultimate Value Chart				
Dia.	Metal Gauge/1lb	Tension (Pull) Lbs. 1 Pc.	Shear Lbs. Metal to Metal	Minimum Torsional Strength (Lb)
8	25	149	337	39
	22	196	591	
	20	574	829	

Self Piercing Screws Ultimate Value Chart		
Dia.	Wood	Withdrawal Value (Pull out)
8	redwood	206
	3/4" partial board	266
	2x4 fir	398

Ultimate Value Charts

Steel - Screws driven into steel were driven with three exposed threads on the off side of the connection, then pulled out with testing machine.

Wood - Screws driven 3/4" into the wood material, then pulled out the testing machine.

Note that all results were obtained in strict adherence to ASTM test protocol. These ultimate figures are offered only as a guide and are not guaranteed in any way by PrimeSource Building Products. A 4:1 safety ratio is recommended.

Installation Guidelines

0-2500rpm Screwgun with torque adjustment - Overdriving may result in fastener failure or stripout of the work surface

The fastener is fully seated when the head's bearing surface is flush with the steel.
The fastener must penetrate beyond the metal a minimum of three threads to comply with the code

NOT Recommended for use with treated wood.


ALL PRIMESOURCE FASTENERS ARE MANUFACTURED IN AN ISO 9002 AND ISO 14001 CERTIFIED AND APPROVED FACTORY TO PRIMESOURCE PERFORMANCE SPECIFICATIONS AND PRINT DRAWINGS.



MODIFIED TRUSS HEAD SELF-DRILL SCREW


The "old standard" head design for the attachment of metal lath and steel framing

ES ESR 1408



#2 Reduced Phillips

Product Specifications



Part #	Dia.	Length	TPI	Bulk Qty	Finish	Corrosion	Thread	Head Dia.	Drill Capacity
MTD812	8	1/2	18	10M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD834	8	3/4	18	10M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD8100	8	1	18	8M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD8114	8	1-1/4	18	6M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD8158	8	1-5/8	18	5M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD8178	8	1-7/8	18	3M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD8200	8	2	18	2.5M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD8212	8	2-1/2	18	2M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD8300	8	3	18	1.5M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.033"-.100"
MTD1034	10	3/4	16	5M	Zinc	24 hr. min. B-117	FULL	10.8-11.4mm	.110"-.175"

Pro-Twist drill screws meet or exceed ASTM C-954 and/or C-1513

Self-Drilling Screws Ultimate Connection Value Chart				
Dia.	Metal Gauge/lb	Tension (Pull) Lbs. 1 Pc.	Shear Lbs. Metal to Metal	Torsional Strength
8	20	285	829	42 lbs.
	18	444	994	
	16	550	1096	
	14	924	1332	
	12	1100	1337	
10	20	389	811	61 lbs.
	18	554	1223	
	16	727	1492	
	14	1050	1545	
	12	1216	1650	

Ultimate Value Charts

Screws driven into steel were driven with three exposed threads on the off side of the connection, then pulled out with testing machine.

Note that all results were obtained in strict adherence to ASTM test protocol. These ultimate figures are offered only as a guide and are not guaranteed in any way by PrimeSource Building Products. A 3:1 safety ratio is recommended.

Installation Guidelines

0-2500rpm Screwgun with torque adjustment - Overdriving may result in fastener failure or stripout of the work surface
 The fastener is fully seated when the head's bearing surface is flush with the steel.
 The fastener must penetrate beyond the metal a minimum of three threads to comply with the code.

ALL PRIMESOURCE FASTENERS ARE MANUFACTURED IN AN ISO 9002 AND ISO 14001 CERTIFIED AND APPROVED FACTORY TO PRIMESOURCE PERFORMANCE SPECIFICATIONS AND PRINT DRAWINGS.

3.2.5 GENERAL APPLICATION FASTENERS

3.2.5.1 PRODUCT DESCRIPTION

X-U* Universal Series This universal high performance fastener is designed for applications in concrete and high strength or standard strength steel. The shank diameter is consistent through the fastener offering at 0.157". X-U fastener lengths range from 5/8" through 2-7/8" and are available as single fasteners (P8) or collated (MX) in strips of 10. All X-U fasteners have a unique twist knurling reaching 7/8" from the tip up the shank.

X-P* Premium Concrete Fastener

The X-P fastener is optimized for high performance in concrete base materials. With a shank diameter of 0.157", an optimized conical tip design, and high steel hardness, the X-P is designed for demanding concrete applications, in base materials up to 8,000 psi in strength. The X-P fastener is available in lengths ranging from 5/8" to 1 9/16", making it ideal for drywall track to concrete applications. X-P fasteners are available as single fasteners (P8) or collated (MX) in strips of 10.

X-C Standard Series The X-C series of fasteners is a cost effective solution for applications in concrete and masonry. This fastener is not suited for fastening to steel base materials. Fastener lengths range from 3/4" through 2-7/8" with a shank diameter of 0.138". X-C fasteners are offered in a single (P8) fastener version as well as in collated (MX) strips of 10.

X-CR and X-R Fastener Series The X-CR is a high performance, corrosion resistant fastener equivalent to SAE 316 stainless steel. This fastener is ideally suited for applications where corrosion is a concern whether on concrete or steel base materials. The X-CR is designed mainly for concrete applications and is offered as a single (P8) fastener in lengths from 5/8" through 2-1/8". The X-R fastener is intended for steel applications and is offered in 1/2" shank length. Shank diameter for these fasteners is 0.145" for shank lengths less than 1-1/2" and 0.157" for longer fasteners.

X-S Steel Fastener The X-S is an economical fastener for steel. It has a 0.145" smooth shank diameter and is offered in a 1/2" and 5/8" length. The X-S13 comes collated (MX) in strips of 10 or individually with a plastic "tophat" (THP). The X-S16 comes singly with a metal "tophat" (TH). This fastener is ideally suited for fastening drywall track to standard strength steel and is discussed further in Section 3.2.6.

X-C G2/G3/B3, X-P G2/G3/B3, X-PN G3, X-S B3

These collated fastener lines for Hilti's gas-actuated and battery actuated tools are designed for applications in interior finishing, mechanical and electrical trades. These fasteners are used for fastenings in concrete and masonry (X-C G2/G3/B3 standard, X-P G2/G3/B3 premium), and steel (X-S B3 and X-P G2/G3). For more details refer to Section 3.2.6.

DS/EDS Fastener Series The DS series fastener is a high performance fastener of 0.177" shank diameter suitable for both concrete and steel applications. It is offered in a single fastener version only with a 10 mm dome head design and a 10 mm guidance washer. Available lengths are 3/4" through 2-1/2". Knurling is offered on 3/4" and 7/8" lengths; designated as EDS and ideally suited for steel applications.


X-U 15 Steel Fastener The X-U 15 is a premium, high performance fastener designed specifically for attachments to steel (e.g. drywall track, tagging, etc.). It is offered in a 0.145" shank diameter and 5/8" length with a unique step shank design as either single fasteners with metal tophat or collated in strips of 10.

3.2.5.1 Product description

3.2.5.2 Material specifications

3.2.5.3 Technical data

3.2.5.4 Ordering information



Listings/Approvals

ICC-ES (International Code Council)

ESR-2269 (X-P, X-U and X-U 15)
ESR-1663 (DS, EDS, X-R and X-CR)
ESR-1752 with 2017 LABC/LARC
Supplement (X-C, X-P G2/G3/B3, X-S)

COLA (City of Los Angeles)

RR 25675 (X-P, X-U and X-U 15)
RR 25646 (DS, X-C, EDS, and X-CR)



3.2.5.2 MATERIAL SPECIFICATIONS

Fastener designation	Fastener material	Fastener plating ¹	Steel washer or clip plating ^{1,2}	Washer or clip plating ^{1,2}
X-P*	Carbon Steel	5 µm Zinc	N/A	N/A
X-U*	Carbon Steel	5 µm Zinc	Carbon Steel	5 µm Zinc
DS/EDS	Carbon Steel	5 µm Zinc	N/A	N/A
X-C	Carbon Steel	5 µm Zinc	Carbon Steel	5 µm Zinc
X-R, X-CR ³	SAE 316	N/A	SAE 316	N/A
X-C/ X-P/ X-PN/ X-S: G2/G3/B3	Carbon Steel	2-10 µm Zinc	N/A	N/A
X-CT Forming Nail	Carbon Steel	5 µm Zinc	N/A	N/A
BC X-C	Carbon Steel	5 µm Zinc	Carbon Steel	5 µm Zinc

1 The 5 µm zinc coating is in accordance with ASTM B 633, SC 1, Type III. Refer to Section 2.3.3.1 for more information.

2 Most fasteners have a plastic washer for guidance when installing. Not all fastener lengths have a pre-mounted steel washer. Refer to Section 3.2.2.4 for more information on available fasteners.

3. The X-CR and X-R fastener material is a proprietary material, which provides a corrosion resistance equivalent to SAE 316 stainless steel. The steel washer material is SAE 316 stainless steel.

* More details about the innovative X-P and X-U fasteners can be found in Section 3.2.6.

3.2.5.3 TECHNICAL DATA

Allowable loads in normal weight concrete ^{1,2}

Fastener description	Fastener	Shank diameter in. (mm)	Minimum embedment in. (mm)	Concrete compressive strength							
				2000 psi		4000 psi		6000 psi		8000 psi	
				Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)
Premium Concrete Fastener	X-P	0.157 (4.0)	3/4 (19)	100 (0.44)	155 (0.69)	100 (0.44)	175 (0.78)	105 (0.47)	205 (0.91)	135 (0.60)	205 (0.91)
			1 (25)	165 (0.73)	220 (0.98)	180 (0.80)	225 (1.00)	150 (0.67)	300 (1.33)	150 (0.67)	215 (0.96)
			1-1/4 (32)	240 (1.07)	310 (1.38)	280 (1.25)	310 (1.38)	180 (0.80)	425 (1.89)	–	–
			1-1/2 (38)	310 (1.38)	420 (1.87)	–	–	–	–	–	–
Universal Knurled Shank Fasteners	X-U	0.157 (4.0)	3/4 (19)	100 (0.44)	125 (0.57)	100 (0.44)	125 (0.57)	105 (0.47)	205 (0.91)	–	–
			1 (25)	165 (0.73)	190 (0.85)	170 (0.76)	225 (1.00)	110 (0.49)	280 (1.25)	–	–
			1-1/4 (32)	240 (1.07)	310 (1.38)	280 (1.25)	310 (1.38)	180 (0.80)	425 (1.89)	–	–
			1-1/2 (38)	275 (1.22)	420 (1.87)	325 (1.45)	420 (1.87)	–	–	–	–
Standard Fastener	X-C (Black collated strip or guidance washer)	0.138 (3.5)	3/4 (19)	45 (0.20)	75 (0.33)	65 (0.29)	105 (0.47)	95 (0.42)	195 (0.87)	–	–
			1 (25)	85 (0.38)	150 (0.67)	160 (0.71)	200 (0.89)	105 (0.47)	270 (1.20)	–	–
			1-1/4 (32)	130 (0.58)	210 (0.93)	270 (1.20)	290 (1.29)	165 (0.73)	325 (1.45)	–	–
			1-1/2 (38)	175 (0.78)	260 (1.16)	270 (1.20)	360 (1.60)	–	–	–	–
Heavy Duty Fastener	DS	0.177 (4.5)	3/4 (19)	50 (0.22)	120 (0.53)	125 (0.56)	135 (0.60)	–	–	–	–
			1 (25)	130 (0.58)	195 (0.87)	155 (0.69)	240 (1.07)	–	–	–	–
			1-1/4 (32)	220 (0.98)	385 (1.71)	270 (1.20)	425 (1.89)	–	–	–	–
			1-1/2 (38)	300 (1.33)	405 (1.80)	355 (1.58)	450 (2.00)	–	–	–	–
Stainless Steel Fastener	X-CR	0.145 (3.7)	3/4 (19)	30 (0.13)	40 (0.18)	65 (0.29)	40 (0.18)	–	–	–	–
			1 (25)	55 (0.24)	185 (0.82)	120 (0.53)	190 (0.85)	100 (0.44)	170 (0.76)	–	–
			1-1/4 (32)	110 (0.49)	290 (1.29)	125 (0.56)	300 (1.33)	120 (0.53)	440 (1.96)	–	–
			1-1/2 (38)	265 (1.18)	405 (1.80)	350 (1.56)	450 (2.00)	–	–	–	–
Gas Fastener	X-C B3, X-C G3	0.118 (3.0)	3/4 (19)	110 (0.5)	190 (0.9)	110 (0.5)	190 (0.9)	110 (0.5)	190 (0.9)	–	–
Premium Gas Fastener	X-GHP, X-P 17 G2, X-P 20 G2, X-P G3, X-P B3	0.118 (3.0)	5/8 (16)	–	–	50 (0.2)	120 (0.5)	50 (0.2)	90 (0.4)	–	–
			3/4 (19)	80 (0.4)	120 (0.5)	–	–	–	–	–	–
Forming Fastener	X-CT 47 ³	0.145 (3.7)	1 (25)	60 (0.27)	65 (0.29)	–	–	–	–	–	–
	X-CT 62 ³	0.145 (3.7)	1 (25)	75 (0.33)	75 (0.33)	–	–	–	–	–	–

1 The tabulated allowable load values are for the low-velocity fasteners only, using a safety factor that is greater than or equal to 5.0, calculated in accordance with ICC-ES AC70. Wood or steel members connected to the substrate must be investigated in accordance with accepted design criteria.

2 Multiple fasteners are recommended for any attachment.

3 For temporary fastening of formwork only.

Allowable loads in minimum $f'_c = 3000$ psi structural lightweight concrete^{1,5}

Fastener description	Fastener	Shank diameter in. (mm)	Minimum embedment in. (mm)	Fastener location					
				Installed into concrete		Installed through 3" deep metal deck into concrete ^{2,3}			
				Tension lb (kN)	Shear lb (kN)	Tension lb (kN)		Shear lb (kN)	
						Upper flute	Lower flute	Upper flute	Lower flute
Premium Concrete Fastener	X-P*	0.157 (4.0)	3/4 (19)	155 (0.7)	165 (0.7)	130 (0.6)	105 (0.5)	285 (1.3)	285 (1.3)
			1 (25)	225 (1.0)	300 (1.3)	215 (1.0)	165 (0.7)	340 (1.5)	340 (1.5)
			1-1/4 (32)	325 (1.4)	445 (2.0)	295 (1.3)	230 (1.0)	375 (1.7)	375 (1.7)
			1-1/2 (38)	425 (1.9)	480 (2.1)	400 (1.8)	330 (1.5)	365 (1.6)	365 (1.6)
Universal Knurled Shank Fasteners	X-U*	0.157 (4.0)	3/4 (19)	125 (0.56)	115 (0.51)	130 (0.58)	95 (0.42)	245 (1.1)	245 (1.1)
			1 (25)	205 (0.91)	260 (1.16)	215 (0.96)	155 (0.69)	330 (1.5)	330 (1.5)
			1-1/4 (32)	315 (1.40)	435 (1.93)	295 (1.31)	200 (0.89)	375 (1.7)	375 (1.7)
			1-1/2 (38)	425 (1.89)	475 (2.11)	400 (1.78)	260 (1.16)	430 (1.9)	430 (1.9)
Standard Fastener	X-C (Black collated strip or guidance washer)	0.138 (3.5)	3/4 (19)	120 (0.53)	175 (0.78)	120 (0.53)	95 (0.42)	265 (1.2)	265 (1.2)
			1 (25)	180 (0.80)	260 (1.16)	215 (0.96)	155 (0.69)	485 (2.2)	485 (2.2)
			1-1/4 (32)	225 (1.00)	400 (1.78)	250 (1.11)	200 (0.89)	500 (2.2)	500 (2.2)
			1-1/2 (38)	285 (1.27)	400 (1.78)	285 (1.27)	210 (0.93)	555 (2.5)	555 (2.5)
Heavy Duty Fastener	DS ⁴	0.177 (4.5)	3/4 (19)	100 (0.44)	200 (0.89)	100 (0.44)	-	200 (0.9)	200 (0.9)
			1 (25)	180 (0.80)	360 (1.60)	180 (0.80)	180 (0.80)	405 (1.8)	405 (1.8)
			1-1/4 (32)	300 (1.33)	520 (2.31)	300 (1.33)	250 (1.11)	515 (2.3)	515 (2.3)
			1-1/2 (38)	450 (2.00)	680 (3.02)	450 (2.00)	325 (1.45)	625 (2.8)	625 (2.8)
Stainless Steel Fastener	X-CR	0.145 (3.7)	1 (25)	230 (1.02)	240 (1.07)	230 (1.02)	-	240 (1.1)	240 (1.1)
			1-1/4 (32)	320 (1.42)	400 (1.78)	320 (1.42)	-	400 (1.8)	400 (1.8)
			1-1/2 (38)	405 (1.80)	500 (2.22)	405 (1.80)	-	500 (2.2)	500 (2.2)
Gas Fastener	X-GN, X-C B3, X-C G3	0.118 (3.0)	3/4 (19)	115 (0.5)	140 (0.6)	75 (0.3)	85 (0.4)	175 (0.8)	215 (1.0)
			1 (25)	170 (0.8)	220 (1.0)	155 (0.7)	160 (0.7)	255 (1.1)	315 (1.4)
Premium Gas Fastener	X-GHP, X-P 17 G2, X-P 20 G2, X-P G3, X-P B3	0.118 (3.0)	5/8 (16)	60 (0.3)	140 (0.6)	60 (0.3)	60 (0.3)	175 (0.8)	215 (1.0)

1 The tabulated allowable load values are for the low-velocity fasteners only, using a safety factor that is greater than or equal to 5.0, calculated in accordance with ICC-ES AC70. Wood or steel members connected to the substrate must be investigated in accordance with accepted design criteria.

2 The steel deck profile is 3" deep composite floor deck with a minimum thickness of 20 gauge (0.0358"). Figure 1 (Section 3.2.1.6) shows the nominal flute dimensions, fastener locations, and load orientations for the deck profile.

3 Structural lightweight concrete fill above top of metal deck shall be a minimum of 3-1/4" deep.

4 DS fasteners installed at 1-1/2" embedment through steel deck into the lower flute must be installed at a minimum distance of 6" from the edge of the floor deck.

5 Multiple fasteners are recommended for any attachment.

* More details about the innovative X-P and X-U fasteners can be found in Section 3.2.6.

Allowable Loads Into Minimum $f'_c = 3000$ psi Structural Lightweight Concrete Over 1-1/2" Deep, B-Type Steel Deck^{1,4}


Fastener description	Fastener	Shank diameter in. (mm)	Minimum embedment in. (mm)	Fastener location installed through metal deck into concrete ^{2,3}			
				Tension lb (kN)		Shear	
				Upper flute	Lower flute	lb (kN)	
Premium concrete fastener	X-P*	0.157 (4.0)	3/4 (19)	140 (0.6)	130 (0.6)	335 (1.5)	
			1 (25)	215 (1.0)	215 (1.0)	385 (1.7)	
			1-1/4 (32)	–	270 (1.2)	465 (2.1)	
Universal knurled shank fastener	X-U*	0.157 (4.0)	3/4 (19)	95 (0.42)	95 (0.42)	370 (1.65)	
			1 (25)	125 (0.56)	125 (0.56)	415 (1.85)	
Standard fastener	X-C	0.138 (3.5)	3/4 (19)	80 (0.36)	80 (0.36)	315 (1.40)	
			1 (25)	205 (0.91)	205 (0.91)	445 (1.98)	
Gas fastener	X-GN, X-C B3, X-C G3	0.118 (3.0)	3/4 (19)	75 (0.3)	85 (0.38)	175 (0.8)	
			1 (25)	155 (0.7)	160 (0.71)	255 (1.1)	
Premium gas fastener	X-GHP, X-P 17 G2, X-P 20 G2, X-P G3, X-P B3	0.118 (3.0)	5/8 (16)	60 (0.27)	60 (0.3)	175 (0.8)	

- 1 The tabulated allowable load values are for the low-velocity fasteners only, using a safety factor that is greater than or equal to 5.0, calculated in accordance with ICC-ES AC70. Wood or steel members connected to the substrate must be investigated in accordance with accepted design criteria.
- 2 Steel deck profiles are 1-1/2" deep, B-type deck with a minimum thickness of 20 gauge (0.0358" thick steel). Fasteners may be installed through the metal deck into lightweight concrete having both nominal and inverted deck profile orientations with a minimum lower flute width of 1-3/4" or 3-1/2", respectively. Fasteners shall be placed at centerline of deck flutes. Refer to Figures 2 and 3 (Section 3.2.1.6) for additional flute dimensions, fastener locations, and load orientations for both deck profiles.
- 3 Structural lightweight concrete fill above top of metal deck shall be a minimum 2-1/2" deep.
- 4 Multiple fasteners are recommended for any attachment.

Allowable Loads in Concrete Masonry Units^{1,2,3,4,5,10}

Fastener Description	Fastener	Shank diameter in. (mm)	Min. embed. in. (mm)	Hollow CMU				Grout filled CMU					
				Face shell ⁶		Mortar joint		Face shell ⁶		Mortar joint		Top of grouted cell ⁸	
				Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear ⁷ lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear ⁷ lb (kN)	Tension lb (kN)	Shear ⁹ lb (kN)
Premium concrete fastener	X-P*	0.157 (4.0)	1 (25)	70 (0.31)	105 (0.47)	85 (0.38)	70 (0.31)	150 (0.67)	145 (0.65)	150 (0.67)	155 (0.69)	165 (0.73)	240 (1.07)
Universal knurled shank fasteners	X-U*	0.157 (4.0)	1 (25)	70 (0.31)	85 (0.38)	25 (0.11)	70 (0.31)	225 (1.00)	220 (0.98)	150 (0.67)	190 (0.85)	165 (0.73)	240 (1.07)
Standard fastener	X-C	0.138 (3.5)	3/4 (19)	40 (0.18)	85 (0.38)	25 (0.11)	50 (0.22)	100 (0.44)	105 (0.47)	45 (0.20)	80 (0.36)	115 (0.51)	175 (0.78)
Gas fastener	X-GN, X-C B3, X-C G3	0.118 (3.0)	3/4 (19)	145 (0.65)	190 (0.85)	80 (0.36)	80 (0.36)	155 (0.69)	195 (0.87)	110 (0.49)	135 (0.60)	105 (0.47)	145 (0.65)
			1 (25)	185 (0.82)	205 (0.91)	105 (0.47)	105 (0.47)	205 (0.91)	215 (0.96)	135 (0.60)	190 (0.85)	120 (0.53)	150 (0.67)
Gas fastener	X-C G2	0.108 (2.7)	3/4 (19)	75 (0.33)	140 (0.62)	60 (0.27)	80 (0.36)	100 (0.44)	170 (0.76)	100 (0.44)	160 (0.71)	80 (0.36)	130 (0.58)
			1 (25)	110 (0.49)	190 (0.85)	70 (0.31)	145 (0.65)	135 (0.60)	195 (0.87)	125 (0.56)	165 (0.73)	110 (0.49)	145 (0.65)

- 1 The tabulated allowable load values are for the low-velocity fastener only, using a safety factor of 5.0 or higher calculated in accordance with ICC-ES AC70. Wood or steel members connected to the substrate must be investigated in accordance with accepted design criteria.
- 2 The tabulated allowable load values are for low-velocity fasteners installed in normal weight or lightweight concrete masonry units conforming to ASTM C90.
- 3 The tabulated allowable load values are for low-velocity fasteners installed in concrete masonry units with mortar conforming to ASTM C270, Type N or S.
- 4 The tabulated allowable load values are for low-velocity fasteners installed in concrete masonry units with grout conforming to ASTM C476, as coarse grout.
- 5 The tabulated allowable load values are for one low-velocity fastener installed in an individual masonry unit cell and at least 4" from the edge of the wall.
- 6 Fastener can be located anywhere on the face shell or mortar joint as shown in the figure to the right.
- 7 Shear direction can be horizontal or vertical (Bed Joint or T-Joint) along the CMU wall plane.
- 8 Fastener located in center of grouted cell installed vertically.
- 9 Shear can be in any direction.
- 10 Multiple fasteners are recommended for any attachment.



Acceptable locations (NON-SHADED AREAS) for power-actuated fasteners in CMU walls

* More details about the innovative X-P and X-U fasteners can be found in Section 3.2.6.

Allowable loads in minimum ASTM A36 ($F_y \geq 36$ ksi, $F_u \geq 58$ ksi) steel^{1,2,4,5}

Fastener description	Fastener	Shank diameter in. (mm)	Steel thickness (in.)											
			1/8		3/16		1/4		3/8		1/2		$\geq 3/4$	
			Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)
Universal knurled shank*	X-U ⁶	0.157 (4.0)	-	-	535 (2.38)	720 (3.20)	775 (3.45)	720 (3.20)	935 (4.16)	720 (3.20)	900 (4.00)	720 (3.20)	350 (1.56)	375 (1.67)
Stepped-shank knurling-lengthwise	X-U 15 ⁷	0.145 (3.7)	-	-	155 (0.69)	395 (1.76)	230 (1.02)	395 (1.76)	420 (1.86)	450 (2.00)	365 (1.62)	500 (2.22)	365 (1.62)	400 (1.78)
Standard knurled shank	X-S13	0.145 (3.7)	140 (0.62)	300 (1.33)	300 (1.33)	450 (2.00)	300 (1.33)	450 (2.00)	300 (1.33)	450 (2.00)	-	-	-	-
Drywall smooth shank w/metal top hat washer	X-S16	0.145 (3.7)	-	-	225 (1.00)	420 (1.87)	225 (1.00)	430 (1.91)	225 (1.00)	430 (1.91)	225 (1.00)	430 (1.91)	-	-
Heavy duty knurled shank	EDS ⁸	0.177 (4.5)	-	-	305 (1.36)	615 (2.67)	625 (2.78)	870 (3.87)	715 (3.18)	870 (3.87)	890 (3.96)	960 (4.27)	400 (1.78)	655 (2.91)
Heavy duty smooth shank	DS	0.177 (4.5)	-	-	365 (1.62)	725 (3.22)	580 (2.58)	725 (3.22)	695 (3.09)	725 (3.22)	735 (3.27)	860 (3.83)	-	-
Stainless steel smooth shank	X-R ¹⁰	0.145 (3.7)	-	-	460 (2.05)	460 (2.05)	615 (2.74)	500 (2.22)	-	-	-	-	-	-
	X-R ^{8,10}	0.145 (3.7)	300 (1.33)	190 (0.85)	615 (2.74)	495 (2.20)	760 (3.38)	500 (2.22)	220 (0.98)	325 (1.45)	225 (1.00)	335 (1.49)	-	-
Standard gas fastener for steel	X-EGN 14 ⁹ , X-S 14 B3	0.118 (3.0)	140 (0.6)	230 (1.0)	220 (1.0)	245 (1.1)	225 (1.0)	290 (1.3)	280 (1.2)	330 (1.5)	280 (1.2)	330 (1.5)	280 (1.2)	330 (1.5)
Standard gas fastener for steel	X-EGN 14 ^{8,9} , X-S 14 B38	0.118 (3.0)	-	-	220 (1.0)	295 (1.3)	260 (1.2)	355 (1.6)	280 (1.2)	385 (1.7)	280 (1.2)	385 (1.7)	280 (1.2)	385 (1.7)
Premium gas fastener	X-GHP, X-P G3, X-P B3	0.118 (3.0)	125 (0.6)	230 (1.0)	170 (0.8)	245 (1.1)	200 (0.9)	230 (1.0)	250 (1.1)	255 (1.1)	-	-	-	-

- 1 The tabulated allowable load values are for the low-velocity fasteners only, using a safety factor that is greater than or equal to 5.0, calculated in accordance with ICC-ES AC70. Wood or steel members connected to the substrate must be investigated in accordance with accepted design criteria.
- 2 Low-velocity fasteners shall be driven to where the point of the fastener penetrates through the steel base material in accordance with Section 3.2.2.3, except as noted in this table.
- 3 EDS fasteners installed into greater than 1/2" thick steel require 1/2" minimum penetration.
- 4 Multiple fasteners are recommended for any attachment.
- 5 Refer to guidelines for fastening to steel, Section 3.2.2, for application limits.
- 6 Tabulated allowable load values provided for 3/4" steel are based upon minimum point penetration of 1/2" into the steel. If 1/2" point penetration into the steel is not achieved, but a point penetration of at least 3/8" is obtained, the tabulated tension value should be reduced by 20 percent and the tabulated shear load should be reduced by 8 percent.
- 7 X-U 15 fasteners installed into greater than 3/8" thick steel require 15/32" minimum penetration into the steel.
- 8 Based on testing with $F_y = 50$ ksi base material.
- 9 Fasteners installed into 3/8" or thicker base steel require 0.320" minimum penetration depth into the steel.
- 10 Fasteners installed into 3/8" or thicker base require 0.38" minimum penetration depth into the steel.

Allowable tensile pullover and shear bearing load capacities for steel framing with power driven fasteners^{1,2,3,4}

Fastener description	Fastener	Head dia. in. (mm)	Sheet steel thickness													
			14 ga.		16 ga.		18 ga.		20 ga.		22 ga.		24 ga.		25/26 ga.	
			Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)	Tension lb (kN)	Shear lb (kN)
0.157" shank with or w/o plastic washers or MX collation	X-U, X-P	0.322 (8.2)	825 (3.67)	1,085 (4.83)	685 (3.05)	720 (3.20)	490 (2.18)	525 (2.34)	360 (1.60)	445 (1.98)	300 (1.33)	330 (1.47)	205 (0.91)	255 (1.13)	120 (0.53)	145 (0.64)
0.145" shank with or w/o plastic washers or MX collation	X-C, X-R	0.322 (8.2)	-	985 (4.38)	685 (3.05)	720 (3.20)	490 (2.18)	515 (2.29)	360 (1.60)	440 (1.96)	300 (1.33)	310 (1.38)	205 (0.91)	235 (1.05)	120 (0.53)	145 (0.64)
0.177" shank without washer	DS, EDS	0.322 (8.2)	965 (4.29)	1,085 (4.83)	810 (3.60)	815 (3.63)	625 (2.78)	535 (2.38)	460 (2.05)	465 (2.07)	360 (1.60)	350 (1.56)	300 (1.33)	260 (1.16)	240 (1.07)	180 (0.80)
0.145" shank with plastic top hat washers	X-S13 THP, X-S16 TH	0.322 (8.2)	-	985 (4.38)	685 (3.05)	720 (3.20)	490 (2.18)	515 (2.29)	360 (1.60)	440 (1.96)	300 (1.33)	310 (1.38)	205 (0.91)	235 (1.05)	120 (0.53)	145 (0.64)
0.118" shank with MX collation	X-EGN, X-GN, X-GHP	0.276 (6.8)	-	-	-	-	325 (1.45)	390 (1.73)	265 (1.18)	335 (1.49)	250 (1.11)	235 (1.05)	170 (0.76)	185 (0.82)	100 (0.44)	125 (0.56)

- 1 Allowable load values are based on a safety factor of 3.0.
- 2 Allowable pullover capacities of sheet steel should be compared to the allowable fastener tensile load capacities in concrete, steel, and masonry to determine controlling resistance load.
- 3 Allowable shear bearing capacities of sheet steel should be compared to allowable fastener shear capacities in concrete, steel and masonry to determine controlling resistance load.
- 4 Data is based on the following minimum sheet steel properties, $F_y = 33$ ksi, $F_u = 45$ ksi (ASTM A653 material).

* More details about the innovative X-U fastener can be found in Section 3.2.6.

3.2.5.4 ORDERING INFORMATION

Carbon steel non-collated (without pre-mounted steel washer)

Fastener description	Shank length in. (mm)	Shank Ø in. (mm)	Washer Ø
Concrete, Masonry and Steel			
X-U P8*	5/8 to 2-7/8 (16 to 72)	0.157 (4.0)	8 mm plastic
X-U P8 TH*	5/8, 3/4, 1 (16, 19, 27)	0.157 (4.0)	8 mm plastic and metal tophat
Concrete and Masonry			
X-P P8	7/8 to 1-9/16 (22 to 40)	0.157 (4.0)	8 mm plastic
DS P10	1 to 2-1/2 (27 to 62)	0.177 (4.5)	8 mm plastic
X-C P8	1 to 2-1/2 (19 to 62)	0.138 (3.5)	8 mm plastic
X-C THP	3/4 (20)	0.138 (3.5)	8 mm plastic tophat
Steel			
X-S13 THP	1/2 (13)	0.145 (3.7)	8 mm plastic tophat
X-S16 TH	5/8 (16)	0.145 (3.7)	8 mm plastic and metal tophat
EDS P10	3/4, 7/8 (19, 22)	0.177 (4.5)	10 mm plastic

Carbon steel collated (without pre-mounted steel washer)

Fastener description	Shank length in. (mm)	Shank Ø in. (mm)	Washer Ø
Concrete, Masonry and Steel			
X-U MX*	5/8 to 2-7/8 (16 to 72)	0.157 (4.0)	Collated
Concrete and Masonry			
X-P MX	7/8 to 1-9/16 (22 to 40)	0.157 (4.0)	Collated
X-C MX	1 to 2-1/2 (27 to 62)	0.138 (3.5)	Collated
X-GN MX	3/4 to 1-1/4 (20 to 32)	0.118 (3.0)	Collated
X-GHP MX	11/16, 3/4 (18, 20)	0.118 (3.0)	Collated
Steel			
X-S13 MX	1/2 (13)	0.145 (3.7)	Collated
X-EGN MX	1/2 (14)	0.118 (3.0)	Collated
X-GHP MX	11/16, 3/4 (18, 20)	0.118 (3.0)	Collated

Carbon steel non-collated (with pre-mounted steel washer)

Fastener description	Shank length in. (mm)	Shank Ø in. (mm)	Washer Ø
Concrete, Masonry and Steel			
X-U P8 S15*	7/8, 1, 1-1/4 (22, 27, 32)	0.157 (4.0)	8 mm plastic and 15 mm steel
X-U P8 S36*	1-1/4, 2-7/8 (32, 72)	0.157 (4.0)	8 mm plastic and 36 mm steel
Concrete and Masonry			
X-C P8 S23	1 to 1-7/8 (27 to 47)	0.138 (3.5)	8 mm plastic and 23 mm steel
X-C P8 S36	1-1/2, 2, 2-1/2 (37, 52, 62)	0.138 (3.5)	8 mm plastic and 36 mm steel

SAE 316 stainless steel non-collated (with and without pre-mounted steel washer)

Fastener description	Shank length in. (mm)	Shank Ø in. (mm)	Washer Ø
Concrete and Masonry			
X-CR P8	1/2 to 1-9/16 (14 to 39)	0.145 (3.7)	8 mm plastic
X-CR P8	1-3/4, 2-1/8 (44, 54)	0.157 (4.0)	8 mm plastic
X-CR P8 S12	1-9/16 (39)	0.145 (3.7)	8 mm plastic and 12 mm steel
X-CR P8 S12	1-3/4 (44)	0.157 (4.0)	8 mm plastic and 12 mm steel
Steel			
X-R P8	9/16 (14)	0.145 (3.7)	8 mm plastic
X-CR S12	5/8 (16)	0.145 (3.7)	12 mm steel

Carbon steel removable and clip fasteners

Fastener description	Shank length in. (mm)	Shank Ø in. (mm)	Washer Ø
Forming Nail			
X-CT 47MX, X-CT 62 MX, X-CT 62 DP8	1-7/8, 2-7/16 (47, 62)	0.145 (3.7)	Double 8 mm plastic
Rebar Basket Clip			
BC X-C P8T	1-7/8, 2-7/16 (47, 62)	0.145 (3.5)	8 mm plastic & rebar basket clip

* More details about the innovative X-U fastener can be found in Section 3.2.6.

ANGLE CLIP IN CONCRETE

PART NUMBER SERIES	SHANK DIAMETER (INCH)	MINIMUM PENETRATION (INCH)	ALLOWABLE WORKING VALUES INSTALLED IN NORMAL WEIGHT CONCRETE					
			ALLOWABLE LOAD - <i>Ultimate Load</i>					
			4000 PSI			6000 PSI		
			TENSION (LBS)	SHEAR (LBS)	OBLIQUE (LBS)	TENSION (LBS)	SHEAR (LBS)	OBLIQUE (LBS)
SDC100 SDC125	0.145	7/8	115 <i>575</i>	120 <i>1014</i>	145 <i>726</i>
SDC125	0.145	1-1/8	130 <i>744</i>	167 <i>1090</i>	205 <i>1032</i>
SPC78	0.150	3/4	155 <i>897</i>	188 <i>1050</i>	150 <i>788</i>	153 <i>949</i>	140 <i>769</i>
SPC114	.150/.180	1-1/8	127 <i>811</i>	226 <i>1130</i>	181 <i>904</i>	169 <i>853</i>	300 <i>1500</i>	223 <i>1114</i>

PART NUMBER SERIES	SHANK DIAMETER (INCH)	MINIMUM PENETRATION (INCH)	ALLOWABLE WORKING VALUES INSTALLED IN 3000 PSI LIGHTWEIGHT CONCRETE				
			ALLOWABLE LOAD - <i>Ultimate Load</i>				
			3000 PSI LIGHTWEIGHT WITH METAL DECKING				
			LOWER FLUTE TENSION (LBS)	LOWER FLUTE SHEAR (LBS)	LOWER FLUTE OBLIQUE (LBS)	UPPER FLUTE TENSION (LBS)	UPPER FLUTE SHEAR (LBS)
SDC100 SDC125	0.145	7/8	67 <i>335</i>	237 <i>1186</i>	90 <i>448</i>	104 <i>571</i>	310 <i>1678</i>
SDC125	0.145	1-1/8	94 <i>471</i>	276 <i>1378</i>	119 <i>596</i>	106 <i>528</i>	319 <i>1597</i>
SPC78	0.150	3/4	59 <i>293</i>	202 <i>1109</i>	65 <i>323</i>	84 <i>419</i>	324 <i>1622</i>
SPC114	.150/.180	1-1/8	157 <i>786</i>	272 <i>1358</i>	153 <i>766</i>	180 <i>899</i>	334 <i>1673</i>

Note 1: ALLOWABLE loads are shown in the **LARGE BOLD** font, *Ultimate* loads are shown in *smaller italic* font. **Note 2:** Testing conducted in accordance with ICC AC70 & ASTM E1190. **Note 3:** Safety factors are based on coefficient of variation. In accordance with ICC AC70, the safety factor will be no less than 5. **Note 4:** Values shown in concrete are for the clip assembly only. Connected members must be investigated separately. **Note 5:** Cyclic, fatigue, shock loads, and other design criteria may require a different safety factor. **Note 6:** Job site testing may be required to determine actual job site values. **Note 7:** Minimum edge distance is 3 inches unless otherwise approved. **Note 8:** For SI: 1 lbf = 4.448 N, 1 inch = 25.4 mm, 1 ksi = 6.89MPa. **Note 9:** Metal deck is 20g.

LADD 652 ANGLE CLIP ASSEMBLY

PART NUMBER SERIES	SHANK DIAMETER (INCH)	MINIMUM PENETRATION (INCH)	ALLOWABLE WORKING VALUES INSTALLED IN STONE AGGREGATE CONCRETE			
			CONCRETE COMPRESSIVE STRENGTH			
			ALLOWABLE LOAD - <i>Ultimate Load</i>			
			3000 PSI		4000 PSI	
			TENSION (LBS)	SHEAR (LBS)	TENSION (LBS)	SHEAR (LBS)
LADD CEILING SYSTEM	0.152	1-1/8	211 <i>1688</i>	193 <i>1544</i>

Note 1: ALLOWABLE loads are shown in the **LARGE BOLD** font, *Ultimate* loads are shown in *smaller italic* font. **Note 2:** Except as noted, values shown reflect an 8 to 1 safety factor. **Note 3:** Values shown are for concrete at the designed strength and are for the clip system only. **Note 4:** Cyclic, fatigue or shock loads and other design criteria may require a different safety factor. **Note 5:** Job site testing may be required to determine actual job site values. **Note 6:** Edge distance is 3 inches unless otherwise approved. **Note 7:** For SI: 1 lbf = 4.448 N, 1 inch = 25.4 mm, 1 ksi = 6.89MPa

A

B

C

2.4 Accessory Materials (Fasteners)

REV

DESCRIPTION

DATE

APPROVAL

FRONT VIEW

SIDE VIEW

0.5"

2"

3/16" HOLE

0.75"

1/4" - 14BSD



ESR-3135



Notes: I-LAG™ Brand eye lag screw part # 750SD, Self-drilling screw designed specifically for suspended ceiling applications only. ICC ESR-3135, distributed by Doc's Industries, Inc. Simi Valley, CA 93063 (For tension applications only)

Material	CHQ 1022 STEEL
Finish	Electro-Galvanized Yellow Zinc Cr3+

Release Approval:

Release Date:

Customer Approval:

Tolerances:

.X = + / - 0.02in
 .XX = + / - 0.01in
 .XXX = + / - .005in
 Unless Otherwise Specified

Proprietary Rights:
 All information that is contained within is proprietary. Not for unauthorized use or disclosure.



DOC'S INDUSTRIES, INC.

Title:

I-LAG™ 750SD

Size:

A

Scale:

None

Part Number:

750SD

Rev:

Date: 8/28/13

Drawn by: RO

Drawing Number: 0176

Sheet 1 of X

A

B

C

D



Structural Design Calculations COSTCO Garage

Interior / Exterior Suspended Ceiling

Issaquah, Washington

Prepared For: PCI
Project No.: 20-086
Date: February 16, 2021

Table of Contents
Structural Design Calculations
for
Interior / Exterior Suspended Ceiling
Issaquah, Washington

Devco Job # 20-086
February 16, 2021

Subject	Page
Loads	1-2
Hanger Splay Wires	3
Hanger Connections	4-8
Splay Connection	9-12
Compression Post	13-14
Trapeze Exterior	15-16
Trapeze Anchor	17-19



ENGINEERS NORTHWEST, INC. is not responsible
for this design or performance of this product.

ENGINEERS NORTHWEST, INC. has reviewed the
applied loads only for conformance to the construction
documents and has reviewed absolutely nothing else

02-25-2021

Date

CAR

By

COSTCO

WIND LOAD - ASCE 7-10

110 mph, Exposure B, Mean Roof Height = 105.0 ft

K_{zt} at Base = 1

$K_d = 0.85$, Roof Slope 0.0 degrees

Enclosed Building, $GC_{pi} = 0.18$

(Wind Loads Shown are for Alternate Basic Load Combinations Using Allowable Stress Design and are Multiplied by a Factor of 0.6 to convert to ASD)

WALL COMPONENTS AND CLADDING per ASCE7-10 Figure 30.6-1

		<u>GCp by Zone</u>							
		Zone 4 (+/-)	Zone 5 (+/-)						
20 ft ²		0.90/-0.90	0.90/-1.80						
500 ft ²		0.60/-0.70	0.60/-1.00						
				<u>Wind Pressures (psf) by Zone ()</u>					
Height				Windward (4,5)		Leeward (4)		Leeward (5)	
z (ft)	K_z	K_{zt}	q_z (psf)	A=20	A=500	A=20	A=500	A=20	A=500
105	1.00	1.00	26.38	17.1	12.3	-17.1	-13.9	-31.3	-18.7

PROJECT: COSTCO

PROJECT NO: 20-086

DESIGN: B.J.P.

DATE: 10/2020

Seismic Design Values

Per ASCE 7

Seismic Properties

Risk Category =	II	
Design Spectral Acceleration	SDS = 0.634	Per Structural General Note Sheet
Amplification Factor	ap = 1.0	
Response Modification Factor	Rp = 2.5	
Importance Factor	I = 1.00	
Design Ceiling Weight Min	W = 4.0	psf Minimum per ASCE7 13.5.6.1
Design Height	Z = 1.0	ft
Bldg Height	H = 1.0	ft

Seismic Design Force

$$\text{Seismic Design Force } F_p = \frac{0.4 * a_p * SDS * W}{\left(\frac{R_p}{I_p} \right)} \left(1 + \frac{2 * Z}{H} \right)$$

$$\text{Maximum Design Force } F_{pmax} = 1.6 * SDS * I_p * W$$

$$\text{Minimum Design Force } F_{pmin} = .3 * SDS * I_p * W$$

$$\begin{aligned} F_p &= 0.30 \quad \times \text{Weight} \\ F_{pmax} &= 1.01 \quad \times \text{Weight} \\ F_{pmin} &= 0.19 \quad \times \text{Weight} \end{aligned}$$

$$\text{Seismic Design Value ASD } F_p = 0.22 \quad \times \text{Weight}$$

PROJECT: COSTCO

PROJECT NO: 20-086

DESIGN: B.J.P.

DATE: 10/2020

Suspended Ceiling Design

Per IBC

Seismic Properties

 Seismic Response Coefficient $C_s =$ 0.22

Ceiling Properties

 Ceiling Weight $W =$ 4.0 psf

 in Ceiling Weight "Seismic Calc" $W =$ 4.0 psf per ASCE7-10 13.5.6.1

 Main Tee Spacing $S_m =$ 4.0 ft

 Cross Tee Spacing $S_c =$ 2.0 ft

Splay Wire

 Splay Wire Angle 45 degrees

 Splay Wire Gauge 12GA
 $T_a =$ 209 lb

 Max Splay Wire Tributary Area 168 ft²

Wire Hanger

 Wire Spacing Along Mains 4.0 ft

 Wire Hanger Gauge 12GA
 $T_a =$ 209 lb

 $T_{max} =$ 64 lb

OK

PROJECT: COSTCO

PROJECT NO: 20-086

DESIGN: B.J.P.

DATE: 10/2020

HANGER WIRE CONNECTIONS

DESIGN LOADS

$T_{max} = 4\text{PSF} \times 4\text{ft} \times 4\text{ft} = 64\text{lb}$ (INTERIOR)

$T_{max} = (4\text{PSF} + 17.1\text{PSF}) \times 2\text{ft} \times 1.5\text{ft} = 64\text{lb}$ (EXTERIOR)

CONCRETE OVER METAL DECK


HILTI X-CX ALH32 per ICC ESR 2184

$T_a = 150\text{lb} > T_{max}$

RAMSET SPC 114 per ICC ESR 1799

$T_a = 157\text{lb} > T_{max}$

USE HILTI X-CX ALH32 OR RAMSET SPC 114




ROOF METAL DECK

ILAG 750SD ICC ESR 3135

$T_a = 82\text{lb} > T_{max}$

USE I LAG 750SD @ MIN 20GA ROOF DECK



CONCRETE P.T. SLAB ($F_c' = 4\text{KSI MIN}$)

HILTI X-CX ALH27 per ICC ESR 2184

$T_a = 110\text{lb} > T_{max}$

RAMSET SPC 78 per ICC ESR 1799

$T_a = 150\text{lb} > T_{max}$

USE HILTI X-CX ALH27 OR RAMSET SPC 78

TABLE 9—ALLOWABLE TENSION AND SHEAR VALUES FOR CEILING CLIP ASSEMBLIES
INSTALLED IN MINIMUM 3000 psi SAND-LIGHTWEIGHT CONCRETE FILLED STEEL DECK PANEL ^{1,2,3}


PART NUMBER	NOMINAL SHANK DIAMETER (inch)	MINIMUM EMBEDMENT DEPTH (inches)	MINIMUM SPACING (inches)	ALLOWABLE LOADS (lbf)			
				Lower Flute Tension	Lower Flute Shear	Upper Flute Tension	Upper Flute Shear
SDC100	0.145	7/8	4	67	237	104	310
SDC125	0.145	1 1/8	4	94	276	106	319
SPC78	0.150	7/8	4	59	202	84	324
SPC114	0.150/0.180	1 1/8	4	157	272	180	334
TEC100	0.157	7/8	5.1	88	—	—	—

For SI: 1 inch = 25.4 mm, 1 lbf = 4.45 N, 1 psi = 6.89 kPa.

¹The fasteners must not be driven until the concrete has reached the designated minimum compressive strength. Minimum concrete thickness above the deck must be a minimum of 3 1/2 inches (2 1/4 inches for TEC fasteners).

²For fasteners installed through steel deck, the fastener must be installed through and into the upper or lower flute of the deck with a minimum edge distance of 1 1/8 inches from the edge of the steel deck and 4 inches (5.1 inches for TE fasteners) from the end of the deck panel.

³The steel deck panel must be configured as shown in Figure 1 and have a minimum base-metal thickness of 0.035 inch and minimum yield strength of 50 ksi and a minimum tensile strength of 65 ksi.



For SI: 1 inch = 25.4 mm.

See Tables 4 and 9.

t = 3 1/2" for 1500 and SP Series Fasteners (See Table 4)

t = 3 1/2" for SDC100, SDC125, SPC78, and SPC114 (See Table 9)

t = 2 1/4" for TE Series Fasteners (See Tables 4 and 9)

FIGURE 1—FASTENER INSTALLATION LOCATION IN SAND-LIGHTWEIGHT CONCRETE FILLED 3 INCH DEEP STEEL DECK

TABLE 6—ALLOWABLE LOADS FOR FASTENERS INSTALLED IN ASTM A572 GRADE 50 OR ASTM A992 STEEL¹ (lbf)

PART NUMBER SERIES	NOMINAL SHANK DIAMETER (inch)	TYPE OF SHANK	MINIMUM SPACING (inch)	MINIMUM EDGE DISTANCE (inch)	ALLOWABLE LOADS (lbf)									
					Steel Thickness (inch):		³ / ₁₆		¹ / ₄		³ / ₈		¹ / ₂	
Load Direction:					Tension ⁴	Shear	Tension ⁴	Shear	Tension	Shear	Tension	Shear	Tension	Shear
1500K (excluding 1506B)	0.145	Knurled	1	¹ / ₂	260	499	579	725	383 ²	595 ²	—	—	—	—
SP	0.150	Smooth	1	¹ / ₂	356	569	554	637	604 ⁴	602	814 ³	820 ³	243 ⁴	381 ⁴
TE	0.157	Knurled	1	¹ / ₂	442	676	630	662	760 ⁴	725	582 ⁴	532	311 ²	467 ²

For SI: 1 inch = 25.4 mm, 1 lbf = 4.45 N.

¹Except where noted otherwise in this table, the allowable load values shown are for fastenings that have the entire pointed end of the fasteners driven through the steel plate.

²Fastener penetration into the steel must be a minimum of ³/₈ inch.

³Fastener penetration into the steel must be a minimum of ¹/₂ inch.

⁴Fastener penetration into the steel must be a minimum of ⁷/₁₆ inch.

⁵For steel-to-steel connections designed in accordance with Section 4.1.4, the tabulated allowable load may be increased by a factor of 1.25, and the design strength may be taken as the tabulated allowable load multiplied by a factor of 2.0.

TABLE 7—ALLOWABLE LOADS FOR FASTENERS DRIVEN INTO CONCRETE MASONRY UNITS^{1,2}

PART NUMBER SERIES	SHANK DIAMETER (inch)	MINIMUM EMBEDMENT (inch)	ALLOWABLE LOADS (lbf)											
			Masonry Type:				Fastener Location:							
			HOLLOW UNGROUTED CMU				GROUT-FILLED CMU							
			Face Shell ³		Mortar Joint ⁴		Face Shell ³		Mortar Joint ⁴		Top of Grouted Cell ^{3,6}			
Load Direction:			Tension	Shear ⁷	Tension	Shear ⁵	Tension	Shear ⁷	Tension	Shear ⁵	Tension	Shear ⁷		
TE	0.157	1	33	100	42	68	139	145	91	127	165	171		

For SI: 1 inch = 25.4 mm, 1 lbf = 4.4 N.

¹See Section 3.6.4 for CMU, mortar and grout requirements.

²Fasteners must be installed a minimum of 5.1 inches from the end of the wall.

³Fasteners must be installed at the center of the CMU cell. No more than one fastener may be installed in an individual CMU cell.

⁴Applicable to fasteners installed in the horizontal mortar joint (bed joint). Minimum fastener spacing must be 5.1 inches.

⁵Allowable shear load value applies to load applied perpendicular to the mortar joint.

⁶Fastener must be installed vertically at the top, center of grouted cell.

⁷Shear load can be in any direction perpendicular to the axis of the fastener.

TABLE 8—ALLOWABLE TENSION AND SHEAR VALUES FOR CEILING CLIP ASSEMBLIES INSTALLED IN NORMALWEIGHT CONCRETE¹

PART NUMBER	NOMINAL SHANK DIAMETER (inch)	MINIMUM EMBEDMENT DEPTH (inches)	MINIMUM SPACING (inches)	MINIMUM EDGE DISTANCE (inches)	ALLOWABLE LOADS (lbf)			
					Concrete Compressive Strength:		4000 psi	
Load Direction:					Tension	Shear	Tension	Shear
SDC100	0.145	7/8	4	3.2	115	120	—	—
SDC125	0.145	1 1/8	4	3.2	130	167	—	—
SPC78	0.150	3/4	5.1	3.2	155	188	150	153
SPC114	0.150/0.180	1 1/8	5	3.5	127	226	169	300
TEC100	0.157	7/8	5.1	3.5	207	—	—	—

For SI: 1 inch = 25.4 mm, 1 lbf = 4.45 N, 1 psi = 6.89 kPa.

¹The fasteners must not be driven until the concrete has reached the designated minimum compressive strength. Minimum concrete thickness must be three times the fastener embedment into the concrete.

TABLE 1—HILTI CEILING CLIP ASSEMBLY TYPES

DESIGNATION	FASTENER SHANK DIAMETER (inch)	FASTENER SHANK LENGTH (inch)	EMBEDMENT OF FASTENER IN CONCRETE (inch)	APPLICABLE BASE MATERIAL	APPLICABLE LOAD TABLES
X-CX ALH22	0.177	0.866	$\frac{3}{4}$	Concrete Conc.-filled deck Steel	2, 3, 4
X-CX ALH27	0.177	1.063	$\frac{7}{8}$	Concrete Conc.-filled deck	2, 3
X-CX ALH32	0.177	1.260	1	Concrete Conc.-filled deck	2, 3
X-CX C27	0.138	1.063	$\frac{7}{8}$	Concrete Conc.-filled deck	2, 3

For SI: 1 Inch = 25.4 mm.

TABLE 2—ALLOWABLE LOADS FOR HILTI CEILING CLIP ASSEMBLIES
INSTALLED IN NORMALWEIGHT CONCRETE^{1,2}

DESIGNATION	ALLOWABLE LOADS (lbf)					
Concrete Compressive Strength:	4,000 psi			6,000 psi		
Load Direction:	Tension	Shear	45-Degree	Tension	Shear	45-Degree
X-CX ALH22	90	—	125	90	—	125
X-CX ALH27	125	—	165	110	—	150
X-CX ALH32	160	—	210	145	—	200
X-CX C27	90	—	125	—	—	—

For SI: 1 inch = 25.4 mm; 1 lbf = 4.448 N; 1 psi = 6895 Pa.

¹ Allowable load values are for assemblies installed in concrete having the designated compressive strength at the time of installation.² The concrete thickness at the point of penetration must be a minimum of three times the fastener embedment depth.TABLE 3—ALLOWABLE LOADS FOR HILTI CEILING CLIP ASSEMBLIES INSTALLED INTO MINIMUM 3,000 psi STRUCTURAL SAND-LIGHTWEIGHT CONCRETE FILLED COMPOSITE STEEL DECK PANEL^{1,2}

DESIGNATION	ALLOWABLE LOAD (lbf)					
Fastener Location:	Lower Flute			Upper Flute		
Load Direction:	Tension	Shear	45-Degree	Tension	Shear	45-Degree
X-CX ALH22 ³	90	—	110	110	—	110
X-CX ALH27 ³	120	—	125	150	—	130
X-CX ALH32 ³	150	—	145	190	—	160
X-CX C27 ⁴	80	—	110	110	—	110

For SI: 1 inch = 25.4 mm; 1 lbf = 4.448 N; 1 psi = 6895 Pa, 1 ksi = 6.895 MPa.

¹ Allowable load values are for assemblies installed in concrete having the designated compressive strength at the time of installation.² Deck panel must be 3-inch deep composite floor deck and have a minimum 0.0358 inch base-metal thickness, a minimum yield strength of 40 ksi and a minimum tensile strength of 55 ksi. See Figure 2 for deck configuration and required concrete topping thickness.³ Fasteners must be installed with a minimum of 3.5 inches from the end of the deck, and a minimum spacing of 5 inches.⁴ Fasteners must be installed with a minimum of 3 inches from the end of the deck, and a minimum spacing of 4 inches.TABLE 4—ALLOWABLE LOADS FOR HILTI CEILING CLIP ASSEMBLIES INSTALLED IN STEEL^{1,2}

DESIGNATION	ALLOWABLE LOADS (lbf)								
Steel Thickness (inch):	$\frac{1}{4}$			$\frac{3}{8}$			$\frac{1}{2}$		
Load Direction:	Tension	Shear	45-Degree	Tension	Shear	45-Degree	Tension	Shear	45-Degree
X-CX ALH22	270	—	270	270	—	270	270	—	270

For SI: 1 inch = 25.4 mm, 1 lbf = 4.448 N.

¹ Steel must comply with Section 3.2.3 of this report.² Allowable load capacities are based on base steel with a minimum yield strength (F_y) of 36 ksi and a minimum tensile strength (F_u) of 58 ksi.

- 5.1 The fasteners are manufactured and identified in accordance with this report.
- 5.2 Fastener installation complies with this report and the manufacturer's published installation instructions. In the event of conflict between this report and the published instructions, this report governs.
- 5.3 Available tension loads are as noted in Table 3. The stress increases and load reductions described in Section 1605.3.2 of the IBC are not allowed. No adjustments for duration of load are allowed.
- 5.4 Use of the screws to attach bracing wire to the supports is outside the scope of this report.
- 5.5 The allowable loads noted in Section 4.1 apply to the fasteners and their connection to the steel only. Adequacy of the steel deck to support the suspended loads must be justified to the satisfaction of the code official.
- 5.6 Calculations demonstrating that the applied loads are less than the allowable loads described in this report must be submitted to the code official for approval. The calculations must be prepared by a registered design professional where required by the statutes of the jurisdiction in which the project is to be constructed.
- 5.7 Use of the fasteners is limited to dry, interior locations.
- 5.8 The fasteners are manufactured under a quality control program with inspections by ICC-ES.
- 6.0 EVIDENCE SUBMITTED**
- Data in accordance with the ICC-ES Acceptance Criteria for Self-drilling Tapping Screws Used to Attach Miscellaneous Building Materials to Steel Base Material (AC500), dated December 2017.
- 7.0 IDENTIFICATION**
- 7.1 The I-Lag Brand screws are embossed with four I's radiating from the shank on the top portion of the collar as shown in Figure 1. The packaging is labeled with the fastener type, part number, report holder name (Doc's Industries, Inc.) and evaluation report number (ESR-3135).
- 7.2 The report holder contact information is the following:
- DOC'S INDUSTRIES, INC.**
4121 GUARDIAN STREET
SIMI VALLEY, CALIFORNIA 93063
(805) 583-9911
www.docindustries.com

TABLE 1—I-LAG BRAND EYE LAG SCREWS

FASTENER TYPE	NOMINAL FASTENER SIZE (dia-tpi)	NOMINAL DIAMETER (in.)	LENGTH FROM UNDERSIDE OF COLLAR TO TIP (in.)	FASTENER "HEAD" LENGTH ¹ (in.)	EYE DIAMETER (in.)	COLLAR DIAMETER AND THICKNESS (in.)
750 SD	¹ / ₄ -14	0.250	³ / ₄	1 ¹ / ₄	0.18	0.5 by 0.07
175 SD	¹ / ₄ -14	0.250	1 ¹⁵ / ₁₆	1 ¹ / ₄	0.18	0.5 by 0.07

For SI: 1 inch = 25.4 mm.

¹Length from the underside of the collar to edge of the driving end of the fastener.

TABLE 2 — I-LAG™ BRAND EYE LAG SCREW FASTENER SHEAR AND TENSION STRENGTHS (lbf)

FASTENER TYPE	NOMINAL FASTENER SIZE	NOMINAL STRENGTH		ALLOWABLE STRENGTH (ASD)		DESIGN STRENGTH (LRFD)	
		Tension, P _{ts}	Shear, P _{ss}	Tension, (P _{ts} /Ω)	Shear, (P _{ss} /Ω)	Tension, (ΦP _{ts})	Shear, (ΦP _{ss})
750SD	¹ / ₄ -14	1560	2527	520	872	780	1263
175SD	¹ / ₄ -14	1560	2527	520	842	780	1263

For SI: 1 inch = 25.4 mm, 1 lbf = 4.4 N.

TABLE 3 —AVAILABLE TENSION LOADS FOR I-LAG™ BRAND EYE LAG SCREWS INSTALLED IN STEEL DECK PANELS (lbf)^{1,2}

FASTENER TYPE	MINIMUM DESIGN BASE METAL THICKNESS (inch)			
	0.030	0.036	0.047	0.062
ALLOWABLE STRENGTH (ASD)				
750 SD 175 SD	82	125	176	229
DESIGN STRENGTH (LRFD)				
750 SD 175 SD	131	201	281	366


For SI: 1 inch = 25.4 mm, 1 lbf = 4.4 N, 1 ksi = 6.895 MPa.

¹The tabulated allowable load values are for the screws only, based on fastener strength and pullout capacity. Ceiling wire capacity is outside the scope of this report. Deck capacity is also outside the scope of this report.

²Values are based on installation into steel having a minimum tensile strength, F_u , of 45 ksi.

PROJECT: COSTCO
PROJECT NO: 20-086
DESIGN: B.J.P.
DATE: 10/2020
SPLAY WIRE CONNECTIONS
DESIGN LOADS

$$R_x = R_y = C_s W = 0.22 \times 12\text{ft} \times 12\text{ft} \times 4\text{psf} = 126\text{lb}$$



Devco Engineering

10/20/2020

Hilti KH-EZ in Underside of Metal Deck

Deck Profile: **W2** (ESR-3027 Figure 5)
 KH-EZ Size: **$\frac{3}{8}$ " x 2 $\frac{1}{2}$ "**
 Seismic Load: **Yes**
 Concrete Strength f'_c : **3000** psi
 Minimum Spacing: **7.50"** along flute

ANCHOR @ CONCRETE OVER METAL DECK

$$T = 126\text{lb} \times 1.5\text{in} / 0.75\text{in} = 253\text{lb} \text{ (seismic ASD)}$$

$$V = 126\text{lb} \text{ (seismic ASD)}$$

USE 3/8" Dia x 2 1/2" Hilti KH-EZ

ASD Load (lb):
 LRFD Factor(s):
 Factored Load (lb):

Tension	Shear
253	126
1.40	1.40
354	176

Nominal Strength (lb)
 Reduction Factor ϕ
 Seismic Reduction Factor
 Conversion Factor α
 Allowable Strength (lb)

Tension	Shear
1590	905
0.65	0.60
0.75	1.00
1.40	1.40
554	388

[ESR-3027](#)

Interaction	0.78 OK
-------------	----------------

ANCHOR @ P.T CONCRETE SLAB

$$T_u = 1.4 \times 126\text{lb} \times 1.5\text{in} / 0.75\text{in} = 354\text{lb} \text{ (seismic LRFD)}$$

$$V = 1.4 \times 126\text{lb} = 176\text{lb} \text{ (seismic LRFD)}$$

USE (3) 3/8" Diameter HDI-P-TZ

www.hilti.com

Company:

Address:

Phone | Fax:

Design:

Fastening point:

Concrete - Jan 20, 2021

Page:

Specifier:

E-Mail:

Date:

1

1/20/2021

Specifier's comments:

1 Input data


Anchor type and diameter:
HDI-P TZ 3/8

Item number:

not available

Effective embedment depth:

 $h_{ef} = 0.750 \text{ in.}$, $h_{nom} = 0.750 \text{ in.}$

Material:

ASTM A 36

Evaluation Service Report:

ESR-4236

Issued | Valid:

4/1/2020 | 7/1/2021

Proof:

Design Method ACI 318 / AC193

Stand-off installation:

 $e_b = 0.000 \text{ in.}$ (no stand-off); $t = 0.500 \text{ in.}$

Anchor plate^R:

 $l_x \times l_y \times t = 12.000 \text{ in.} \times 4.000 \text{ in.} \times 0.500 \text{ in.}$; (Recommended plate thickness: not calculated)

Profile:

Round bars (AISC), 1/16; (L x W x T) = 0.062 in. x 0.062 in.

Base material:

cracked concrete, 2500, $f'_c = 2,500 \text{ psi}$; $h = 6.000 \text{ in.}$

Reinforcement:


tension: condition B, shear: condition B; no supplemental splitting reinforcement present

edge reinforcement: none or < No. 4 bar

Seismic loads (cat. C, D, E, or F)

yes (D.3.3.5)

^R - The anchor calculation is based on a rigid anchor plate assumption.

Geometry [in.] & Loading [lb, in.lb]




www.hilti.com

Company:		Page:	2
Address:		Specifier:	
Phone Fax:		E-Mail:	
Design:	Concrete - Jan 20, 2021	Date:	1/20/2021
Fastening point:			

1.1 Design results

Case	Description	Forces [lb] / Moments [in.lb]	Seismic	Max. Util. Anchor [%]
1	Combination 1	N = 354; V _x = 176; V _y = 0; M _x = 0; M _y = 0; M _z = 0;	yes	85

www.hilti.com

Company:		Page:	3
Address:		Specifier:	
Phone Fax:		E-Mail:	
Design:	Concrete - Jan 20, 2021	Date:	1/20/2021
Fastening point:			

2 Proof I Utilization (Governing Cases)

Loading	Proof	Design values [lb]		Utilization	
		Load	Capacity	β_N / β_V [%]	Status
Tension	Pullout Strength	118	139	85 / -	OK
Shear	Pryout Strength	176	870	- / 21	OK

Loading	β_N	β_V	ζ	Utilization $\beta_{N,V}$ [%]	Status
Combined tension and shear loads	0.846	0.202	5/3	83	OK

3 Warnings

- Please consider all details and hints/warnings given in the detailed report!


Fastening meets the design criteria!



SECTION DESIGNATION: 162S125-30 [33] Single

Section Dimensions:

Web Height = 1.625 in
Top Flange = 1.250 in
Bottom Flange = 1.250 in
Stiffening Lip = 0.188 in
Inside Corner Radius = 0.0782 in
Punchout Width = 0.750 in
Punchout Length = 4.000 in
Design Thickness = 0.0312 in



Steel Properties:

Fy = 33.000 ksi
Fu = 45.000 ksi
Fya = 33.000 ksi

ALLOWABLE AXIAL LOADS

INPUT PARAMETERS

Overall Stud Length = 8 ft
Load has not been modified for load type or duration
Member Configuration: SINGLE MEMBER

K-phi (axial) for Distortional Buckling = 0.00 lb*in/in

TOTAL ALLOWABLE AXIAL LOADS (lb)

WEAK AXIS BRACING	MAXIMUM KL/r	CONCENTRIC LOADING	LOADED THROUGH WEB
NONE	218	186	151
MID Pt	141	358	266
THIRD Pt	141	504	341


COMPRESSION POST
C = 126LB < 151LB OK



SECTION DESIGNATION: 162T125-30 [33] Single

Section Dimensions:

Web Height = 1.766 in
Top Flange = 1.250 in
Bottom Flange = 1.250 in
Inside Corner Radius = 0.0782 in
Design Thickness = 0.0312 in



Steel Properties:

Fy = 33.000 ksi
Fu = 45.000 ksi
Fya = 33.000 ksi

ALLOWABLE AXIAL LOADS

INPUT PARAMETERS

Overall Stud Length = 8 ft
Load has not been modified for load type or duration
Member Configuration: SINGLE MEMBER

TOTAL ALLOWABLE AXIAL LOADS (lb)

<u>WEAK AXIS BRACING</u>	<u>MAXIMUM KL/r</u>	<u>CONCENTRIC LOADING</u>	<u>LOADED THROUGH WEB</u>
NONE	235	242	155
MID Pt	131	426	272
THIRD Pt	131	579	357


COMPRESSION POST
C = 126LB < 155LB OK



2012 NASPEC [AISI S100-2012]

Project: Costco
Model: Trapeze

Date: 2/16/2021



Section : (2) 162S162-33 Back-to-Back C Stud (X-X Axis)
Maxo = 335.4 Ft-Lb **Moment of Inertia, I =** 0.177 in⁴

Fy = 33.0 ksi
Va = 1201.4 lb

Loads have not been modified for strength checks
Loads have not been modified for deflection calculations

Flexural and Deflection Check

Span	Mmax Ft-Lb	Mmax/ Maxo	Mpos Ft-Lb	Bracing (in)	Ma(Brc) Ft-Lb	Mpos/ Ma(Brc)	Deflection (in)	Ratio
Center Span	141.8	0.423	141.8	None	335.4	0.423	0.099	L/545

Distortional Buckling Check

Span	K-phi lb-in/in	Lm Brac (in)	Ma-d Ft-Lb	Mmax/ Ma-d
Center Span	0.00	54.0	358.4	0.396

Combined Bending and Web Crippling

Reaction or Pt Load	Load P(lb)	Brng (in)	Pa (lb)	Pn (lb)	Mmax (Ft-Lb)	Intr. Value	Stiffen Req'd ?
R1	126.0	1.00	778.8	1557.6	0.0	0.07	No
R2	126.0	1.00	778.8	1557.6	0.0	0.07	No

Combined Bending and Shear


Reaction or Pt Load	Vmax (lb)	Mmax (Ft-Lb)	Va Factor	V/Va	M/Ma	V + M Intr.
R1	126.0	0.0	1.00	0.10	0.00	0.10
R2	126.0	0.0	1.00	0.10	0.00	0.10



2012 NASPEC [AISI S100-2012]

Project: Costco
Model: Trapeze

Date: 2/16/2021



Section : (2) 362S162-33 Back-to-Back C Stud (X-X Axis)
Maxo = 881.7 Ft-Lb **Moment of Inertia, I** = 1.102 in⁴

Fy = 33.0 ksi
Va = 2047.2 lb

Loads have not been modified for strength checks
Loads have not been modified for deflection calculations

Flexural and Deflection Check

Span	Mmax Ft-Lb	Mmax/ Maxo	Mpos Ft-Lb	Bracing (in)	Ma(Brc) Ft-Lb	Mpos/ Ma(Brc)	Deflection (in)	Ratio
Center Span	448.0	0.508	448.0	None	774.9	0.578	0.159	L/605

Distortional Buckling Check

Span	K-phi lb-in/in	Lm Brac (in)	Ma-d Ft-Lb	Mmax/ Ma-d
Center Span	0.00	96.0	904.8	0.495

Combined Bending and Web Crippling

Reaction or Pt Load	Load P(lb)	Brng (in)	Pa (lb)	Pn (lb)	Mmax (Ft-Lb)	Intr. Value	Stiffen Req'd ?
R1	224.0	1.00	776.0	1552.0	0.0	0.13	No
R2	224.0	1.00	776.0	1552.0	0.0	0.13	No

Combined Bending and Shear

Reaction or Pt Load	Vmax (lb)	Mmax (Ft-Lb)	Va Factor	V/Va	M/Ma	V + M Intr.
R1	224.0	0.0	1.00	0.11	0.00	0.11
R2	224.0	0.0	1.00	0.11	0.00	0.11

www.hilti.com

Company:
Address:
Phone | Fax: |
Design: Concrete - Feb 16, 2021 (1)
Fastening point:

Page: 1
Specifier:
E-Mail:
Date: 2/16/2021

Specifier's comments:

1 Input data

Anchor type and diameter: HDI-P TZ 3/8

Item number: not available

Effective embedment depth: $h_{ef} = 0.750$ in., $h_{nom} = 0.750$ in.

Material: ASTM A 36

Evaluation Service Report: ESR-4236

Issued | Valid: 4/1/2020 | 7/1/2021

Proof: Design Method ACI 318 / AC193

Stand-off installation: $e_b = 0.000$ in. (no stand-off); $t = 0.500$ in.

Anchor plate^R: $l_x \times l_y \times t = 12.000$ in. \times 3.000 in. \times 0.500 in.; (Recommended plate thickness: not calculated)

Profile: Round bars (AISC), 1/16; (L \times W \times T) = 0.062 in. \times 0.062 in.

Base material: cracked concrete, 4000, $f'_c = 4,000$ psi; $h = 6.000$ in.

Reinforcement: tension: condition B, shear: condition B; no supplemental splitting reinforcement present
edge reinforcement: none or \leq No. 4 bar


Seismic loads (cat. C, D, E, or F) no



^R - The anchor calculation is based on a rigid anchor plate assumption.

Geometry [in.] & Loading [lb, in.lb]

$$T_u = (4\text{PSF} \times 2.67\text{FT} \times 8\text{FT}/2 \times 1.2 + 17.1\text{PSF} \times 2.67\text{FT} \times 8\text{FT}/2 \times 1.6) \times 1.5\text{IN} / 0.75\text{IN} = 686\text{LB}$$





www.hilti.com

Company:		Page:	2
Address:		Specifier:	
Phone Fax:		E-Mail:	
Design:	Concrete - Feb 16, 2021 (1)	Date:	2/16/2021
Fastening point:			

1.1 Design results

Case	Description	Forces [lb] / Moments [in.lb]	Seismic	Max. Util. Anchor [%]
1	Combination 1	N = 686; V _x = 0; V _y = 0; M _x = 0; M _y = 0; M _z = 0;	no	78

www.hilti.com

Company:		Page:	3
Address:		Specifier:	
Phone Fax:		E-Mail:	
Design:	Concrete - Feb 16, 2021 (1)	Date:	2/16/2021
Fastening point:			

2 Proof I Utilization (Governing Cases)

Loading	Proof	Design values [lb]		Utilization	Status
		Load	Capacity	β_N / β_V [%]	
Tension	Pullout Strength	171	222	78 / -	OK
Shear	-	-	-	- / -	N/A

Loading	β_N	β_V	ζ	Utilization $\beta_{N,V}$ [%]	Status
Combined tension and shear loads	-	-	-	-	N/A

3 Warnings

- Please consider all details and hints/warnings given in the detailed report!

Fastening meets the design criteria!